

MANAGEMENT OF WORKING AT HEIGHT

2026-04




2

ADMIN & INTRO

3

Z O O M I N G

- **Mace** require your camera to be on
- **Microphones** muted if noisy
- **Temporary un-mute:** <CTRL> & <SPACE BAR>
- **Gallery view** to see everyone
- **Same link** for each day



4

S L I D E D E C K

**Link shared at end
to download
a copy of slides**

5

REFRESHMENTS

Tea & coffee will be provided only at the start of the day.

The coffee machine in reception is for use by for external visitors only.

Please use the canteen on the 1st floor for your beverages, or external shops.

8

YOUR TRAINER



John Hynes

BEng(Hons) MSc(Eng)

30 years in Construction:

**Design, Site Management, Fixing Technology,
Remedials, Nuclear & Petrochem**

25 years Work at Height:

**Design & Installation,
Trade Bodies & Standards**

Family, Sports & Socialising

9

HIGHER SAFETY



AUTUMNAL

Independent & Impartial Height Safety Consultancy

Previously Higher Safety - established by Barney Green - now retired

10

WHAT DO WE DO?

- **Consultancy Service**
 - Project Advice, Design support, Planning, WAH review
- **Business Development**
 - Planning, Processes, Solution Development Support
- **Education & Training**
 - Awareness, Regulations, Best Practice
- **Expert Witness**
 - Advising the court




AUTUMNAL

www.autumnalservices.com

11

EXPERT WITNESS

- **Ensure competence**
- **Justify decisions**
- **Keep good records**



12

WHAT ABOUT YOU?



What are your...

- **roles?**
- **current / recent projects?**
- **experiences?**
- **interests outside of work?**

13

MACE WORKING AT HEIGHT STANDARD

- Overview
- Hazards
- MACE Hierarchy
- MACE Risk Rating
- Tool Tethering Standard
- Exclusion Zones & PPE
- Edge Protection
- Overhead Protection
- Access Equipment
- MEWPs & Low-Level Access Equip't
- Access Towers, Steps & Ladders
- Personal Fall Protection Equip't (PFPE)
- Riser Management
- Floor Horizontal Protection
- Edge Vertical Protection
- Vertical Access Space Protection
- Work at Height Plan

Current version: Construct

CN-HSW-SD-0007 v1.1 (2024?)


revision due by Q3-2026?!

14

FEEDBACK

www.sli.do

Requirement for Mace HSW Team



15

AGENDA

Day 1 (Level 1)

09:00	Introduction
09:30	<u>WaH Regulations & MACE</u>
10:15	<u>MACE WaH Standard</u>
10:45	BREAK
11:00	<u>Tethering, Exclusion Zones, Secondary Systems & Signage</u>
11:30	<u>Edge Protection Standards</u>
12:15	<u>Edge Protection Levels</u>
12:45	LUNCH
13:15	<u>Access Equip Common Management Controls</u>
13:30	<u>Access Scaffold</u>
14:30	BREAK
14:45	<u>MEWPs, PAVs & Peco</u>
15:45	<u>Towers & Podiums</u>
16:30	FINISH

16

AGENDA


Day 2 (Level 1)

09:00	<u>PFPE – Work Restraint & Fall Arrest</u>
10:30	Assessment (Level 1)
11:00	BREAK



Questions:

- 5 admin
- 28 tech



17

AGENDA


Day 2 (Level 2)

- 11:15 Overhead Protection
- 12:00 Void Protection
- 12:15 Mast Climbers (MCWP) & Cradles (TSAE)
- 13:00 **LUNCH**
- 13:30 Delta Decks, Ladders, Steps, Hop-Ups
- 14:00 Rope Access (Abseiling)
- 15:00 **BREAK**
- 15:15 Riser Management
- 15:45 MACE WaH Plan
- 16:15 Feedback & Assessment (Level 2)
- 16:45 **FINISH**



18

ASSESSMENT SCORES



19

THE END

*Thank you
for your
attention & participation...*

20

REGULATIONS & HIERARCHY

21

GENERAL H&S LAW

HSWA (Health & Safety at Work Act)


- **Duties on all employers & employees**
- **Protect SFARP** (So Far As Reasonably Practicable)
- **Enforcement**

RIDDOR (Reporting of Injuries, Diseases & Dangerous Occurrences Regulations)

- **Report 'hospital treated' injuries without delay**
- **Source of data**

22

RIDDOR STATISTICS



In construction, falls account for **52%** of all fatalities

UK HSE RIDDOR Data – November 2025

23

WAHR (WORKING AT HEIGHT REGULATIONS)

- Implemented in 2005
- Nearly lost in Brexit 'sunset' (2023)
- Applies to all work (not just construction)
- Definition of WAH
“Any place from which, if no action were taken, a person could fall a distance likely to cause injury”
- Hierarchy of controls
- Unifies previous regulations on WAH



24

MAIN SECTIONS OF WAHR

- Organization & **planning** (~60% of WAHR convictions)
- **Competency** & training
- **Avoidance** of risks (~30% of WAHR convictions)
- Risks **assessment** & equipment selection
- Identifying **fragile** surfaces
- Controlling falling **objects**
- Identifying danger **areas**
- **Maintenance** & Inspection

25

TERMS

Hazard
(potential cause of harm)

x

Likelihood
(chance of encountering Hazard)

=

Risk
(product of Hazard & Likelihood)



Control Measure
(means of reducing Risk)

26

HIERARCHY OF CONTROLS

S F A R P




Consider

Collective over Personal
Passive over Active
Permanent over Temporary




27

COMBINED HIERARCHY



28

RISK MATRIX





29

AVOID



30

AVOID




31

COLLECTIVE PREVENTION




32

COLLECTIVE PREVENTION



33

PERSONAL PREVENTION




34

COLLECTIVE MINIMISE HEIGHT & CONSEQUENCE




35

PFPE – MITIGATION & PREVENTION



36

PERSONAL MINIMISE CONSEQUENCE



37

PERSONAL FALL ARREST EXAMPLE



- Slow fall
 - Tried to hang-on
 - Little energy absorber deployment
- Long fall
 - Too much slack
 - Just enough clearance
- Swing fall – hit racking to side

38

RECOMMENDED ORDER FOR OPTIONS

Work Equipment	Collective	Personal
Prevents a fall	Edge protection systems Advanced guard rails Work platforms	PFPE (Fall Factor 0 to 1) Pulpit steps Single user MEWPs
Minimise height and consequence	Nets (close) Material nets Soft landing systems	PFPE (Fall Factor 1 to 2)
Minimises Consequence	Net (Low level <6m) Remote soft landing systems	Lifejackets Inflating air suits Injury reduction
Does neither	Hop-ups Trestles Platforms	Ladders Stilts


39

PASSIVE VS ACTIVE



40

PASSIVE VS ACTIVE



41

OTHER WAH HAZARDS




Responsibility?

Falling Equipment
Falling Materials
Falling Debris



42

CONTROL OF MATERIALS AT HEIGHT



Design-Out Risk!!!

43

WHAT IS IT REALLY ALL ABOUT?




44

60 DROPPED ITEM REVIEW

- Lifting & Transport
- Shafts & Risers
- Demolition
- Cladding
- Others

Ask more of the package contractor!



45

MAJOR PROJECT WAH REVIEW

Early consideration

CDM
Asking questions
Tease-out details
How? (e.g. minimise repeat cladding visits)

Ask More!



Set expectations

Demand more of the package contractor.
Check their RAMS and Plan.
Ensure they delivers.



46

SUGGESTED ACTION SUMMARY

- | | |
|---|--------------------------------------|
| 1. Specialist advice early | 10. Demand more from scaffolder. |
| 2. Project/activity specific RAMS | 11. MACE public protection standard. |
| 3. Tough stand on competence | 12. MACE temp cradles (SAEMA). |
| 4. Vertical segregation | 13. Housekeeping. |
| 5. Revised sequence consequences | 14. Chin straps. |
| 6. MACE tethering standard | 15. MACE ramps and levels. |
| 7. Early cladding details. Min bits/visits. | 16. MACE off loading. |
| 8. Specify containment standard. | |
| 9. Consistent EP. MACE shafts & risers. | |
- MACE Working at Height Standard**

47

COMPETENCE



- Scaffolders
- MEWPs
- PASMA
- Slinger
- Banksmen
- Cladders
- Rope Access
- Edge Protection
- Etc.




Ask for More !



48

METHOD STATEMENTS



49

VERTICAL SEGREGATION



**Briefing....
Be vertically alert!**

50

QUESTIONS?



51

WORKING AT HEIGHT STANDARD

52

WORK AT HEIGHT OVERVIEW

- **Largest single cause of significant incident (including within MACE)**
- **WatH Regulations 2005 require “all that is reasonably practicable”**
- **Falling and falling materials review**
- **MACE hierarchy (similar to WAHR)**
- **MACE “risk rating” system**
- **Follow the MACE standards:**
 - **Work at Height Guidelines & Standards**
 - **Riser Standards & Guidance**
 - **Tool Tethering Policy**


**Working at Height
Standard**

CN-HSW-SD-0007 v1.1

53

MACE WORK AT HEIGHT STANDARD

- Applies to **ALL** work at height
- Does **NOT** specify “min height”
- Does **NOT** specify “time”
- Requires task-specific RAMS



54

MACE RISK RATINGS

Best Practice

- First consideration
- Preferred Option

Caution


- Additional Management controls
- In task RAMS
- Justification required (WAH plan)

Alert

- Exceptional Use **ONLY**
- Justification required
- Approval required (BUD/HSL)

55

WORK AT HEIGHT PLANNING PROCESS



56

ROLES AND RESPONSIBILITIES

Roles	Responsibilities
Designers	<ul style="list-style-type: none"> Design work to prevent or minimise WAH activities. Review the risk ratings of this document and design work in-line with best practice rating, wherever possible.
Mace project team	<ul style="list-style-type: none"> Develop project WAH and Riser Strategy and delivery plan. Plan, organise and coordinate WAH activities and work relating to risers. Review and sign off on Safe System of Work (SSOW), including risk assessment and method statement (RAMS). Review work and report on any issues or opportunities for improvement.
Supply chain	<ul style="list-style-type: none"> Develop and work to approved SSOW. Provide adequate resources. Supervise and report on any issues or opportunities for improvement.

WAH coordinator	<ul style="list-style-type: none"> Co-ordinate the development of the WAH plan with the Mace Project team. Confirm compliance with the WAH plan and requirements of this standard. Review the WAH plan and arrange for appropriate sign off. Additional responsibilities are outlined in the Mace safety coordinators.
Scaffold coordinator	<ul style="list-style-type: none"> See Mace approved safety coordinators
Riser coordinator	<ul style="list-style-type: none"> Co-ordinate the development of the Riser Strategy and Delivery plan with the Mace project team. Confirm compliance with the Riser standard and requirements of this standard. Lead the Riser coordination meetings. Review the Riser Strategy and arrange for appropriate sign off. Additional responsibilities are outlined in the Mace safety coordinators.

57

MACE FOUR STEPS...

Going home safe and well

Safe behaviours
Are you, and everyone around you, behaving in a safe manner and making safe decisions?

Safe systems
Are there safe systems of work in place for you, and your colleagues?

Safe workplace
Are you, and your colleagues, in a safe and supportive working environment?

Safe equipment
Do you, and your colleagues, have safe and suitable equipment?

Four steps to going home safe and well

Stop immediately if any of the four steps are not in place and re-evaluate if anything changes.

Safety first: Second nature.

mace

Applying the four steps to safety:
Working at height


Before you start work ask yourself...

<p>1 Are you in a safe place?</p> <p>Are you able to get to and from your work area safely? Has a suitable means of access to height been provided? Is the work area clean and tidy? Are suitable controls in place to prevent you being affected by adjacent work?</p>	<p>2 Do you have a safe system of work?</p> <p>Has an assessment been completed to determine if work at height can be avoided? Have collective fall prevention measures been identified ahead of personal measures? Do you fully understand the safe system of work? If required, is an emergency rescue plan in place?</p>	<p>3 Are the correct safe tools, plant and equipment available for you to use?</p> <p>Are you trained to use the tools and equipment you are using? Have you inspected the equipment prior to use? Is the equipment suitable for the task? Have you tethered your tools and equipment?</p>	<p>4 Are your colleagues safe?</p> <p>Have suitable measures been taken to prevent materials falling from height? Have adequate controls been provided to protect against any materials that may fall?</p>
--	--	---	---

...if not, stop working and speak to your supervisor or Mace manager.


58

FOUR STEPS AT HEIGHT




59

MACE WORKING AT HEIGHT HIERARCHY



60

DETAILS CAN AFFECT RISK HIERARCHY



61

WORK AT HEIGHT PLAN... MINIMUM REQUIREMENTS

Tender Stage	<ul style="list-style-type: none"> • A high level review should be undertaken. • Involve specialists (steel/MEP/decking). Note: Include all relevant trades e.g. substructure, RC frame, cladding etc. • Allocate correct costs/package splits. • Carry out a design review incorporating CDM/PD obligations are met (use Design Review checklist for this task).
Pre-construction phase	<ul style="list-style-type: none"> • Produce WAH Plan, at the same time as the project 'Riser Strategy and Delivery Plan'.
Construction phase	<ul style="list-style-type: none"> • Hold a workshop to communicate the WAH standard and plan to all employees and subcontractors. (Reference the WAH Training Plan) • Review every four (4) weeks as part of the Project Safety Review • Update the document as necessary in response to changes in working drawings and have a 'refresh' session • The H&S Manager and the Project Manager should ensure the practical implementation of the WAH Plan at regular intervals (e.g. weekly safety jacket).

All members of delivery team ...
DABs and NABs

62

REMOVE/REDUCE HAZARD AT DESIGN




- **Build at ground-level & hoist into place**
- **Consider Temporary EP vs cladding fixings**
- **Consider changing floor levels (risers, lifts)**
- **Plan lighting; perm / temp / emergency (incl shafts & risers)**
- **Fabricate steel for pre-fitting of EP**
- **Cast-in fittings to minimise site drilling**
- **Sequence tasks to reduce temporary works**
- **Specify workable parapet heights**
- **Use double-height edge trim on metal decking**

63

SYSTEM DETAILS

- Edge Protection (6 levels)
- Ground & Void Protection – fans/ decks/ tunnels/ covers
- Access Methods – scaffolds to ladders (11 methods)
- PFPE – harness-based (3 methods)
- Risers – Horizontal (4 types)
- Risers – Vertical (2 types)
- Access Vertical space (1 type)



64

CCC EXAMPLES

Compliance	Standards Trade Associations (Methods) Specific Limits
Competence	Designer / Selector Installer / Inspector User
Comprehensive Maintenance	Inspection (Frequency / Scope) Servicing Demarcation/ Exclusion Zones



65

QUESTIONS?



66

TETHERING, SIGNAGE & EXCLUSION ZONES

67

MACE TETHERING

Required:-

- Within 3m of the edge
- When “external”
- Could fall > 3m
- Above PPE free/Public zone


Tethers must be:-

- Specifically for tethering
- Suitable for the item weight
- Lock at the connection points



68

MACE TETHERING



69

TETHERING AND OTHER CONTROLS

**Tethers
(Straps)**



**Zip-Up Pockets
Tool Bags**




Sterile Zone

Stay > 3m from edge !

72

SIGNAGE

**Risers, Edge Protection,
Access Points, Hazards,
Falling Objects, add Controls**



Must be managed !

73

EXCLUSION ZONES

Hierarchically inferior... always required
 “Last line of defence”... for when other controls have failed
 Size?... Spotters!... Barriers?... Signage?...




74

OVERHEAD PROTECTION (SECONDARY MEASURES)

- Public interface & risk of falling materials
- Required:
 - when risk of fatal injury
 - for all structural works
- Consider trajectory - object shape & weight
- RAMS must include removal/ retrieval

Risk Assess for size of area...
 ... no agreed ratio yet!
 (NFDC guidance 25% of height)



Item	Distance fallen	Speed on impact	Weight on impact
0.48kg initial weight of a spanner 	5 floors 	38mph 	72kg a washing machine 

75

QUESTIONS?




76

TEMPORARY EP STANDARDS

77

TEMPORARY EP SCOPE

Scaffolding & Edge Protection



78

MACE- "TRIPLE LOCK PROTECTION"

3 independent controls:


- Required when edge >3m
- Excludes scaffolds

Example:

1. Tether
2. Containment
3. Catch Fan

Example:

1. Tether
2. Containment
3. Tunnel



79

EARLY ENGAGEMENT & DETAILING CONSIDERATIONS

- Steel frame ... pre-fitted to perimeter beams ?
- RC frame ... in place and fixing considered ?
- Cladding collaboration at design stage / interface ?
- Wind loading (allow for containment / debris netting) ?
- Containment ... gaps ?
- Screed allowance ... changing levels ?
- Vertical and Horizontal segregation ...
- Sterile Zone (3m from edge) ?
- Access controls ?
- Don't compromise products (no mixing ?)
- Tethered components ? (loose fixings ?)
- Plant stop blocks ?



80

CCC



81


CCC - COMPLIANCE



- **Regional Standard - BS EN 13374**
- **EPF Guidance (2 documents):**
 - **Code Of Practice (for BS EN 13374)**
 - **Containment Standard (gaps & porosities)**
- **Safe System Work (RAMS) (up & down)**
- **Manufacturer User Instructions**
- **Sterile Zone Permit ?**
- **TWC re loading**

82

CCC - COMPETENCE




- **Operative training (Generic/EPF)**
- **Management - EPF Code of Practice**
- **Tethered components**
- **Pre-fitted if possible**
- **Wind loading – for containment ?**
- **Maximise captive fittings**
- **Cladding collaboration**
- **Vertically alert**

83

CCC - COMPREHENSIVE MAINTENANCE

- **Inspection**
 - Weekly
 - Following adverse weather, adjustment or impact
- **Tagged**
 - EP not scaffold
 - Temp Works drawing to show tag location & extent covered (Mace std)
- **Minimal gaps underneath**



84

DESIGN REQUIREMENTS

- BS EN 13374
- Principle Guardrail
- Vertical gaps < 470mm
- Horizontal gaps < 120mm
- No unintentional removal


Mace standards:
>1500mm (otherwise **Alert**)



Tube & Fitting




Mesh Panel



85


APPLICATION CLASSES




86

CONTAINMENT-CLASS A

**Class A
(Tube & Fitting)**




**Class A
(Mesh Panel)**




87

CONTAINMENT-CLASS B

Class B
(Tube & Fitting)




Class B
(Mesh Panel)



88


CONTAINMENT-CLASS C

Class C
(Netting)



89




GAPS AT BASE



90


CLASS TEST PERFORMANCE

Wind Load Performance
 Static (calc) & Dynamic (test)
 Max Height 40m – Pressure 600N/m²



91

EN 13374 - SUMMARY



All Classes:
1.0m min height

Class	Containment	
	Tube & Fitting	Mesh Panel
A	Ø 470	Ø 250
B	Ø 250	
	Netting	
C	Ø 100	

Gaps beneath < Ø20mm

92


ADDITIONAL FEATURES



Extended or Full Height systems




Compression Posts



93

CONTAINMENT: EPF STANDARD EXAMPLE



Containment Area (Ca)	Height	Example Containment Porosity (Cp)
3	2m - Soffit	100mm
2	1m - 2m	60mm
1	Floor - 1m	5mm

~~20mm~~ 6mm

95



CONTAINMENT: CLIMBING SCREEN EXAMPLE



Containment Area (Ca)	Height	Example Containment Porosity (Cp)
3	2m - Soffit	6mm
2	1m - 2m	6mm
1	Floor - 1m	6mm

96

EN 13374: COMPLIANT PRODUCT



97


COMPETENT INSTALLATION

- Trained installers ? (EPF)
- Method Statement ? (UI)
 - Access Method ?
 - Work sequence ?
 - Erection and Dismantle ?
 - Interface with other trades ?
- Common errors



98

COMPETENT INSTALLATION



99

AVOID!



100


COLLECTIVE PREVENTION



101

PREVENTION VS MITIGATION


Prevent	Collective	Passive	Permanent
Mitigate	Personal	Active	Temporary



Rope & Grab

- Can be adjusted to Prevent
- May require Active adjustment

Prevent	Collective	Passive	Permanent
Mitigate	Personal	Active	Temporary




Inertia Reel

- Will not Prevent, can only Mitigate
- Adjusts Passively

102

FALLING MATERIALS AND EQUIPMENT




103

CONCRETE FRAME



104

CONCRETE FRAME



On form work – then move on to slab.

105


STEEL FRAME



106

STEEL FRAME


- **Bracket Adjustment**
- **Vertical & Horizontal**
- **Do it on ground – Avoid!**



107

COMMON PROBLEMS


Too close to the edge




108

POOR ANCHOR SETTING


Anchor installation



Anchor proud
of surface




Anchor installed
out of plumb




Anchor correctly
installed


Socket base installation



Socket base
proud of surface



Socket base installed
out of plumb



Socket base
correctly installed



109

UNSAFE INSTALLATIONS



110


FIXING OPTIONS



111

COMMON PROBLEMS:

Edge protection too low




112

RELATIVE HEIGHT:



113

MOUNTING BEAM ORIENTATION



114

WRONG MOUNTING BEAM



115

WRONG MOUNTING BEAM



116

CLIMBING SCREENS



117

COMPREHENSIVE MAINTENANCE:

Handover?
 Inspection Frequency?
 Recording?

Date	Name	Signature

Fail Date	Name	Signature



118

MACE INITIATIVES - SHARD



119

MACE INITIATIVES - STERILE ZONES



120

QUESTIONS?



121

TEMPORARY EP MACE LEVELS

122


TRIPLE LOCK ?

Three Independent Layers .. of Protection.

Common Control Measures ?



**Ask
More !**



123

EDGE PROTECTION - MACE LEVELS

EP Description	Panel Height	Guard Rail Height	Screen / Net Height	Risk Rating
Climbing Screen	Full	x	x	Best Practice
Full Panels & Screen	1.5m - Full	> 1.0m	Full	Best Practice
Panels with Guard Rails	> 1.5m	> 1.0m	x	Caution
Scaffolding with Panels	as per Guard Rail	> 1.5m	x	Caution
Panels Only	> 1.0m	x	x	Alert
Scaffolding Only	x	> 1.0m	as per Guard Rail	Alert

124

CLIMBING SCREEN


SAFE

Compliance	Competence	Comprehensive Maintenance
<p>BS5975 - Temporary Works CoP Containment - Usually 6mm for 3/4 levels Off-site fabrication & crane-in Crane or Jack to raise Install EP before raising</p>	<p>Design & Install - Specialist & TWC Lifting Plan - Appointed Person Inter-trade coordination - Site Manager Housekeeping; skirts, flaps, gaskets - Supervisor Platform SWL - Supervisor / Banksman</p>	<p>Inspections: - As per LOLER - Formal & Logged Weekly Keep clean and clear (especially before raising) Good Lighting</p>



125

CLIMBING SCREEN EXAMPLES



126

POST & PANEL + GUARDRAILS + FULL-HT NETTING

SAFE

Best Practice

Compliance

Competence

Comprehensive Maintenance

EN13374 >1.5m + full-height netting
 Layout as per Manufacturer's Instructions
 Containment Porosity Specified at Design
 Maximise captive / pre-fitted components
 Pre-fitted for steelwork / Cast-In for Concrete
 Guardrail vertical gaps < 470mm
 TWC if non-standard

System Design - Manufacturer
 Wind & Fixing Design - TWC
 Install/Adjust - **Certified** by Manufacturer / EPF
 Inter-trade coordination - Site Manager
 Tethering of tools & materials - Supervisor

Inspections:
 - Formal, Tagged & Logged Weekly
 - Following adjustment / adverse events
Sterile zone & Materials tied-down
 Plant stop-blocks





127

POST & PANEL + GUARDRAILS + FULL-HT NETTING EXAMPLES





128

POST & PANEL + GUARDRAILS MIN HT 1.5M

SAFE			Caution
Compliance	Competence	Comprehensive Maintenance	
<p>EN13374 >1.5m & Rails Layout as per Manufacturer's Instructions Containment Porosity Specified at Design Maximise captive / pre-fitted components Pre-fitted for steelwork / Cast-In for Concrete Guardrail vertical gaps < 470mm TWC if non-standard</p>	<p>System Design - Manufacturer Wind & Fixing Design - TWC Install/Adjust - Certified by Manufacturer / EPF Inter-trade coordination - Site Manager Tethering of tools & materials - Supervisor</p>	<p>Inspections: - Formal, Tagged & Logged Weekly - Following adjustment / adverse events Sterile zone & Materials tied-down Plant stop-blocks</p>	 

129

TUBE & FITTING TRIPLE-RAIL + PANEL MIN HT 1.5M

SAFE			Caution
Compliance	Competence	Comprehensive Maintenance	
<p>EN13374 >1.5m & Panels Layout as per Manufacturer's Instructions Containment Porosity Specified at Design Maximise captive / pre-fitted components Guardrail vertical gaps < 470mm TWC if non-standard</p>	<p>System Design - Manufacturer Wind & Fixing Design - TWC Install/Adjust - CISRS Scaffolder Inter-trade coordination - Site Manager Tethering of tools & materials - Supervisor</p>	<p>Inspections: - Formal, Tagged & Logged Weekly - Following adjustment / adverse events Sterile zone & Materials tied-down Plant stop-blocks</p>	 

130

MIN HT 1.5 M
EXAMPLES



131

POST & PANEL ONLY MIN HT 1.0 M

SAFE

Compliance	Competence	Comprehensive Maintenance
<p>EN13374 Layout as per Manufacturer's Instructions Containment Porosity Specified at Design Maximise captive / pre-fitted components</p>	<p>System Design - Manufacturer Wind & Fixing Design - TWC Install/Adjust - Certified by Manufacturer / EPF Inter-trade coordination - Site Manager Tethering of tools & materials - Supervisor</p>	<p>Inspections: - Formal, Tagged & Logged Weekly - Following adjustment / adverse events Sterile zone & Materials tied-down Plant stop-blocks</p>




132

POST & PANEL ONLY MIN HT 1.0M
EXAMPLES



133

POST & PANEL ONLY MIN HT 1.0M
EXAMPLES



135

TUBE & FITTING ONLY MIN HT 1.0M

SAFE		
Compliance	Competence	Comprehensive Maintenance
<p>EN13374 Guardrail vertical gaps < 470mm</p>	<p>System Design - Manufacturer Wind & Fixing Design - TWC Install/Adjust - CISRS Scaffolder Inter-trade coordination - Site Manager Tethering of tools & materials - Supervisor</p>	<p>Inspections: - Formal, Tagged & Logged Weekly - Following adjustment / adverse events Sterile zone & Materials tied-down Plant stop-blocks</p>



136

TUBE & FITTING ONLY MIN HT 1.0M
EXAMPLES



137

QUESTIONS?



138

ACCESS EQUIPMENT
COMMON MANAGEMENT CONTROLS

139

OVERVIEW

Access Equipment Mgt Ctrls

Access Scaffold

High Level Access MCWP

High Level Access TSAE

MEWPs & Low Level Mgt Ctrls

MEWPs

Power Tower / PAVs

Peco / Nano

Tower, Step, Ladders Mgt Ctrls

Towers

Podiums


Delta Decks

Ladders & Step Ladders

Hop Ups

140

COMMON MANAGEMENT CONTROLS



141

COMMON CONTROL MEASURES

Compliant



- SSOW (trade) for each application.
- Equipment/Method meet relevant local Standard.
- Safe Loads clearly signed (not exd).
- LOLER indicators.
- Exclusion Zone (above/below).



142

COMMON CONTROL MEASURES

Competent

SQEP ?

- Competent Selection (Mgt train).
- Competent Operation (cards).
- Competent Install, Inspection ?
- Competent Rescue




143

COMMON CONTROL MEASURES


Comp Maint

- Emergency rescue plan.
- Daily checks (recorded?).
- Periodic TE (as required).
- Tagging.
- Operational limitations.
- Weather limitations.




Ask More!

144



145

COMMON MANAGEMENT CONTROLS



146

QUESTIONS?




147

ACCESS EQUIPMENT SCAFFOLDING

148

COMMON MANAGEMENT CONTROLS



149

ACCESS SCAFFOLD (T&F OR SYSTEM)

Compliant

T&F – EN 12811
System – EN 12810
Components – EN 74, EN 30, etc
Load class on tags

Best Practice

Competent

CISRS (& System)
NASC TG20 (:yy)
NASC SG4 (:yy)
Tethering / Fans (discussed later)
AGR / PFPE / Rescue



Comp Maint

Inspection frequency / competence
Footings & ties
Exclusion zones
Clean & clear



150

ACCESS SCAFFOLD STANDARDS

- **BS EN 12810 – Façade Scaffolds – Prefabricated Components:**
 1. Product specification
 2. Methods of structural design

- **BS EN 12811 – Temporary Works Equipment:**
 1. Performance & general design
 2. Materials
 3. Load testing
 4. Protection fans for scaffolds

151

ACCESS SCAFFOLD NASC PUBLISHED GUIDANCE

Health & Safety


- Guide to Appointing a Scaffolding Contractor (Management Guide)
- SG01:14 Control of Substance Hazardous to Health in Scaffolding
- SG02:22 Asbestos Licences & Ancillary Work Involving Scaffolding Contractor
- SG03:21 Asbestos Awareness for the Scaffolding Contractor
- **SG04:22 Preventing Falls in Scaffolding Operations**
- SG05:18 Overhead Power Sources and Earthing of Scaffold Structures
- SG06:22 Management of manual handling in the scaffolding industry
- SG07:19 Risk Assessments & Method Statements RAMS

Technical

- TG01:22 Temporary Edge Protection
- TG03:25 Rubbish Chutes
- TG04:25 Anchorage Systems for Scaffolding
- TG05:24 Timber scaffold boards – BS 2482:2009
- TG06:22 Care and Maintenance of Scaffold Boards
- TG07:21 Scaffold Board Nailplates
- TG08:21 Fire Damage
- TG09:18 Design & Constr'n of Temp Roofs & Buildings
- TG10:21 Fire Retardant Treatments Timber Boards & Battens
- TG11:20 Stress Corrosion Cracks High Tensile & Alloy Steels
- TG12:22 Tying Down of Scaffold Boards
- TG13:23 Non-Standard Boarded Platforms
- TG14:20 Supplementary Couplers and Check Couplers
- TG16:21 Anchoring to the Ground
- TG17:22 Identification of EN74 – 1 Couplers
- **TG20:21 Good Practice for Tube & Fitting Scaffolding**
- TG21:20 A Guide to Commissioning Scaffold Design
- TG23:22 Prefabricated Beams
- TG25:21 Scaffold Tube Storage Racks
- TG26:22 Galvanic Corrosion Alumin'm Tubes & Prefab Beams
- TG27:25 Cladding of Scaffolding - Digital Download

152

COMPLIANT GENERAL DESIGN



Load Class

Bracing

Ties

Leg Load

Bearing ?

Butted boards

Clipped

< 225 gaps

Tethered

RAMS (up/down)

Handover

Clean/Clear



153


COMPLIANT
STANDARDISED DESIGN

When should a Scaffold be Designed?



ALL should be designed...
A Compliance Sheet is evidence of design

COMPLIANT
COMPLIANCE SHEET



Lists maximum:

- Height
- Loading
- Tie Spacing

And:

- Location
- Other Criteria
- Additions
- Etc....

COMPLIANT DESIGN LOAD CLASSES

Four main load classes :-

- | | | |
|-----------|------------------------|-----------------------------------|
| • Class 1 | 0.75 kN/m ² | Very Light Duty (or 'inspection') |
| • Class 2 | 1.5 kN/m ² | Light Duty |
| • Class 3 | 2.0 kN/m ² | General Purpose |
| • Class 4 | 3.0 kN/m ² | Heavy Duty |

All should take point load of 1.5kN



© Scafftag

156

COMPLIANT OTHER DESIGN DETAILS

- **Width**
 - Number of boards (+ inside boards)
 - No minimum in Regulations (usually 600mm)
- **Max Bay length**
 - Depends on loading and width ...
- **Bracing**
 - Usually every other bay... detail options
- **Ties**
 - Usually every other bay
 - NOTE Duty of ties



157

COMPLIANT SCAFFOLD TIES


Three classes of tie (working load pure tension)

- Light duty 3.5kN
- Standard duty 6.1kN
- Heavy duty 12.2kN



Examples of ties


Ringbolt in internally threaded socket anchor



Proprietary tie in socket anchor



Band and plate coupler in socket anchor




Special hook in Nylon plug and screw in eye



M16 threaded rod set in socket anchor and sheathed by tube under compression to avoid buckling



Threaded coupler on stud projecting anchor



Threaded coupler welded to base plate



158

COMPLIANT SCAFFOLDING TYPES


■ Tied Independent Scaffolding



159

COMPLIANT SCAFFOLDING TYPES

■ Free-standing Independent Scaffolding



NASC

160

COMPLIANT SCAFFOLDING TYPES


■ Bridging with Beams



NASC

161

COMPLIANT LIFT LOADING & HEIGHTS



Lifts to 3m !!

2m

2m

2.7m




162

COMPLIANT SCAFFOLDING TYPES

■ Loading Bay



■ Ladder Access Tower



163


COMPLIANT
ACCESS & EGRESS



164

COMPLIANT
LEDGER BRACES

Every other bay
&
Every lift



- or -



Structural Transoms
(e.g. "Readylock")
Max 30m high

165

COMPETENT UNACCEPTABLE TRADITIONS




166

COMPETENT PLANNING ERECTION & STRIKING



167

COMPETENT CISRS SCHEME



1 year minimum

2.5 years minimum

Note NASC Safety Guidance.

- Working From Vehicles
- Manual Handling
- Preventing Falls

Considered as Trainee until CISRS & NVQ

Refresher training (5 years)

Labourers .. Work on the floor, or on completed scaffold

Competent... Confident... Complacent?

COMPETENT INSPECTOR




Ask More...

COMPETENT FORMAL GUIDANCE

~~SG4:22~~
~~SG4:15~~

**Preventing Falls in
Scaffolding Operations**

NASC



170


COMPETENT GUIDANCE STRUCTURE

SG4:15 Preventing Falls in Scaffolding Operations

- **Section 1** **Planning for Work at Height**
- **Section 2** **Scaffolders' Safe Zone**
- **Section 3** **Other Applications**
- **Section 4** **Access and Egress**
- **Section 5** **PFPE**
- **Section 6** **Rescue**


171

COMPETENT AVOID




172

COMPETENT COLLECTIVE PREVENTION (SAFE ZONE)




173

COMPETENT
MITIGATE (PFPE)



174

COMPETENT
SCAFFOLDER'S SAFE ZONE



175



COMPETENT
AGR PRINCIPLE



Advanced
Guard
Rail



176

COMPETENT
AGR PROCESS





177

COMPETENT "SCAFF STEP"




178

COMPETENT AGR ALTERNATIVE OPTIONS




179

COMPETENT
AGR HORIZONTALLY



180

COMPETENT
PASSIVE NOT ACTIVE




**“Protected Traverse”
Too ACTIVE to be reliable**

181


COMPETENT SCAFFOLDER'S PFPE

Basic "Construction" kit, with added features...



182

COMPETENT POOR ANCHOR SELECTION




183

COMPETENT TETHERING



Tethering Tubes?
Especially for fans...



184

COMPETENT OPERATIONS




185

COMPETENT FAILURES



Loosely Stacked Boards



No Protection from Vehicles

186

COMPREHENSIVE MAINTENANCE INSPECTION & TAGGING

Handover ?
Inspection Frequency ?
Recording ?
Ties ?



187

COMPREHENSIVE MAINTENANCE MACE CHECKLIST

Scaffold co-ordinator checklist

	Name of Company	Package Number	Supply Chain Assessed	Yellow Jacket License Holder	Design / System Scaffold	Scaffold Location & Marked up Site Drawing	Design Drawing & Calculation Ref.	3 rd party design checks complete	Erection / removal RAMS in place	Start Date	Handover certs complete	Scaffold inspection Tags utilised	Permit to strike	Completion Date
1														
2														
3														
4														
5														
6														
7														
8														
9														
10														

188

QUESTIONS?



189

ACCESS EQUIPMENT

MEWP

(MOBILE ELEVATED WORK PLATFORM)

PAV

(PUSH AROUND VERTICAL)

190

MEWP EXAMPLES




191

MEWP OBSERVATIONS




192

COMMON MANAGEMENT CONTROLS



193

MEWP



194


PAV (PUSH AROUND VERTICAL)

Less than 5m Reach height?




195

CCC - MEWPS & PAVS

Compliant	Capacity marked. Lifting plan (task). Rescue plan.	Best Practice
Competent	Competent Selection. IPAF MEWPs for Mgrs. Competent rescue. Zones / Stop blocks.	Risk Assessment Method Statement
Comp Maint	Regular inspection (daily). LOLER Displayed on machine.	

196


CCC - MEWPS

Compliant	EN 280 / BS 8460 : 2025 Capacity indicated CE marked anti entrapment (Boom) MEWPs for Mgt	Best Practice
Competent	Lifting plan IPAF/PAL (PAL +) Specific operative/task only Rescue plan Exclusion / Wheel stops Tethering.	Risk Assessment Method Statement
Comp Maint	Daily Inspt (tag) Bearing LOLER	

197

COMPLIANCE BS 8460:2025 CHANGES

- **Principal changes:**
 - Compliance with EN280 changes
 - Process map for safe use of MEWPs & content restructured to suit
- **Clarifications:**
 - Confined work-spaces
 - PFPS use over water
 - Segregation from pedestrians
- **Informative annexes:**
 - Hoist lift height limits
 - Wind speed vs height
- **New / enhanced recommendations:**
 - Risk management
 - Effect of wind
 - MEWP as part of a fall arrest system
 - Loading and handling with MEWP
 - Zone & motion control
 - Minimum attributes of personnel
 - Avoiding trapping / crushing & guarding
 - Pedestrian controlling
 - Returning to service after non-use
 - New definitions







198

COMPLIANCE ANTI-ENTRAPMENT

- Mace requirement:**
- **Cherry Pickers – for many years**
 - **Scissor Lifts – since Jan-2026**
(as per People Plant Interface Standard)
- Included in BS8460:2025 for cherry pickers




	Physical Barrier Fixed Full Cage Structure
	Physical Barrier Operator Protective Structure
	Physical Barrier Side Protection Barriers
	Pressure Sensing Device Pressure sensing bar – stops further movement & audible & visual alarm

199

MANAGER COMPETENCY




MEWPs for Managers?




200

CHERRY PICKER:

Straight Boom





Articulated Boom



201

CHERRY PICKER:



202

CHERRY PICKER:



203

CHERRY PICKER:



204

CHERRY PICKER:



205

CHERRY PICKER:



206

SCISSOR LIFT:



207

SCISSOR LIFT:



208

WHAT DO YOU THINK?



**Design issues with
corner brackets...**

Emergency lowering

Wind load

Slab capacity


Wheel stops

No tethering



209

OBSERVATIONS?




210

OBSERVATIONS?



211

COMPETENT:



Specifics listed on the back
 1a, 1b (Static) + ?
 3a, 3b (mobile) + ?
 PAV
 Special (Mgt, Mast Climbers ...)
 Etc



Health and Safety
 Executive

The selection, management and use of mobile
 elevating work platforms

HSE information sheet

General Information Sheet No 6

212

MEWPS - FALL PROTECTION



Layers of Protection

- Generally – guard rail (**collective prevention**)
- Occasionally – restrained by PFPE (**personal prevention**)
- Rarely – fall arrested by PFPE (**personal mitigation**)




IPAF IPAF Guidance (2025)

- **PFPE in boom type MEWPs essential due to risk of falling or catapulting/ ejecting (not a risk in verticals)**
- **Lanyard should be short enough to restrain within platform (adjustable) & may contain an energy-absorber**
- **Over water risk assess to determine PFPE or life-jacket**

213

CHERRY PICKER- CLIMBING-OUT?

- Generally equipment not designed for this
- IPAF require additional controls including:
 - No fall risks – platform to be at least 2m from roof edge
 - Operator to remain in platform – extra person required




214

CHERRY PICKER- OVER-REACHING?



215

COMPREHENSIVE MAINTENANCE - RESCUE




216

COMPREHENSIVE MAINTENANCE



**Exclusion Zones
Tethering,
Wheel stops
Wind Resistance**



217

COMPREHENSIVE MAINTENANCE

Daily Inspection
6 month LOLER



218

PAVS: (INCLUDING PECO)

Compliant

EN 280 (power tower)
MEWPs for Mgt
Capacity clear
Bearing (raised floor)
< 5m working height
Internal flat only (unless rated)



Competent

Lifting plan (competent person)
IPAF - PAV (or 1a/3a with familiarisation)
Rescue/Lower plan
Exclusion / Wheel stops
Tethering.



Comp Maint

Daily Op insp (tag)
LOLER.



219

PAV - COMPLIANCE

No specific Standard as yet but they meet "others" (EN 280)



220

PAV - COMPLIANCE

Internal Use Only!



High bearing pressure?



221

PAV - COMPETENCE

- **Used Preferred**
 - IPAF PAV
- **User Adequate (with familiarisation)**
 - IPAF 1a / 1b / 3a / 3b
- **Managers / Supervisors**
 - IPAF MEWPs for Managers



222

COMPETENT:

- **Wheel stops**
- **Wind**
- **Over-reaching**
- **Access to work area**
- **Bearing pressure**
- **Exclusion**
- **Etc..**



223

QUESTIONS?




226

ACCESS EQUIPMENT TOWERS & PODIUMS

227

COMMON MANAGEMENT CONTROLS




228

LOW-LEVEL WORK PLATFORMS

"PASMA" Tower
EN 1004

Max platform heights:
Indoor: 12m
Outdoor: 8m



Podium Step
BS 8620 (or PAS 250)

2.5m
max

229

TOWER CCC

Compliant

EN 1004
 AGR preferred to 3T
 Legs/Riggers as per manufacturer
 Platform capacity marked (SWL)
 Add stability in wind (<2m edge)



Caution

Competent

PASMA (erect/adjust/inspect)
 Users?
 Always leave SAFE (up/down) locked
 Toe Boards
 Tethering
 Don't overload

**Comp Maint**

Daily pre-use PASMA
 Weekly PASMA (tagged)



230

TOWER STANDARDS

BS EN 1004-1:2020

Mobile access and working towers
 made of prefabricated elements -
 Materials, dimensions, design loads, **safety and performance** requirements

BS EN 1004-2:2021

Mobile access and working towers
 made of prefabricated elements -
 Rules and guidelines for the preparation of an **instruction manual**


231

TOWER TRAINING

PASMA

Prefabricated Access
Suppliers and Manufact
Association

(Category on Cards)



Basic Tower
(T)



On Stairs
(A5)



Cantilever
(A6)



Bridges
(A7)



Linked
(A8)



Large Deck
(A9)

232

COMPETENT USE



- **PASMA Ticket** (to erect, strike, significant adjustment, or inspection)
- **Always leave SAFE**
- **Toe Boards (Risk Assess)**
- **Tethering (Risk Assess)**
- **SWL**
- **Locked** 🗝️



233

TOWER ASSEMBLY TECHNIQUES



AGR
Advanced Guard Rail
Preferred

Technique depends
on tower design


Choice at procurement!



3T
Through The Trapdoor
Prone to mis-use & abuse

234

TOWER ASSEMBLY DETAILS



235

TOWER WIDTH & STABILITY



**Choose widest
for task space**

**Use Outriggers
whenever
tower is tall
enough to fit**



236

SINGLE PERSON TOWERS




**Easier to handle
Fold-away options**

**Reduced Stability
Narrower Platforms
Challenging Rescue**



237

CLOSE TO THE EDGE?



238

COMPREHENSIVE
MAINTENANCE

Must be inspected:

- Every time
 - Assembled, or
 - Altered (significantly)
- Every 7 days

239

OBSERVATIONS ?



- Outriggers
- Deck spacing
- Toe boards
- Bracing positions
- Proximity to glass
- Ladder alignment (outside tower)

240

PODIUM STEPS

Compliant

BS 8620 (PAS 250)
 Max 2 wheel
 Podiums that do not require outriggers.
 Fold out preferred
 Erected to Manuf Inst.

Caution

Competent

PASMA (<2.5m)
 Clear and Level
 Folding preferred
 Legs trip hazard ?
 Leave SAFE (up /down) Locked




Comp Maint

Use PASMA check list
 Daily pre-use
 Weekly (tag)



241

COMPLIANT



Opportunity ?

242

COMPLIANT



Max 2 wheels
 Max 2.5m high
 Prefer Fold-Out

BS 8620 (PAS 250)

243

BASIC REQUIREMENTS



BS8620 Stability Check

- 0.75kN on platform
- Legs attached
- 0.30kN push at platform

Toe board required?

WaH Regs - Suitable and sufficient steps to prevent falling objects liable to cause injury
Depends on task, tools & environment

244

COMPETENT



Specific < 2.5m course

Card remains the property of PASMA

Report any dangerous or inappropriate activity by the cardholder

245

COMPREHENSIVE MAINTENANCE


Must be inspected:

- **BEOOU**
- **Every 7 days & tagged**



246

OBSERVATIONS?



- **Outriggers**
(in view!)
- **Other means of stabilising**
(tied or soffit pole)
- **4 x wheels**
- **Wheel jacks over-extended**
(one should always be minimum)
- **Bottom step height**
- **Edge Protection**
- **Containment**
(Triple Lock)

247

OBSERVATIONS?



Protecting finishes
but can't inspect

Platform too high
No Outriggers
Top step reach
Bracing
Proximity to Riser



248

QUESTIONS?




249

PFPE


(PERSONAL FALL PROTECTION EQUIPMENT)

250




251

P F P E – C C C	
Compliant	<p>CE-Marked Certified anchor installation</p> <p><u>Prevention</u></p> <ul style="list-style-type: none"> • Prevents Falls <p><u>Mitigation</u></p> <ul style="list-style-type: none"> • Overhead inertia preferred
Competent	<p>PFPE Selection & Use Anchor Design & Install Passive preferred to Active Exclusion Zones & Tethering Controlled Zones & Signage</p> <p><u>Mitigation</u></p> <ul style="list-style-type: none"> • Clearance (vertical & swing) • Rescue
Comp Maint	<p>User daily inspection (visual & tactile) Formal inspection (<=6 monthly & logged) Tagged Clean dry storage</p>






Risk Assessment Method Statement



252

PFPE – COMPLIANCE STANDARDS (PREVENTION & MITIGATION)

EN 353-1 - Rigid Line Arresters	EN 363 - Fall Protection Systems
EN 353-2 - Flexible Line Arresters	EN 364 - Test Methods
EN 354 - Lanyards	EN 365 - Instructions, Examination, Marking
EN 355 - Energy Absorbers	BS 7883 - Design, Installation, Inspection
EN 358 - Work Positioning Lanyards	BS 8437 - Selection, Use, Maintenance
EN 360 - Retractable Fall Arresters	BS 8454 - WAH Training Delivery
EN 361 - Full Body Harnesses	BS 8610 - Anchor Systems Specification
EN 362 - Connectors	
EN 795 - Anchor Devices	
BS 8513 - Twin-Legged Lanyards	







253

PFPE - COMPETENCE ANCHOR POSITIONING

Anchor Position:

- Set-back from edge (>2.5m)
- High – but reachable
- Parallel to Edge – to reduce adjusting





254

PFPE - COMPETENCE GOOD PRACTICE



255

PFPE - COMPETENCE WORK RESTRAINT IN CORNERS




256

PFPE - COMPETENCE VOIDS

Is this effective fall prevention?

**Falls in front!
Anchors behind!**




Extra rope length increase free-fall:

- Increased clearance required
- Arrest loads above design specification

257

PFPE - COMPLIANCE SYSTEM ELEMENTS




Comprehensive specification
required...
from worker to anchor

BS 8437:2022
Code of Practice
Selection, use & maintenance
of PFPE

258

PFPE - COMPETENCE HARNESSE SELECTION

- Many types available
- All suitable for Arrest & Restraint
- All need to be fitted correctly
- General categories:
 - Construction – flexible / light / simple / low cost
 - Utilities – stiffer / heavier / more options / mid cost
 - Rope Access – supportive / heavy / complex / expensive
- All have rear (Dorsal) points – generally recommended
- Some also have front (Sternal) points



259

PFPE - COMPETENCE

DORSAL EXTENDERS

- Reaching rear (“Dorsal”) point of correctly-fitted harness is difficult
- Extender allows easier, safe self-attachment
- Fitted to Dorsal Point (factory or retro-fit)
- Length 300mm to 500mm (to minimise slack)





260

PFPE - COMPETENCE

HARNESS CHECKS

- 1. Rear Attachment Point**
Condition & Position
- 2. Chest & Thigh Straps**
Tight (2 to 4 fingers)
Cannot pull off shoulders
Comfortable at groin
- 3. Rear Strap**
Beneath back-side
- 4. Connectors**
All Locked
- 5. Link to Anchor**
Short with minimal slack

1 + 2 + 3 requires time & effort !




261

PFPE - COMPETENCE LANYARD SELECTION



- Maximum length 2m (including energy absorber)
- Energy absorber always justified
- Always have energy absorber at user end (not anchor)
- Choice of connectors at both ends
- Usually webbing (can be rope)
- Twin tail (single energy absorber)
- Check if rated for edges (tested to CNB-RFU-11.074)



262

PFPE - COMPLIANCE ENERGY ABSORBERS

- Many types depending on system
- “Plastic” deformation, not elastic, so no “bounce”
- High initiation force (2kN = 200kg)
- Limited peak force (6kN = 600kg)
- Will not deploy accidentally, can be used in Restraint systems...




**“Its better to have one & not need it,
than to need one & not have it!”**

263


PFPE-COMPLIANCE DEMONSTRATION

- Demo from 3M



264

PFPE-COMPLIANCE LANYARD ENERGY ABSORBERS



265

PFPE - COMPLIANCE ROPE & GRAB SYSTEMS



- **Manually adjusted to set length**
- **No energy absorber...
No fall arrest!**
- **Good for WORK RESTRAINT**
- **Most designed only for vertical use**
- **Ensure rated for horizontal use & over edges
(tested to CNB-RFU-11.075)**



266

PFPE COMPLIANCE RETRACTABLE FALL ARRESTERS

- **AKA... Inertia Reel / Fall Arrest Block / SRL** (Self-Retracting Lifeline)
- **Range of lengths & line materials**
- **Most models have limited safe use range:**
 - **Angle – lock may fail closer to horizontal (marked)**
 - **Edge – lines can be cut**
- **Most older models only rated for overhead use**
 - **Use higher spec (more expensive) models
(tested to CNB-RFU-11.060)**
 - **Plan all anchors to be overhead**
- **Latest standard BSEN360:2023**
 - **Option to test for horizontal use**
 - **Will be marked**




Often
only
30° - 40°




267

PFPE COMPLIANCE COMMON RETRACTABLE ISSUE




268

PFPE - COMPETENCE CONNECTORS



269

PFPE-COMPETENCE ANCHOR SELECTION




270

PFPE-COMPETENCE TEMPORARY ANCHORS


Wire Rope Anchor



Toggle Anchor



Anchor Sling
(Webbing or Wire)



Temporary
Horizontal Life Line

271

PFPE - COMPETENCE ANCHOR STRENGTH

- **Arrest Force = 6kN**
(limited by Energy Absorber)
- **Safety Factors**
= **2.0** (EN) Temporary, or
= 2.5 (BS) Permanent
- **Required Strength**
= $2.0 \times 6 = 12\text{kN}$ (1200kg) for EN
= $2.5 \times 6 = 15\text{kN}$ (1500kg) for BS
- **Typical car weight = 12kN**
(Ford Focus)



272


PFPE - COMPETENCE DEADWEIGHT ANCHORS

Comply with EN 795 – Type E 

Platform surface must be:

- Tested with anchor (wet & dry)
- Max 5° pitch
- Clean
- Not frozen

Allowed to
slide 1m
& still comply!



273

PFPE-COMPREHENSIVE MAINTENANCE FALL INDICATORS?



274

PFPE-COMPREHENSIVE MAINTENANCE USER INSPECTIONS



275

HARNESSES SUSPENSION

Time critical

- Medical issues can develop for 20% within 10 minutes
- Lack of muscle movement affects circulation (orthostatic intolerance)
- Blood collects in feet & legs (Venus pooling)
- Lack of oxygen to brain leads to dizziness (Pre-syncope)



Emergency services too slow

(& medical attention probably not required after prompt rescue)

Site-based plan required

276

RESCUE PLANNING



FIRE RISK



FALL RISK



Keep the emergency kit VERY close!

Practice → Experience → Competence

Fully Planned:

Location & Task Specific
Detailed in Task RAMS
DOWNWARDS to 'safe place'
Aim for 10mins

Rescue Ready:


Rescue kit close by
Always >1 person in harnesses

Practice:

Regular toolbox talks
(on the ground – low risk only!)
Spare kit for training
(if main kit 'sealed')

277

RESCUE RPD (RAISE-PROTECT-DELIVER)



278

RESCUE EXAMPLE KIT & PLAN

- Example Kit
- Constant Rate Descender (CRD)
 - Rope (long enough???)
 - Sling
- Reach Pole (Telescopic)
- Corner Protector

Restrain rescuer
Rig descender
Reach harness
Raise casualty
Release lanyard
Regulate descent



279

PFPE MANAGEMENT CONTROLS:



- Signage – “Use PFPE”
- Anchor – Compliant Design & Specification (EN795)
- Anchor – Competent & Certified Installation (BS7883)
- Exclusion Zones
- Tethering
- Competency – Use & Rescue
- Rescue Planning
- Rescue Practice – Low risk



**Restraint
Fall Prevention**



**Fall Arrest
Min Ht & Consq**

280

QUESTIONS?




281


OVERHEAD PROTECTION

282

OVERHEAD PROTECTION



**Whom
from
What
&
How ?**




283

KINETIC ENERGY

- What is the “major” concern?
- What are we trying to “capture”...?



Kinetic Energy!



284

SCAFFOLD FAN

**DROP TEST
A513**

285

SAFETY NET



286

FANS - CCC
NETS & SCAFFOLD**Compliant**

**BS EN 1263 (Nets)
SG34:17 (new)
Local authority requirements
EP must be in place**

**Best
Practice**

Competent

**FASET/Manufacturer Training
CISRS / SG4:15.
Design load / Scaffold capacity..
TWC involvement**

**Comp Maint**

**Free of Debris.
7 day inspection.
Recorded.
Lighting etc (tunnels).**



287

NETS - COMPLIANT

EN 1263 – Safety Nets

- Part 1 - Product Performance, (test, and maintenance)
- Part 2 - Positioning Limits (rigging)





FASET Best Practice Guidance

BS 8411 : 2007

Code of Practice for Safety Nets on
Construction Sites


288

NETS - SYSTEMS




System S

Safety Net with
border rope to be
fitted to suitable
structure



System U

Safety Net attached to
supporting frame for
vertical use




System T

Safety Net attached to
brackets for horizontal
use

289

NETS - DROP TESTS

System T Drop Test



290

NETS - LABELS & TEST CORDS

Label:


EN 1263-1 – S – A2 _ Q100 – 18 x 15

- Year/month (first in service)
- Test Cord Min
- Manufacturers Identification
- Serial Number (also on test meshes)



291

NETS - LAYERED



Mesh density :-

- 100 x 100
- 60 x 60
- 20 x 20
- Debris



292

NETS - COMPETENCY

FASET
Fall Arrest Safety Equipment Training



NVQ L2

- Work unsupervised
- Handover
- Supervise



- Work under supervision

293

NETS - INSTALLATION TRAINING



294


NETS - INSTALLATION ISSUES

- **Access?**
- **Working on the edge?**
- **Below?**
- **Exclusion Zones**
(how high does that work?)
- **Tethers?**
- **Tools plus components & fixings**
Scaffold tubes?
- **Interfaces?**
- **Edge Protection, Cladding, etc ...**
- **Loading?**
- **Temporary Works / Scaffold**



295

NETS - FALL ARREST REQUIREMENTS



maximum
fall height

He	≤ 1.0m	≤ 3.0m	≤ 6.0m
b	≥ 2.0m	≥ 2.5m	≥ 3.0m

minimum
width

296

NETS - INSTALLATION ERRORS



297

NETS - CAPABILITY EXAMPLE

- Mr Rahman fell from 8th floor
- Into Safety Net Fan on 4th floor
- Fall of 15m
- Unknown weight



298


NETS - COMPREHENSIVE MAINTENANCE

- Inspection > 7 days? (recorded)
- Keep clear (hats, ply, concrete)
- Check fittings (loosen in wind)
- Tie up in high wind
- (>25MPH, crane down)



299


SCAFFOLD FANS



300

FANS, DECKS & TUNNELS

**Kinetic
Energy ?**



301

OBSERVATIONS?



302

FANS -
PERFORMANCE

**Guidance on
Protecting the Public:**
HSE - HSG 151
NASC - SG 34



**Mostly relates to actual
“scaffold” .. But has some use.**

Local Authority requirements


303

LACK OF HAZARD AWARENESS



304

PEDESTRIAN PROTECTION



305

VEHICLE CLEARANCE & PAVEMENT ISSUES



5.05m minimum clearance
between the road and fan (may
vary between local authorities)



0.45m minimum from the
outer barrier to the scaffold

Less than 0.45m
to the kerb

Consider the following:

- Disabled & Buggies / Prams
 - Children-Proof
 - Lighting (incl. emergency)
 - Snagging on sharps
 - Earthing
 - Mugging
 - Escape
 - Underground services
 - Drainage
- etc...

LA
Pavement Licence

306

PUBLIC PROTECTION



307

PUBLIC PROTECTION


HSE Guidance on “protecting the public”.
Local authority standards?



308

OBSERVATIONS?

- **Gaps Overhead**
 - **No lighting**
 - **Snagging**
 - **Climbable**
 - **Trip hazards**
- **No collision barrier**
 - **Escape routes**



309

QUESTIONS?



310

VOID PROTECTION

311

VOID PROTECTION

Compliant

No specific Standard
 Load bearing !!
 TW Eng / Tworks BS 5975
 New designs .. Proper covers
 Max load needed (pics/kgs).
 MACE Tech Note E16

Competent

Temp Wks Designer
 Warning signs (capacity)
 Nom Person (mgt)
 Riser Coordination meetings
 Installation equipment needed

Comp Maint

Formal Weekly.
 Recorded
 Signs (pics/numbers)



312

COMPLIANT

- TWC Approval
- HSE Guidance (withdrawn?)
- Significant Loads:
 - Distributed (persons, materials etc)
 - Point (wheels such as MEWPs, pods)
 - Factors
- Span Orientation (timber)
- Bearing (all sides ?)
- Secured !!
- Access hatches
- Signage



313

COMPLIANT

Proprietary load-bearing deck system ?
 (provision made in support surface ?)
 (designed/selected for the load?)
 (fire stopped?)




Best Practice



Inspection tag
 system

314

COMPLIANT




315

TECH NOTE E 16

Loading intensity:

Imagine a room with a grid of 1m² drawn on the floor, and if we had one operative stood in each 1m square – then you'd have a floor load of 100kg per square metre or 1.0 kN/m².
 Similarly, if you then had two operatives stood in each square metre, then it would be 200kg per square metre or 2.0 kN/m². (as shown on central image below).
 Noting that people and items move within a space, these loads are looked at as an average, thus in the image (right), the average loading is 1.0 kN/m².



316

WITH VEHICLES ..
 DIFFICULT TO SIGN ?



317

OBSERVATION ?



318

OBSERVATION ?



319

OBSERVATION ?



320

WHY NOT LEARN FROM SCAFFOLDING?...

VERY LIGHT DUTY USE ONLY

MAXIMUM SCAFFOLDING LOAD:
0.75 kN/m² = 75 Kg/m²
15lbs / sq. foot

EQUIVALENT TO:
Load Class 1

PER m²

GENERAL PURPOSE USE ONLY

MAXIMUM SCAFFOLDING LOAD:
2 kN/m² = 200 Kg/m²
42lbs / sq. foot

EQUIVALENT TO:
Load Class 3

PER m²

LIGHT DUTY USE ONLY

MAXIMUM SCAFFOLDING LOAD:
1.5 kN/m² = 150 Kg/m²
31.5lbs / sq. foot

EQUIVALENT TO:
Load Class 2

PER m²

HEAVY DUTY USE ONLY

MAXIMUM SCAFFOLDING LOAD:
3 kN/m² = 300 Kg/m²
51.1lbs / sq. foot

EQUIVALENT TO:
Load Class 4

PER m²

© Scafftag

321

QUESTIONS?



322

ACCESS EQUIPMENT

MCWP


(M A S T C L I M B I N G W O R K P L A T F O R M S)

TSAE

(T E M P O R A R Y S U S P E N D E D A C C E S S E Q U I P M E N T)

323

COMMON MANAGEMENT CONTROLS



324

MCWP

A Work Platform
NOT a hoist



325

T S A E

A cradle or work platform.



326

A E : M C W P

Compliant

BS 7981 (install, maint, TE)
BS EN 1495
Rescue RAMS
Exclusion

Competent

Operator train (IPAF)
Supplier/Manuf (demo)
Inspector (daily)
Temp Wks (Wind)
Debris
PFPE (RAMS)
Daily pre-use
Specific maint
LOLER
Left clean clear


Comp Maint

Caution



327

COMPLIANT: MCWP ELEMENTS



328

MCWP - COMPLIANCE

**BS7981:2017 - Code of practice
installation, maintenance, thorough examination & safe use of MCWPs**

- **Hazards**
- **Specification, installation planning, erection and dismantling**
- **Management and control**
- **Personnel and training**
- **Planning of the installation**
- **Siting**
- **Installation**
- **Operation, use, maintenance and inspection**
- **Thorough examination and testing**
- **Safety at the work site**

329

MCWP - COMPLIANCE

BS EN 1495:1997+A2:2009

Lifting platforms. Mast climbing work platforms

- List of hazards
- **Safety requirements and/or measures**
- Verification of the safety requirements and/or measures
- **Information for use**

330

OBSERVATIONS?



331

OBSERVATIONS?



332

COMPLIANT:



- Position
- Foundation (design)
- Ties (design, install & removal)
- Capacity (tasks / activities)
- Access to Platforms (higher levels)
- Interlocks (platforms sharing mast / overlapping)
- Ground Protection (exclusion zones / deck)
- Prevention of Unauthorised Use
- Power Supply (fixed with switch)
- Weather / Wind (monitoring & actions)
- Inspection (LOLER)

333


COMPLIANT : MACE REQUIREMENTS

- **Limit switches**
- **Levelling system**
- **PFPE & Rescue (RAMS)**
- **Stop Button**
- **Direction controls (?)**
- **Gate interlock**
- **Manual descent & Overspeed brake**
- **Max load sign (icons ?)**
- **Tethering**



334

OBSERVATIONS?



335

OBSERVATIONS?



336

COMPETENT: BS 7981

**“Suitably” Qualified Person
(knowledge/experience/training)**

Supplier Competent Person

User Competent Person

Installer

Demonstrator

User/Operator



**IPAF Guidelines for the Safe
Use of Mast Climbing Work
Platforms**

BS 7981:2017



Code of practice for the installation,
maintenance, thorough examination
and safe use of mast climbing work
platforms (MCWPs)

337

COMPETENT:



Installers/Operators/Demonstrators/Inspectors



338

COMPETENCE :



339

COMPREHENSIVE MAINTENANCE:

- **TE prior to 1st use after install**
Frequent Inspection / Testing
- **Daily Pre-Use Inspection**
User Appointed Person
- **LOLER (MACE) / 3 Month (BS)**
- **Inspection following In-Service Maintenance**
As required by Manufacturer / Installer

Handover ?

Check Sheet ?

340


T S A E

A cradle or work platform.



341

COMMON MANAGEMENT CONTROLS



342

AE : TSAE

Compliant

BS 5974
 LOLER / TE
 Task RAMS
 Exclusion / access deck / locked anchors wts

Competent

User Appt Person
 Familiarity training for all
 Supplier/ Manufacturer (demo)
 Rated load
 TWC Design (Wind / Debris)
 PFPE (RAMS) Rescue
 Anemometer

Comp Maint

Inspector (daily)
 Daily pre-use
 Specific maint
 LOLER
 Left free clear

Caution



343

COMPLIANT:

TSAE



344

TSAE - COMPLIANCE

BS 5974:2017 - Planning, design, setting up and use of temporary suspended access equipment. Code of practice

- **Identifying hazards**
- **Planning & info exchange**
- **Responsibilities**
- **Health and safety**
- **Types of TSAE**
- **Materials & components**
- **Overturning & righting**
- **Design criteria**
- **Components & WLL**
- **Electrical requirements**
- **Protection against lightning**
- **Installation, commissioning, handover & dismantling**
- **Maintenance, thorough examination and testing**
- **Using TSAE**
- **Care in storage**
- **Personnel and training**

345

OBSERVATIONS?




346

OBSERVATIONS?



347

OBSERVATIONS?



348

COMPLIANT:



- Position
- Fixings (mechanical / locked ballast)
- Supports
- Façade Ties
- Capacity (tasks / activities)
- Access (higher levels)
- Secondary Support & Braking
- Ground Protection (exclusion zones / deck)
- Prevention of Unauthorised Use
- Power Supply (fixed with switch)
- Weather / Wind (monitoring & actions)
- Inspection (LOLER)

349


MACE REQUIREMENTS

- TWC for supports / fixings / ballast
- Rated Load
- Overspeed brake / 2nd ry support
- PFPE & Rescue (RAMS)
- User Appointed person



350

OBSERVATIONS?



351

SECURITY OF RIGGING




- Requiring hand-tools is sufficient level of security
- Steel cables & grips
or
- Lockable enclosure
- Use signage



352

COMPETENT: BS 5974

User Appointed Person
Supplier Appointed Person



353

COMPETENT

Previously no “accredited” courses...

SAEMA now offer Operator Course:

- Part 1: On-line
- Part 2: On Site



Installers/ Operators / Demonstrators / Inspectors



354

COMPREHENSIVE MAINTENANCE:

- **TE prior to 1st use after install**
Frequent Inspection / Testing
- **Daily Pre-Use Inspection**
User Appointed Person
- **LOLER (MACE) / 3 Month (BS)**
- **Inspection following In-Service Maintenance**
As required by Manufacturer / Installer




Handover ?

Check Sheet ?



355

MCWP & TSAE FIXINGS IN CONCRETE



Affects on Fixing Capacity:

- Fixing Type
- Edge Distance
- Proximity to Each Other
- Slab / Wall Thickness
- Concrete Age (maturity)

356

QUESTIONS?




357

ACCESS EQUIPMENT

DELTA DECKS, LADDERS, STEPS & HOP-UPS

358


DELTA DECKS, LADDERS, STEPS & HOP-UPS



Can it fall over?
Can I fall off it?

359

COMMON MANAGEMENT CONTROLS



360

DELTA DECKS



- **Low & wide**
good stability
- **Guardrails**
high & robust – but compliant?!
- **Fold-Away**
Fewer assembly errors
- **Portable**
25kg to 30kg

Fall over? **Good**
Fall off? **Good**



361

DELTA DECKS - CCC

Compliant

EN 1004-1 tested/rated
 EN 1004-2 instructions (formerly EN 1298)
 SWL 200kgs
 Max work height 2.6m

Caution

Competent

Prod Training / Familiarisation
 Clear and Level
 Leave SAFE



Comp Maint

Daily pre-use
 Weekly (tag).



362

LADDERS & STEPS



Fall over? **Poor**
 Fall off? **Poor**



363

LADDERS & STEPS - CCC

Compliant

EN 131 (Professional)
Composite or metal
Wooden - with RA (BS1129 C1)

Alert

Competent

LA offer training
Use justified (permit)
Incline Sticker/Rating
Secured (tied braced)
Locked against use

**Comp Maint**

Daily pre-use
Tags/Reg.



364

LADDERS & STEPS -
COMPLIANT

- BS EN 131
- No 'domestic' ladders – now termed 'non-professional'
- Only 'professional'
- No wooden ladders (unless risk assessed)
- Do not use as "work platform" without additional controls:
 - 3 points of contact?
 - Fall Protection?
 - Not telescopic ladders




Remove top three
steps/rungs?



365

LADDERS - COMPLIANT



Safe Use Specification

- Competency: Ladder Assoc
- Max height: 6m?
- Marked SWL: 150kg
- Marked Angle: 1H:4V (75°)
- Level Ground: <10°
- Tied / Secured from ground
- Reach: <600mm
- Storage: Locked

366


LADDERS - COMPETENCE



Ladder Performance
Window Placement
Test Class 1, Survey Class 2

θ	$\theta=13.6^\circ$	$\theta=14.4^\circ$	$\theta=16.1^\circ$
175cm	350	380	350
22"	400	630	800
30"	450	630	900
45"	500	750	1050
d	1250	1450	1875

Notes
 1. Max. 6.5m (ladder at 5.5m)
 2. Range above feet
 Feet always below stand-off
 Max reach 1.5m above feet
 Level footing $\pm 10^\circ$ across full
 Ladder/CT reach protrusion
 250 Stand-off (top or nearest rung)
 Feet max 22 rungs up
 No tie back
 Rung and spine on soft ground
 Rung level to floor surface
 Max 10 minutes at a time
 Avoid power lines.



- Tied.
- 1in4 / fully open.
- Locked up
- Loading marked
- Incline marked

367

LADDERS - COMPREHENSIVE MAINTENANCE



- Daily
- Weekly
- Inspection records
- Tags



368

OBSERVATIONS ?



369

OBSERVATIONS ?



370

OBSERVATIONS ?



371

HOP - UPS - COMPLIANT

Length x width: 600 x 600 (minimum)
Height: 500 (maximum)



Permit to use



Fall over? **Good**
Fall off? **Poor**



372

HOP - UPS - CCC

Compliant

600 x 600 min
< 500 ht
SWL 150kg (EN 131)

Competent

Permit to use
Justified (RAMS)
Light work
Tool Box Talk

Comp Maint

Daily pre-use
Weekly Competent
Tag / Locked



373

HOP - UPS -
COMPETENT



150 kgs



Short Duration ??
Light duty ??

Tool Box Talk
Evidence ?

Where no alternative possible...

... "constricted space."

374

HOP - UPS -
COMPREHENSIVE MAINTENANCE

Daily
Weekly
Tags
Register
maintained



Inspectors
Course

Secured when not in use

375

OBSERVATIONS ?



376

QUESTIONS?



377

ROPE ACCESS

378

ROPE ACCESS.. PERSONAL FALL PREVENTION



379

JUSTIFY DECISION ?

Alternatives from hierarchy?...
MACE rating?.....
Consider :-

- Ease of task when in suspension
- Risks to those below
- Handling of tools
- Reaction forces (drilling etc)
- Pace of task
- Exposure of Technician
- Rescue options (down & away)
- Other task-specific hazards

380

ROPE ACCESS

Compliant

IRATA CoP / BS 7985
 Many equipment Standards
 2No Anch 15kN (Annex F)
 “unquestionably reliable”

Alert**Competent**

IRATA Level 1-3
 Rescue Plan
 TWC for Anchor Designs
 Exclusion / Tether / Catch Net
 Watcher

**Comp Maint**

Anchor Protection
 Rope Protection
 TE 6 monthly



381

GUIDANCE



IRATA CoP / BS 7985

- Generally minimum is team of 3
Team of 2 permitted for simplest rescue
- 2 independent anchors
- Rescue provision
- All watched by another abseiler
- Exclusion zone with spotter




382

EQUIPMENT & STANDARDS




383

RIGGING




384

DEVIATIONS



385

“AID CLIMBING”




386

OBSERVATIONS ?



387

TEMPORARY ANCHORS



388

COMPETENCY SCHEME



Level 1 (entry)

- 4 days training
- 1 day assessment
- Log book

Level 2

- +12 months @ L1
- +1000 hours @ L1
- Rescue

Level 3 (Supervisor)

- +12 months @ L2
- +1000 hours @ L2
- First Aid
- Advanced Rescue



389

OBSERVATIONS ?



390

OBSERVATIONS ?



391

COMPETENCY

Query:

- **Team size**
- **Qualifications & experience** (logbook)
- **Anchors** (15kN x 2No)
- **Rope length** (down to access level)
- **Rope protection** (physical / thermal / chemical)
- **Monitoring & Communication**
- **Rescue**
- **Material feeding**
- **Tethering**
- **Ground concerns**
- **Timing** (rests / access)
- **Limits** (wind / weather / cold)



392


COMPREHENSIVE MAINTENANCE

- **User Inspection**
Before Each Occasion Of Use
- **Formal Inspection** (LOLER)
Every **6** months
- **Anchors**
Unquestionably reliable
- **Secure**
Anti-tamper & restricted access



393

CONTROLS BELOW



- Spotter (radio)
- Exclusion Zone
- Activity/Materials



394

POOR ANCHOR SELECTION & POSITIONING




395

ROPE STORAGE



396

UNQUESTIONABLE?...



397

RIGGED TO RESCUE



398

HIGHLY COMPETENT?!...



399

ROPE RIGGING & PROTECTION




400

EXCLUSION ZONES



401

OBSERVATIONS



402

OVER-LOADED?!...



403

QUESTIONS?



404

RISERS STRATEGY & MANAGEMENT

405

RISER MANAGEMENT : WHY THE FOCUS?

- Start early and run throughout project
- Change daily
- Involve many trades
- Divide responsibilities (horizontal/vertical)
- Varied methods and equipment
- Involve “live” services
- Varied shapes and sizes


Riser Strategy

- Required for every project
- Requires both floor (horizontal) & vertical protection
- No deviation without approval (BUD/HSL)



406

WORK AT HEIGHT PLANNING PROCESS



407

RISER STRATEGY

- **Developed at Tender / Pre-Construction**
 - Signed-off before frame design finalised - Utilise pre-fabrication & permanent works
 - “Real intent to use Best Practice” - Minimise activity & risk

- **Specify control measures**
 - Vertical & Horizontal - planning & positioning to reduce movement & drilling
 - Clear SWL on floors
 - Wheel stops / upstands to prevent wheeled access

408

RISER STRATEGY

Task-specific RAMS

- Minimise material falling risks
- For simultaneous activity
 - High Risk (e.g. intrusive works, use of tools equipment, materials)
Requires; floor protection, tethering, no access below
 - Low Risk (e.g. inspections, witness tests, labelling)
- Control cutting of decks.

Riser Co-Ordinator

- Single point of control
- Daily meetings & Co-ordination Board
- Permits / Access / Trade-to-trade hand-overs

409

RISER MANAGEMENT STRATEGY

6 Strategic Plan

Using the table below, list out every riser and explain the build strategy. Refer to the guidance notes on the following page and working examples for clarity. Please remember to drag formulas down in columns F,G,H,I to allow correct population of cells.

A	B	C	D	E	F	G	H	I
Riser Reference	Location	Riser wall / shaft Construction, incl headline construction strategy	Services to be installed	Headline Services installation strategy	Floor horizontal protection type	Edge vertical protection type (incl headline installation strategy)	Riser types	Risk Summary
2	Level 2 south building Grid x - y	Core concrete (back) Dry lining sides and front	Heating Chilled Drainage Condensate	Prefab modules lifted in by crane/bottom up (start ground floor)	F1 - a) Full modular prefabricated solution b) Modular prefabricated riser deck unit installed as the frame progresses	G2 - Scaffold based system 1.5m high with toe-board and netting	R2 - Individual or part preho services with separately installed platform	Caution
3	Level 1 south building Grid x - y	Core concrete (back) Dry lining sides and front	Busbar Containment Gas	Services installed floor by floor	F2 - Floor deck installation installed after the frame prior to the MEP commencing	G3 - 1.5m high post and panel system i.e. no rails	R1 - Fully modular prefabricated cassette with integral platform	Alert

410

RISER MANAGEMENT STRATEGY


6 Strategic Plan

Guidance Notes:

A.	B.	C.	D.	E.	F. Floor horizontal protection type	G. Edge vertical protection type	H. Riser types Key - vertical edge protection riser / shaft wall construction	I. Risk Summary
List out the same reference for each riser from the GA plans	Location references as per the project specific plans	Concrete, shaft wall, standard stud partition existing	Exact services in the riser	High Level Services Installation Strategy	Select from the choices below	Select from the choices below	Select a type of riser from the following and insert into the table. (If none of the below apply, select the blank cell and introduce a new reference)	Based on the selected methods give overall status as below - If two different warning categories are shown, choose the "lesser" of the two
					F1 - a) Full modular prefabricated solution b) Modular prefabricated riser deck unit installed as the frame progresses	G1 - 1.5m high triple rail system with toe-board and demountable panels	R1 - Fully modular prefabricated cassette with integral platform	Best Practice
					F2 - Floor deck installation installed after the frame prior to the MEP commencing	G2 - Scaffold based system 1.5m high with toe-board and netting	R2 - Individual or part prefab services with separately installed platform	Caution
					F3 - a) Timber based solution b) Scaffold based solution	G3 - 1.5m high post and panel system i.e. no rails	R3 - Ductwork	Alert
							R4 - Existing riser condition with platform	
							R5 - Existing riser condition without platform	
							R6 - Slots and holes formed in the riser	
							R7 - Slots and holes formed in slab - individual	

411

RISER MANAGEMENT STRATEGY



412

RISER MANAGEMENT STRATEGY


10 Sign Off

Guidance Note
 Strategy document to be produced and signed off by the Senior Leadership Team and communicated to "all staff" on the project
 This document must be completed during the tender stage if relevant
 A full review should be carried out immediately following appointment

	Name	Sign	Date
The Team			
Project Director	_____	_____	_____
Construction Lead	_____	_____	_____
MEP Lead	_____	_____	_____
Structural Lead	_____	_____	_____
Commercial Lead	_____	_____	_____
Design Lead	_____	_____	_____
Planning Lead	_____	_____	_____
Senior Team			
Construction Director	_____	_____	_____
H&S Lead	_____	_____	_____
Business Unit Director	_____	_____	_____



413

DAILY RISER COORDINATION BOARD



414

EXAMPLES OF 4D PLANS



415

RISER SIGNAGE




416

BEARING SURFACES



417

PROTECTION DIVIDED :



Horizontal Protection
4 Types

Vertical Protection
2 Types

Access Space Protection
1 Type



418

RISERS - COMMON MANAGEMENT CONTROLS

Horizontal & Vertical

- SSOW & competent to install/ adapt/ modify
- Authorisation for access
- Vertically alert (coordinated activities)
- Daily visual inspection (logged)
- Weekly formal inspection (tagged & logged)
- Permit to Work (MEP for charged services)
- Lighting (standard/ task/ emergency)
- Signage (large, robust, clear, pictograms)
- Change/Defect Mgt process (TWC)

Horizontal (additional)

- Load-bearing
- Physical control of access
- Tethering or containment
- Fire-rated (as required)

Vertical (additional)

- Compliant (BS EN 13374 / EPF / Mace)
- Other controls for Access (last resort)
- Changes in floor levels accommodated
- Gaps: Vert < 470, Hor < 100, TB < 6
- Can withstand plant impact or stop blocks
- No protrusions that could harm/ snag

419

HORIZONTAL FLOOR PROTECTION:



F1a - Pre-Fab Modules

Best Practice

F1b - Pre-Fab Deck

Best Practice

F2 - Deck Following Frame

Caution

F3 – Temporary / Scaffolding

Alert

420

F1A - PRE-FAB MODULES

- Self supporting with Integrated services
- Specialist team installation
- Permanent deck (load bearing) and EP
- Voids < 225mm (max)
- All EP designed to permit additional install
- Kick plates
- Fire rated
- Suitably load rating for works within

Best Practice



421

F1B - PRE-FAB DECK

Note Vertical EP must be in place for installation

- Solid Load bearing Deck or Grillage
- Installed as frame progresses
- Covers whole opening (wall to wall)
- Pre-cut & temp covers
- Support designed (no adapt needed)
- Eng support to frame
- Mesh as small as poss (< 225 or EP)
- Suitable bearing for works
- Kick plates
- Deck fire stopped as required



Best Practice



422

F2 DECK FOLLOWING FRAME

- Deck or grillage (whole area) load bearing
- Installed with building frame (from below?)
- Full cover and Cut on site
- Support designed to permit services
- Bearing suitable for works
- Small as possible mesh
- Fire stopped as required
- Kick plates
- EP etc if holes > 225
- Consider EP incorporated



Caution

423

F3 – TEMPORARY / SCAFFOLDING

- Designed for load and bearing
- Covers full opening
- Installed with frame (from below)
- Barriers to prevent overloading
- EP etc if holes > 225
- Toe boards, kick plates
- NOT fire “compartmentable” ...
use alternative

Alert



424

RISER ... EDGE VERTICAL PROTECTION



425

VERTICAL EDGE PROTECTION



Post & Panel with Rail 1.5m

G1 - Tube & Fitting (Scaffolding) 1.5m

G3 – Panel Only (No rails!) 1.5m
(no rail ... no access)

Caution

Alert

426

G1 - TUBE & FITTING (SCAFFOLDING)

1.5m above slab plus debris
Triple rail
Full debris, mesh, or net cover (containment)
Eng connections
Installed with building frame
Competent installers (CISRS)
Tubes capped, No protrusions.

Caution



427

G3 – PANEL ONLY (NO RAILS!)

1.5m above slab
 Only when no access needed
 Approved design/fixing
 No protrusions.



428

VERTICAL ACCESS SPACE PROTECTION

Controlled access process (permit to work/keys)
 Installed by competent persons
 Install ASAP
 Signage as before in good condition
 Robust defects/change process



Single Specialist Contractor

429

SINGLE SPECIALIST CONTRACTOR ACCESS:

- Proprietary system, covers full opening**
- Fitted ASAP .. Designed fixings (NOT friction)**
- EP in place before fitted**
- Lockable (inside turn/escape)**
- 2nd Fall prevention as required**
- Mesh unless fire rated**
- Vision panels or CCTV when active**
- Illuminated when occupied**
- Inspected and tagged < 7days**

Best Practice



430

QUESTIONS?



431

WORK AT HEIGHT PLAN

432

WORKING AT HEIGHT PLAN

What?

Management process to help Project Teams:-

- Select most appropriate WaH method for task
- Justify, Record, and Track the decision making

When?

- All projects

Who?

- All MACE Construction Teams

Where?

- InfoMACE (MG-H&S-PR 2800-V?)

433

WORKING AT HEIGHT PLAN

Working At Height Plan								
Project Number	Project Name	Date	Revision					
??	??	??	?					
Nr	Location	Description of Activity	Work at Height Solution	Company Responsible	Sign-off for ALERT		Wah Solution Affected by Activity?	Additional Control Measures Required / Notes Ref Equipment Choice
					OD	BUD		
A Project-Wide Control Measures								
1								
2								
3								
4								
5								
6								
7								
8								
B Task-Specific Control Measures								
9								

- All WaH tasks
- Each Location & Activity (Project/ Task Specific)
- Chosen method & Risk-Rating
- **ALERT** sign-off (link to email?)
- Solution affected by activity
- Tracks changes & implications
- Note references to Guidance

434

WORKING AT HEIGHT PLAN – OPTIONS

Climbing Screens (2.6.1) - Best Practice
Proprietary post and panel, with horizontal handrail and full height screen/netting (2.6.2) - Best Practice
Proprietary post and panel, with horizontal handrail (1.5 metre height) (2.6.3) - Caution
Triple rail tube and fitting edge protection with mesh panels (minimum 1.5 metre height) (2.6.4) - Caution
Proprietary post and panel minimum 1 metre, no rails (2.6.5) - Alert
Tube and fitting edge protection (scaffolding equipment) (2.6.6) - Alert
Fans/crash decks/tunnels (2.7.1) - Best Practice
Load bearing void protection (2.7.2) - Best Practice
Access scaffold (tube and fitting or system scaffold) (2.8.1) - Best Practice
Mast climbing working platforms (MCWP) (2.8.2) - Caution
Temporary suspended access equipment (TSAE) – temporary cradles (2.8.3) - Caution
Mobile elevated work platforms (MEWPS) (2.9.1) - Best Practice
Low level powered access equipment (up to five metres) (PAV) (2.9.2) - Best Practice
Low level manual access equipment - Peco/eco/nano type units (2.9.3) - Best Practice
Mobile Aluminium Towers (2.10.1) - Caution
Aluminium podium towers/podium steps (2.10.2) - Caution
Delta Decks (2.10.3) - Caution
Ladders and step-ladders (2.10.4) - Alert
Extra wide hop-ups (2.10.5) - Alert
Work restraint systems (2.11.1) - Caution
Fall arrest systems (2.11.2) - Alert
Rope access equipment (2.11.3) - Alert

- Drop down (restrictive).
- Discuss with ESH Mgt if not available.
- Company responsible for implementation

435

WORKING AT HEIGHT PLAN

Project Number:		Project Name:		Date:		Revision:		Working At Height Plan				
123		Test Build		01/01/2023		A						
Nr	Location	Description of Activity	Work at Height Solution	Company Responsible	Sign-off for ALERT		WAH Solution Affected by Activity?			Additional Control Measures Required / Notes Ref Equipment Choice		
					OD	BUD	Y/N	Explanation				
A Project-Wide Control Measures												
1	RC Frame	Construction of in-situ frame	Climbing Screens (2.6.1) Best Practice	GCL	x	x	No	x	All as per Mace standards			
2												
3												
4												
5												
6												
7												
8												
B Task-Specific Control Measures												
9	Cladding Façade	Application of mastic sealant	Rope access equipment (2.11.3) - Alert	RA Abseil Ltd	1/11/22 - confirm email	2/11/22 - confirm email	Yes	Missed design opportunity to specify cladding system which did not require sealant post-install		All as per Mace standards		

436

WORKING AT HEIGHT MANAGEMENT PROCESS

437

MANAGEMENT PROCESS FOR WORKING AT HEIGHT

- **Live document - reviewed at least every 4 weeks**
- **Must be reflective of on site activities**
- **Within Construction Phase Plan of the PDP**
- **Communicated to all Operatives during DABs/ NABs (evidence required)**




438

WORKING AT HEIGHT AUDIT / REVIEW

439

AUDIT PROCESS/REVIEW

Safety first. Second nature. 

Project Name:	1807 Peninsula South	Project Number:	0200	Date:	14/05/2026			
UNRESTRICTED								
© Mace Ltd. Confidential & Not for Distribution								
Stop Off For ALERT								
Location	Activity	Work at Height Solution in Place	Company Responsible	BUD	WAH Solution effected by Activity?	Comments	Additional Control Measures	
1	Control of site	Slipform	AB Contractor		Yes	Review prior WAH Solution		
2	Slab formation	Increase to edge protection. Additional post - removal of double height deck from in preparation of ceiling	AB Contractor		No			
3	External cladding	Tubular guardrail system - no full height fabric screen - Continues (2.3)	AB Contractor		No			
4	Formation of floor	Execution of steel frame	MG Builders Ltd		No			
5	Formation of floor	Execution of steel frame	MG Builders Ltd		No		Policy implemented as per WAH Guidelines & Standards	
6	Formation of floor	Execution of steel frame	MG Builders Ltd		No		Policy implemented as per WAH Guidelines & Standards	
7	Floor 1,2,3,4,5	Installation of metal decking	KN Abrahams Ltd	BUD has reviewed and authorized Alert in small dated SOST	Reviewed and authorized Alert in small dated SOST	Yes	Review prior WAH Solution	Exclusion zone implemented as per WAH Guidelines & Standards
8	Floor 1,2,3,4,5	Installation of metal decking	KN Abrahams Ltd	BUD has reviewed and authorized Alert in small dated SOST	Reviewed and authorized Alert in small dated SOST	No		

Mace Information Handles Classification/Declassification

- Note:-**
- Dated (4 weeks)
 - **ALERT** sign-off
 - Additional measures

440

AUDIT QUESTIONS:-

- Has the Mace Project Team received the WAH training?
- Does the Project Team know where to find the latest WAH Guidelines & Standards (MG-H&S-PR-2800-V#)?
- Has the WaH Plan been completed for the project?
- Where the WAH Plan identifies risk at 'Alert' level, – has
 - this been communicated and
 - specific approval been granted by the BUD and HSL?
- Has the latest WAH Plan been briefed to Mace employees/ contractors?

441

AUDIT QUESTIONS:-

- Has the latest WAH Plan been briefed to supply chain managers and supervisors?
- Has the WAH Plan been reviewed on a monthly basis?
- At the time of inspection, have all WAH tasks been captured within the WAH Plan?
- Is a permit to work procedure in place for all relevant WAH tasks (e.g. ladder use/ riser access etc)?
- Is safe WAH behaviour observed on site at all times during inspection?

442

QUESTIONS?



443