



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Smith County Mississippi at the Smith County Courthouse in Raleigh Mississippi (P.O. Box 160, Raleigh, MS 39153 / 201 Courthouse Square, Raleigh, MS 39153), until 10:00 A.M. on the 29th day of May, 2026 and shortly thereafter publicly opened for the construction of 0.065 miles of BOX BRIDGE and APPROACHES on the Smith County Road 504 being known as Eastern Federal Lands (EFL) Project No. EFL-0330(14)B LPA / 108787-701000 in Smith County Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

<u>ROADWAY ITEMS:</u>	<u>QUANTITY</u>	<u>UNIT</u>
MOBILIZATION	1.000	LS
CLEARING AND GRUBBING	1.000	LS
REMOVAL OF BRIDGE AT STA. 145+77.0	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	2,090.000	CY
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	683.000	CY
CHANNEL EXCAVATION (FM)	257.000	CY
EXCESS EXCAVATION (FM)	300.000	CY
GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B)	466.000	CY
SIZE (I) STABILIZER AGGREGATE, COARSE	6.000	CY
HOT MIX ASPHALT, ST 12.5 MM	99.000	TON
HOT MIX ASPHALT, ST 19 MM	199.000	TON
CLASS "C" STRUCTURAL CONCRETE	60.000	CY
48" REINFORCED CONCRETE PIPE, CLASS III	64.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	1.000	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL)	0.133	MI
4" WIDE THERMOPLASTIC TRAFFIC STRIPE (CONTINUOUS YELLOW) (120 MIL)	700.000	LF
TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	6.000	EA
<u>EROSION CONTROL ITEMS:</u>	<u>QUANTITY</u>	<u>UNIT</u>
SOLID SODDING	175.000	SY
HYDROSEEDING	0.740	AC
TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84)	600.000	LF
WATTLES, 20" DIAMETER	100.000	LF
<u>BRIDGE ITEMS:</u>	<u>QUANTITY</u>	<u>UNIT</u>
TEMPORARY STREAM DIVERSION	1.000	EA
BOX BRIDGE CONCRETE, CLASS "BB"	272.530	CY
REINFORCEMENT	51,920.000	LB
LOOSE RIPRAP, 300 LB.	140.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.21-0.43 NON-WOVEN	350.000	SY

PROJECT NO.
Smith

EFL-0330(14)B LPA / 108787-701000
COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 75 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Smith County, Richmond L. Alexander, P.E. , the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

The Plans and Contract Documents may be purchased at 1724B 23rd Avenue, Meridian, MS at a cost of Fifty Dollars (\$50) Non-Refundable for the PLANS and Fifty Dollars (\$50) Non-Refundable for the CONTRACT DOCUMENTS. The population of this county is less than 20,000.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Smith County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Danny Arender, President
Smith County Board of Supervisors