



OFFICE OF STATE AID ROAD CONSTRUCTION (OSARC)
AND
COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County Mississippi at the Kemper County Courthouse located at 280 Veterans Street in DeKalb, Mississippi, until 10:00 AM on the 30th day of September 2026 and shortly thereafter publicly opened for the construction of 0.179 miles of BRIDGE and APPROACHES on the Old Jackson Road being known as State Aid Program (SAP) Project No. SAP-35(77) in Kemper County Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS

ROADWAY ITEMS:

	<u>QUANTITY</u>	<u>UNIT</u>
Mobilization	1.000	LS
Clearing and Grubbing	1.000	LS
Removal of Bridge at Sta. 20+17.00	1.000	UN
Removal of Bridge at Sta. 26+83.00	1.000	UN
Removal of Pipe (All Sizes)	17.000	LF
Unclassified Excavation (FM)	347.000	CY
Borrow Excavation (Contractor-Furnished FME, Class 9)	788.000	CY
Granular Material (LVM) (Class 9, Group B)	583.000	CY
Crushed Stone (Size 610) (LVM)	134.000	CY
Asphalt, ST, 12.5 mm	139.000	TON
Asphalt, ST, 19 mm	275.000	TON
18" Reinforced Concrete Pipe, Class III	24.000	LF
Guardrail, W-Beam	150.000	LF
Guardrail, Bridge End Section, Type I Thrie-Beam	8.000	EA
Guardrail, Terminal End Section	8.000	EA
Maintenance of Traffic	1.000	LS
Additional Construction Signs	0.000	SF
4"-Wide Thermoplastic Edge Stripe (Continuous White) (90 MIL)	0.359	MI
4"-Wide Thermoplastic Traffic Stripe (Continuous Yellow) (120 MIL)	1,900.000	LF
Two-Way Yellow Reflective High-Performance Raised Markers	12.000	EA
Reflectorized Traffic Object Marker (Encapsulated Lens) (Type 3)	8.000	EA

EROSION CONTROL ITEMS:

	<u>QUANTITY</u>	<u>UNIT</u>
Solid Sodding	248.000	SY
Excelsior Blanket	750.000	SY
Hydroseeding, Temporary Grassing	0.930	AC
Temporary Silt Fence (Type II) (AOS 0.15-0.84)	1,500.000	LF
Wattles, 20"	250.000	LF
Loose Riprap, (200 LB.)	200.000	TON

BRIDGE A ITEMS:

	<u>QUANTITY</u>	<u>UNIT</u>
Test Pile, 14", Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	590.000	LF
18" Preformed Pile Hole	400.000	LF
19' Precast Concrete Slab Unit, 3.5' Interior	18.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	6.000	EA
Precast Concrete Barrier Rail	114.000	LF
31' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.000	EA
31' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
9.25' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 LB.	230.000	TON
Geotextile Under Riprap, Non-Woven, Type V, AOS < 0.43	252.000	SY

BRIDGE B ITEMS:

	<u>QUANTITY</u>	<u>UNIT</u>
Test Pile, 14", Prestressed Concrete	2.000	EA
Conventional Static Pile Load Test	0.000	EA
14" Prestressed Concrete Piling	590.000	LF
18" Preformed Pile Hole	400.000	LF
19' Precast Concrete Slab Unit, 3.5' Interior	18.000	EA
19' Precast Concrete Slab Unit, 3.5' Exterior	6.000	EA
Precast Concrete Barrier Rail	114.000	LF
31' Precast Concrete Cap, Intermediate Unit, Concrete Pile	2.000	EA
31' Precast Concrete Cap, End Unit, Concrete Pile	2.000	EA
9.25' Precast Concrete Wing	4.000	EA
Loose Riprap, 300 LB.	230.000	TON
Geotextile Under Riprap, Non-Woven, Type V, AOS < 0.43	252.000	SY

PROJECT NO.
Kemper

SAP-35(77)
COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 110 Working Days

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement; minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County, Phillip McDonald, P.E. , the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

The plans and contract documents can be purchased from Engineering Plus at 1724B 23rd Avenue; Meridian, MS, phone: 601-693-4234 at a cost of fifty dollars (\$50) Non-Refundable for the PLANS and a cost of fifty dollars (\$50) Non-Refundable for the CONTRACT DOCUMENTS. The population of this county is less than 20,000.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Lee McDonald, President
Kemper County Board of Supervisors