

Bid Tabulation

**Village of Fort Jennings
Street Improvements**

**Bockrath & Associates
Engineering and Surveying, LLC**

					Bidding Contractor >>>>>		Ward Construction	
Ref. No.	ODOT Item No.	Item Description	Quantity	Unit	Total Unit Cost	Subtotal	Total Unit Cost	Subtotal
1	253	Asphalt Pavement Repair (Oak Street - 36'x10')	40	CY	\$ 80.00	\$ 3,200.00		\$ -
2	254	2" Pavement Planning - Full Width	4,722	SY	\$ 3.75	\$ 17,707.50		\$ -
3	407	Tack Coat (0.075 GAL/SY)	354	GAL	\$ 3.00	\$ 1,062.00		\$ -
4	407	Tack Coat for Intermediate Course (0.05 GAL/SY)	236	GAL	\$ 3.00	\$ 708.00		\$ -
5	441	1" Asphalt Conc. Inter. Course, Type 1,(449) PG 64-22	131	CY	\$ 280.00	\$ 36,680.00		\$ -
6	441	1" Asphalt Conc. Surface, Type 1, (449) PG 64-22	131	CY	\$ 280.00	\$ 36,680.00		\$ -
7	604	Manhole Adjustment to Grade with Steel Riser Ring	1	EA	\$ 500.00	\$ 500.00		\$ -
8	614	Maintaining Traffic	1	LS	\$ 2,000.00	\$ 2,000.00		\$ -
9	624	Mobilization	1	LS	\$ 2,000.00	\$ 2,000.00		\$ -
10	642	Pavement Marking - (Crosswalks & Stop Bars)	1	LS	\$ 1,500.00	\$ 1,500.00		\$ -
Base Bid Total:					\$	102,037.50	\$	-

