

ADDENDUM NO. 1

Hickory Street Reconstruction (OPWC Round 39) VILLAGE OF OTTAWA, OHIO

ISSUED TO:
Current Plan Holders & Affiliated Reporting Companies

Date Issued: Tuesday, July 8th, 2025
Number of Pages: 14

ISSUED BY:
Bockrath & Associates Engineering and Surveying, LLC
115 S. Fair Avenue, Suite A
Ottawa, Ohio 45875
Phone: 419-523-5789
Fax: 419-523-5799

An Addendum Receipt must be Returned prior to Bid Opening.

Plan Holders

The current official plan holders list is attached

Bid Opening Date Change

The Bid Opening Date is changed from Thursday July 10th, 2025, to **Thursday July 24th, 2025, at 10:30 am**

Exhibit A of the Bid Form

This project will now have 2 Exhibit A's of the Bid Form which are included with this Addendum #1. Do not use the original Exhibit A of the Bid Form.

- 1) Addendum #1 - **Proposal A** Bid Form with a completion Date of **November 14, 2025.**
- 2) Addendum #1 - **Proposal B** Bid Form with a completion Date of **May 29, 2026.**

Only one or the other proposal will be awarded. The work is to be completed within 60 days of beginning work for either completion date. Contractors may submit either one or both proposals.

ADDENDUM RECEIPT

Plan holder is required fill out the bottom section and fax or email to issuing office to acknowledge receipt of this addendum.

I hereby acknowledge receipt of
Addendum Number 1
issued for:

Hickory Street Reconstruction
(OPWC Round 39)
VILLAGE OF OTTAWA, OHIO

ISSUED BY:

Bockrath & Associates Engineering and Surveying, LLC
115 S. Fair Avenue, Suite A
Ottawa, Ohio 45875
Phone: 419-523-5789
Fax: 419-523-5799

Please note the above project bid date is changed to:
Thursday, July 24, 2025, 10:30 a.m.

An Addendum Receipt must be Returned prior to Bid Opening.

Remit to info@bockrath-es.com troy@bockrath-es.com or fax to 419-523-5799

Receipt of Addendum Acknowledgement

Company Name: _____

Signature: _____

Printed Name: _____

Date: _____

Plan Holders
Village of Ottawa
Hickory Street Reconstruction (OPWC Rd. 39)

~~Bid Date: Thursday, July 10, 2025, at 10:30 a.m.~~

Bid Date: Thursday, July 24, 2025, at 10:30 a.m.

Updated 07/08/25 – Project #24-247

Village of Ottawa, Ohio (owner)
136 North Oak St.
Ottawa, Ohio 45875
Ph: 419-523-5020
jniese@ottawaohio.us

Dangler Excavating
342 W. Wall St.
Paulding, Ohio 45879
Ph. 419-670-4711
michael_dangler@danglerexcavating.com

Ward Construction Co.
385 Oak Street
Leipsic, OH 45856
Ph: 419-943-2450
mrosebrock@wardcompanies.com

Hohenbrink Excavating LLC
684 Tawa Drive
Ottawa, OH 45875
Ph: 419-427-3444
nhohenbrink@hohenbrinkexcavating.com

Fenson Contracting LLC
17670 SR 190
Fort Jennings, OH 45844
PH: 419-286-2458
nolan.kaverman@fensoncontracting.com

Smith Paving & Excavating Inc.
4426 N. Old State Road
Norwalk, Ohio 44857
Ph. 419-668-4165
ddilgerspe@aol.com

Advanced Excavating & Demolition. LLC
651 TR 102
McComb, Ohio 45858
Ph: 567-376-0368
jacob@advanceddemolition.us

Proposal A - Final Completion Date: November 14, 2025

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit		Total Unit Cost	Subtotal
1	201	Clearing & Grubbing	1	LS			
		Total Unit Cost per LUMP SUM in Words:					
2	202	Street Signs Removed, Stored and Reinstalled	2	EA			
		Total Unit Cost per EACH in Words:					
3	202	24" Tree & Stump Removed	1	EA			
		Total Unit Cost per EACH in Words:					
4	202	Concrete Drive Removed	82	SY			
		Total Unit Cost per SQUARE YARDS in Words:					
5	202	Concrete Walk Removed	448	SY			
		Total Unit Cost per SQUARE YARDS in Words:					
6	202	Concrete Curb Removed	790	LF			
		Total Unit Cost per LINEAR FEET in Words:					
7	202	Catch Basins Removed & Reused CB28 & CB399	2	EA			
		Total Unit Cost per EACH in Words:					
8	203	Roadway Excavation - Approx. 18" Deep	1,030	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
9	204	Subgrade Compaction	2,386	SY			
		Total Unit Cost per SQUARE YARDS in Words:					
10	204	Proof Rolling	4	HRS			
		Total Unit Cost per HOURS in Words:					
11	254	Pavement Removed including Saw Cut (Existing Road)	1,556	SY			
		Total Unit Cost per SQUARE YARDS in Words:					

Village of Ottawa
Hickory Street Reconstruction
Proposal A - Final Completion Date: November 14, 2025

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit		Total Unit Cost	Subtotal
12	254	Pavement Planing - Butt Joints -6' min.	98	SY			
		Total Unit Cost per SQUARE YARDS in Words:					
13	301	3" Asphalt Base, PG 64-22	125	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
14	304	9" Aggregate Base	375	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
15	407	Tack Coat (0.075 GAL/SY)	100	GAL			
		Total Unit Cost per GALLON in Words:					
16	407	Tack Coat for Intermediate Course (0.05 GAL/SY)	66	GAL			
		Total Unit Cost per GALLON in Words:					
17	411	4" Aggregate Base - Sidewalks	70	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
18	411	4" Aggregate Base - Concrete Drives	16	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
19	441	1-3/4" Asphalt Conc. Inter., Type 1,(448) PG 64-22	73	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
20	441	1-1/4" Asphalt Conc. Surface, Type 1, (448) PG 64-22	63	CY			
		Total Unit Cost per CUBIC YARDS in Words:					
21	605	4" Storm Sewer Underdrain w/Sock	710	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
22	608	Curb Ramp, ODOT Type 2, w/ Det. Warning Panel	13	EA			
		Total Unit Cost per EACH in Words:					

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit		Total Unit Cost	Subtotal
23	608	6" Reinforced Concrete Drive Apron - Includes 2 Alleys	1,143	SF			
		Total Unit Cost per SQUARE FEET in Words:					
24	608	4" Reinforced Concrete Sidewalk	5,093	SF			
		Total Unit Cost per SQUARE FEET in Words:					
25	609	Combination Curb & Gutter (24"), Type 2	891	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
26	611	12" PVC SDR 35 Storm Sewer, under Pavement CB28	5	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
27	611	Catch Basin 2-2B, Curb Inlet w/EJ7022 Hood & Sinusoidal Grate	1	EA			
		Total Unit Cost per EACH in Words:					
28	611	Storm Sewer Manhole adjusted to grade w/ Mr. manhole Collar	1	EA			
		Total Unit Cost per EACH in Words:					
29	611	Sanitary Sewer Manhole adjusted to grade w/ Mr. manhole Collar	1	EA			
		Total Unit Cost per EACH in Words:					
30	611	Hydrant Watch Valve Adjusted to Grade	1	EA			
		Total Unit Cost per EACH in Words:					
31	611	Connect to existing Storm Sewer (Contingency)	2	EA			
		Total Unit Cost per EACH in Words:					
32	611	Storm Sewer Removed Under Pavement (Contingency)	50	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
33	611	10" Storm Sewer, SDR 35 Under Pavement (Contingency)	50	LF			
		Total Unit Cost per LINEAR FOOT in Words:					

Village of Ottawa
Hickory Street Reconstruction
Proposal A - Final Completion Date: November 14, 2025

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit		Total Unit Cost	Subtotal
34	611	12" Storm Sewer, SDR 35 Not Under Pavement (Contingency)	50	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
35	611	8" Storm Sewer, SDR 35 Under Pavement (Contingency)	50	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
36	611	8" Storm Sewer, SDR 35 Not Under Pavement (Contingency)	50	LF			
		Total Unit Cost per LINEAR FOOT in Words:					
37	614	Maintaining Traffic	1	LS			
		Total Unit Cost per LUMP SUM in Words:					
38	624	Mobilization	1	LS			
		Total Unit Cost per LUMP SUM in Words:					
39	641	Pavement Marking - Crosswalks, Stop Bars & Parking	1	LS			
		Total Unit Cost per LUMP SUM in Words:					
40	641	Pavement Marking - ADA Parking Symbol	1	EA			
		Total Unit Cost per EACH in Words:					
41	641	"ONE WAY" Street Sign & Post	3	EA			
		Total Unit Cost per EACH in Words:					
42	641	"DO NOT ENTER" Street Sign & Post	1	EA			
		Total Unit Cost per EACH in Words:					
43	653	Topsoil Furnished and Placed (Contingency)	20	CY			
		Total Unit Cost per CUBIC YARD in Words:					
44	659	Seeding / Mulching & Restoration	1	LS			
		Total Unit Cost per LUMP SUM in Words:					

Proposal A - Final Completion Date: November 14, 2025

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit	Total Unit Cost	Subtotal
45	832	Erosion Control (Inlet Projection Dandy Bags)	1	LS		
		Total Unit Cost per LUMP SUM in Words:				
46	Special	Testing Allowance	1	LS	\$ 10,000.00	\$ 10,000.00
		Total Unit Cost per LUMP SUM in Words:				
47	Special	MIRAFI 500X or approved equal	16,133	SF		
		Total Unit Cost per SQUARE FOOT in Words:				
Proposal A (Final Completion Date Nov. 14, 2025) Bid Total:						
Proposal A Bid Total in Words:						

Submitted By: _____

Name of Person Responsible for Bid

Name of Company Submitting Bid

Bockrath & Associates
Engineering and Surveying, LLC
115 S. Fair Avenue, Suite A - Ottawa - Ohio 45875
Phone: 419.523.5789

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit			Total Unit Cost	Subtotal
1	201	Clearing & Grubbing	1	LS				
		Total Unit Cost per LUMP SUM in Words:						
2	202	Street Signs Removed, Stored and Reinstalled	2	EA				
		Total Unit Cost per EACH in Words:						
3	202	24" Tree & Stump Removed	1	EA				
		Total Unit Cost per EACH in Words:						
4	202	Concrete Drive Removed	82	SY				
		Total Unit Cost per SQUARE YARDS in Words:						
5	202	Concrete Walk Removed	448	SY				
		Total Unit Cost per SQUARE YARDS in Words:						
6	202	Concrete Curb Removed	790	LF				
		Total Unit Cost per LINEAR FEET in Words:						
7	202	Catch Basins Removed & Reused CB28 & CB399	2	EA				
		Total Unit Cost per EACH in Words:						
8	203	Roadway Excavation - Approx. 18" Deep	1,030	CY				
		Total Unit Cost per CUBIC YARDS in Words:						
9	204	Subgrade Compaction	2,386	SY				
		Total Unit Cost per SQUARE YARDS in Words:						
10	204	Proof Rolling	4	HRS				
		Total Unit Cost per HOURS in Words:						
11	254	Pavement Removed including Saw Cut (Existing Road)	1,556	SY				
		Total Unit Cost per SQUARE YARDS in Words:						

Village of Ottawa
Hickory Street Reconstruction

Bockrath & Associates
Engineering and Surveying, LLC

Proposal B - Final Completion Date: May 29, 2026

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit	Total Unit Cost	Subtotal
12	254	Pavement Planing - Butt Joints -6' min.	98	SY		
		Total Unit Cost per SQUARE YARDS in Words:				
13	301	3" Asphalt Base, PG 64-22	125	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
14	304	9" Aggregate Base	375	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
15	407	Tack Coat (0.075 GAL/SY)	100	GAL		
		Total Unit Cost per GALLON in Words:				
16	407	Tack Coat for Intermediate Course (0.05 GAL/SY)	66	GAL		
		Total Unit Cost per GALLON in Words:				
17	411	4" Aggregate Base - Sidewalks	70	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
18	411	4" Aggregate Base - Concrete Drives	16	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
19	441	1-3/4" Asphalt Conc. Inter., Type 1,(448) PG 64-22	73	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
20	441	1-1/4" Asphalt Conc. Surface, Type 1, (448) PG 64-22	63	CY		
		Total Unit Cost per CUBIC YARDS in Words:				
21	605	4" Storm Sewer Underdrain w/Sock	710	LF		
		Total Unit Cost per LINEAR FOOT in Words:				
22	608	Curb Ramp, ODOT Type 2, w/ Det. Warning Panel	13	EA		
		Total Unit Cost per EACH in Words:				

Village of Ottawa
Hickory Street Reconstruction
Proposal B - Final Completion Date: May 29, 2026

Bockrath & Associates
Engineering and Surveying, LLC

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit			Total Unit Cost	Subtotal
23	608	6" Reinforced Concrete Drive Apron - Includes 2 Alleys	1,143	SF				
		Total Unit Cost per SQUARE FEET in Words:						
24	608	4" Reinforced Concrete Sidewalk	5,093	SF				
		Total Unit Cost per SQUARE FEET in Words:						
25	609	Combination Curb & Gutter (24"), Type 2	891	LF				
		Total Unit Cost per LINEAR FOOT in Words:						
26	611	12" PVC SDR 35 Storm Sewer, under Pavement CB28	5	LF				
		Total Unit Cost per LINEAR FOOT in Words:						
27	611	Catch Basin 2-2B, Curb Inlet w/EJ7022 Hood & Sinusoidal Grate	1	EA				
		Total Unit Cost per EACH in Words:						
28	611	Storm Sewer Manhole adjusted to grade w/ Mr. manhole Collar	1	EA				
		Total Unit Cost per EACH in Words:						
29	611	Sanitary Sewer Manhole adjusted to grade w/ Mr. manhole Collar	1	EA				
		Total Unit Cost per EACH in Words:						
30	611	Hydrant Watch Valve Adjusted to Grade	1	EA				
		Total Unit Cost per EACH in Words:						
31	611	Connect to existing Storm Sewer (Contingency)	2	EA				
		Total Unit Cost per EACH in Words:						
32	611	Storm Sewer Removed Under Pavement (Contingency)	50	LF				
		Total Unit Cost per LINEAR FOOT in Words:						
33	611	10" Storm Sewer, SDR 35 Under Pavement (Contingency)	50	LF				
		Total Unit Cost per LINEAR FOOT in Words:						

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit	Total Unit Cost	Subtotal
34	611	12" Storm Sewer, SDR 35 Not Under Pavement (Contingency)	50	LF		
		Total Unit Cost per LINEAR FOOT in Words:				
35	611	8" Storm Sewer, SDR 35 Under Pavement (Contingency)	50	LF		
		Total Unit Cost per LINEAR FOOT in Words:				
36	611	8" Storm Sewer, SDR 35 Not Under Pavement (Contingency)	50	LF		
		Total Unit Cost per LINEAR FOOT in Words:				
37	614	Maintaining Traffic	1	LS		
		Total Unit Cost per LUMP SUM in Words:				
38	624	Mobilization	1	LS		
		Total Unit Cost per LUMP SUM in Words:				
39	641	Pavement Marking - Crosswalks, Stop Bars & Parking	1	LS		
		Total Unit Cost per LUMP SUM in Words:				
40	641	Pavement Marking - ADA Parking Symbol	1	EA		
		Total Unit Cost per EACH in Words:				
41	641	"ONE WAY" Street Sign & Post	3	EA		
		Total Unit Cost per EACH in Words:				
42	641	"DO NOT ENTER" Street Sign & Post	1	EA		
		Total Unit Cost per EACH in Words:				
43	653	Topsoil Furnished and Placed (Contingency)	20	CY		
		Total Unit Cost per CUBIC YARD in Words:				
44	659	Seeding / Mulching & Restoration	1	LS		
		Total Unit Cost per LUMP SUM in Words:				

Proposal B - Final Completion Date: May 29, 2026

Ref. No.	ODOT Item No.	Item Description - S. Hickory St.	Quantity	Unit	Total Unit Cost	Subtotal
45	832	Erosion Control (Inlet Projection Dandy Bags)	1	LS		
		Total Unit Cost per LUMP SUM in Words:				
46	Special	Testing Allowance	1	LS	\$ 10,000.00	\$ 10,000.00
		Total Unit Cost per LUMP SUM in Words:				
47	Special	MIRAFI 500X or approved equal	16,133	SF		
		Total Unit Cost per SQUARE FOOT in Words:				
Proposal B (Final Completion Date May 29, 2026) Bid Total:						
Proposal B - Bid Total in Words:						

Submitted By:	Name of Person Responsible for Bid	Name of Company Submitting Bid
---------------	------------------------------------	--------------------------------

Bockrath & Associates
Engineering and Surveying, LLC
115 S. Fair Avenue, Suite A - Ottawa - Ohio 45875
Phone: 419.523.5789