

Architecture
Structural
Geotechnical



Materials Testing
Forensic
Civil/Planning

ROCKY MOUNTAIN GROUP
EMPLOYEE OWNED

SUBSURFACE SOIL INVESTIGATION

**Sunset Ridge Subdivision
Severance, Colorado**

PREPARED FOR:

**Journey Homes, LLC
7251 W. 20th St., L-200
Greeley, CO 80634**

JOB NO. 180135

March 30, 2021

Respectfully Submitted,

RMG – Rocky Mountain Group

**Lauren Caruso, P.E.
Geotechnical Project Engineer**



TABLE OF CONTENTS

PROJECT DESCRIPTION AND SCOPE.....	3
Project Location.....	3
Project Description.....	3
Scope of Work	3
Existing Site Conditions	3
FIELD INVESTIGATION AND LABORATORY TESTING.....	4
Subsurface Investigation.....	4
Laboratory Testing.....	4
SUBSURFACE CONDITIONS	4
Soil and Bedrock Profile.....	4
Groundwater	5
CONCLUSIONS.....	5
SITE DEVELOPMENT AND EARTHWORK	6
Site Preparation.....	6
Excavations.....	6
Geotechnical Considerations	6
Foundation Wall Backfill.....	7
Structural Fill	7
Moisture Conditioned Structural Fill	8
FOUNDATION OPTIONS	9
Anticipated Foundation Systems	9
Open Excavation Observations.....	9
INTERIOR FLOOR SYSTEMS.....	9
Interior Floor Slabs	9
Interior Partitions	9
LATERAL EARTH PRESSURES.....	10
SURFACE GRADING AND DRAINAGE.....	10
Grading and Irrigation.....	10
Perimeter Drain.....	11
CONCRETE	11
CLOSING	11
FIGURES	
Site Vicinity Map.....	1
Boring Location Plan.....	2
Test Boring Logs	3-55
Explanation of Test Boring Logs.....	56
Summary of Laboratory Test Results	57
Soil Classification Data.....	58-64
Swell/Consolidation Test Results	65-81

PROJECT DESCRIPTION AND SCOPE

Project Location

The project lies in part of the northeast quarter of Section 3, Township 6 North, Range 67 West of the 6th Principal Meridian. The site is generally located to the west of the Town of Severance in Weld County, Colorado. The site is located south of County Road 74 and east of County Road 21. The approximate location of the site is shown in the Site Vicinity Map on Figure 1.

Project Description

The project is to consist of the development of a parcel of vacant, semi-developed property for residential use. It is our understanding that this development will be occupied by single family residences with no multifamily units planned at this time. RMG was retained to evaluate the subsurface conditions for the 105 lots within the proposed Sunset Ridge Subdivision.

Scope of Work

RMG was retained to assess the soil conditions and develop geotechnical engineering recommendations to support the residential land development for the proposed project. Our scope of services consisted of a field investigation, laboratory testing, engineering analysis, and report preparation.

This report presents geotechnical engineering recommendations for the design of foundations for the single family residences located on the lots listed above. The recommendations in this report are also contingent upon completion of an Open Excavation Observation by RMG, prior to construction of the foundations in order to verify subsurface conditions for the specific excavated site.

The following is excluded from the scope of this report including but not limited to geologic, natural and environmental hazards such as landslides, unstable slopes, seismicity, snow avalanches, water flooding, corrosive soils, erosion, radon, wild fire protection, hazardous waste and natural resources.

Existing Site Conditions

At the time of our field exploration overlot grading was being completed. Water and sewer connections were being installed during our investigation throughout the subdivision. Curb and gutter had not been installed and the roads had not been paved. Topography of the site generally sloped gently down from the northwest to the south and southeast portion of the site. Vegetation was not present at the site due to the overlot grading. The surrounding areas consist of residential properties on all sides of the subdivision.

FIELD INVESTIGATION AND LABORATORY TESTING

The information included in this report has been compiled from field reconnaissance, exploratory soil borings and soil laboratory testing. Monitoring programs, which typically include instrumentation and/or observations for surface water flows, slope stability, subsidence, and similar conditions, are not known to exist and were not considered applicable for the scope of this report.

Subsurface Investigation

The subsurface conditions on the site were investigated by drilling 105 exploratory test borings, approximately one bore on every lot in this investigation. The bores were placed near the center of each lot investigated. The approximate locations of the test borings are presented in the Boring Location Plan on Figure 2.

The test borings were advanced with a truck-mounted, continuous-flight auger drill rig to depths of about 20 feet below the existing ground surface (bgs). Soil samples were obtained from the test borings in general accordance with ASTM D-3550 utilizing a 2½-inch OD modified California sampler. The approximate depth of groundwater was investigated in each of the test borings at the time of drilling. The static groundwater levels were measured following the completion of drilling. The Test Boring Logs are presented in Figures 3 through 55. An Explanation of Test Boring Logs is presented in Figure 56.

Laboratory Testing

The moisture content for the recovered samples was obtained in the laboratory. Grain-size analysis, Atterberg Limits, and swell/consolidation tests were performed on selected samples for purposes of classification and to develop pertinent engineering properties. A Summary of Laboratory Test Results is presented in Figure 57. Soil Classification and Atterberg Test Results are presented in Figures 58 through 64. Swell/Consolidation Test Results are presented in Figures 65 through 81.

SUBSURFACE CONDITIONS

Soil and Bedrock Profile

The subsurface materials encountered in the test borings were classified using the Unified Soils Classification System (USCS). The subsurface materials encountered in the test borings generally consisted of an upper fill material comprised of stiff to very stiff sandy clay as well as native very loose to medium dense silty to clayey sand. Underlying the surface material, weathered to very hard siltstone bedrock was encountered. The siltstone contained thinly interbedded claystone lens in many of the test borings. The siltstone bedrock was encountered in 78 of the test borings at depths ranging from approximately seven feet to 18 feet below existing grade. The shallow siltstone was encountered near anticipated foundation depths on lots predominately located on Blocks 2 and 3.

Additional descriptions and the interpreted distribution (approximate depths) of the subsurface materials are presented on the Test Boring Logs. The classifications shown on the logs are based upon the engineer's classification of the samples at the depths indicated. Stratification lines shown on the logs represent the approximate boundaries between material types and the actual transitions may be gradual and vary with location.

Groundwater

Groundwater was encountered in 40 of the test bores at the time of drilling at depths ranging from 18 feet bgs to 20 feet bgs. When checked following the completion of drilling, static groundwater was observed in each of the 50 test bores at depths ranging from 15 to 20 feet bgs.

Fluctuations in groundwater and subsurface moisture conditions may occur due to variations in rainfall and other factors not readily apparent at this time. Development of the property and adjacent properties may also affect groundwater levels. The groundwater appears to be a perched condition which means it will be more greatly impacted by surface water.

CONCLUSIONS

The following discussion is based on the subsurface conditions encountered in the test borings and on the project characteristics previously described. If conditions are different from those described in this report or the project characteristics change, RMG should be retained to review our recommendations and adjust them, if necessary. The results of this investigation indicate that the site is suitable for the proposed project provided the recommendations presented herein are implemented.

As previously discussed the site is underlain primarily by an upper fill material comprised of stiff to very stiff sandy silty clay and sandy to clayey native soils. The native soils included loose to medium dense silty to clayey sand. Underlying the upper soils, weathered to hard siltstone bedrock was encountered. The siltstone occasionally contained thinly interbedded claystone lens. The native clay samples consolidated up to 8.8% and exhibited up to 5.4% swell. The silty to clayey sand samples exhibited up to 7.6% consolidations and exhibited 0.2% swell potential. Finally, the siltstone bedrock samples tested generally exhibited less than 1.3% consolidation and no swell potential. Swell/consolidation tests for this investigation were performed by wetting all samples against 1,000 psf surcharge pressures.

Geotechnical recommendations based on the field investigation and laboratory testing are presented below. It must be understood that these recommendations should be verified after the excavation on each individual lot is completed.

SITE DEVELOPMENT AND EARTHWORK

Site Preparation

Prior to construction the ground surface in proposed structure and improvement areas should be stripped of existing vegetation, debris, topsoil, undocumented fill, soft, loose, or disturbed native soils, and other deleterious material. Materials generated during clearing operations should be removed from the project site for disposal. Soft, loose, or yielding subgrade should be removed to a depth that exposes firm subgrade and replaced with structural fill. In areas to receive structural fill, the exposed subgrade should be scarified, moisture conditioned, and compacted per the recommendations set forth in this report.

Excavations

The on-site surface and near surface soils may generally be excavated with heavy-duty earthmoving or excavation equipment in good operating condition. In the areas where auger refusal was encountered due to the sandstone bedrock, heavier equipment may be required to break through the sandstone. During wet weather, earthen berms, swales, or other methods should be used where necessary to route water away from excavations. Water that accumulates in excavations should be promptly pumped out or otherwise removed and the area allowed to dry before resuming construction.

Geotechnical Considerations

Soft/Loose and Dry Collapsible Soils:

Soft/loose and dry collapsible soils were encountered at anticipated foundation depths on all blocks throughout the subdivision and are not suitable for direct bearing of shallow foundations. Where soft/loose or dry soils are encountered in the excavation, they will require additional compaction to achieve the allowable bearing pressures indicated in this report. We recommend reconditioning the on-site soils beneath the foundation components prior to constructing the foundation by overexcavating, moisture conditioning and recompacting the soils that results in a minimum of two feet of properly reconditioned soils beneath the footings and slabs. Please reference the Structural Fill section below for compaction recommendations. The zone of overexcavation and replacement should extend beyond the building perimeter a minimum of 4 feet, including beyond the perimeter of counterforts and "T" wall footings. The use of track-mounted excavation equipment or other low-ground-pressure equipment is recommended to reduce the likelihood of loss of stability during excavation.

Isolated pockets of loose soils may be encountered in the excavations, even on lots where none are indicated on the test borings. If soft/loose soils are encountered, they may also require additional compaction and/or stabilization as previously mentioned to achieve the allowable bearing pressure indicated in this report.

Expansive Clay:

The upper dry clay soil on Lot 6, Block 5 and surrounding lots, is considered to possess moderate to high swell potential and is not suitable for direct support of shallow foundations or slabs. If the dry, expansive clay is determined to be 3 feet of the bottom of foundation components and floor slabs, it will require removal (overexcavation) and replacement with non-expansive, granular structural fill to a depth which results in at least 3 feet of compacted granular structural fill below foundation components and floor slabs. The structural fill should be observed and tested during placement as indicated under the Structural Fill section of this report, to ensure proper compaction. An alternative stabilization method would be removal and replacement (overexcavation) with 4 feet of moisture-conditioned of on-site soils in accordance with the Moisture-Conditioned Structural Fill section of this report. The zone of overexcavation and replacement should extend beyond the building perimeter a minimum of 4 feet for granular, non-expansive structural fill and 4 feet for moisture-conditioned onsite soils, including beyond the perimeter of counterforts and "T" wall footings.

Foundation Wall Backfill

Backfill should be placed in loose lifts not exceeding 8 to 12 inches with material no greater than 4 inches in diameter, moisture conditioned to facilitate compaction (usually within 2 percent of the optimum moisture content), and compacted to 90 percent of the maximum dry density as determined by the Standard Proctor test, ASTM D-698 on exterior sides of walls in landscaped areas. In areas where backfill supports pavement and concrete flatwork, the materials should be moisture conditioned to +/- 2 percent optimum moisture content compacted to 95 percent of the maximum dry density as determined by the Standard Proctor test, ASTM D-698.

Fill placed on slopes should be benched into the slope. Maximum bench heights should not exceed 4 feet, and bench widths should be wide enough to accommodate compaction equipment.

Expansive bedrock should not be used as backfill materials. The backfill should not be placed on frozen subgrade or allowed to freeze during moisture conditioning and placement. Backfill should be compacted by mechanical means, and foundation walls should be braced during backfilling and compaction.

Structural Fill

Areas to receive structural fill should have topsoil, organic material, or debris removed. The upper 6 inches of the exposed surface soils should be scarified and moisture conditioned to facilitate compaction (usually within 2 percent of the optimum moisture content) and compacted to a minimum of 95 percent of the maximum dry density as determined by the Standard Proctor test (ASTM D-698) prior to placing structural fill.

Structural fill placed on slopes should be benched into the slope. Maximum bench heights should not exceed 4 feet, and bench widths should be wide enough to accommodate compaction equipment.

Structural fill shall consist of granular, non-expansive material, and it should be placed in loose lifts not exceeding 8 to 12 inches, moisture conditioned to facilitate compaction (usually within 2 percent of the optimum moisture content) and compacted to a minimum of 95 percent of the maximum dry density as determined by the Standard Proctor test, ASTM D-698. The materials should be compacted by mechanical means.

Materials used for structural fill should be approved by RMG prior to use. Structural fill should not be placed on frozen subgrade or allowed to freeze during moisture conditioning and placement.

To verify the condition of the compacted soils, density tests should be performed during placement. The first density tests should be conducted when 24 inches of fill have been placed.

Moisture Conditioned Structural Fill

Areas to receive moisture-conditioned structural fill should have topsoil, organic material, or debris removed. The upper 6 inches of the exposed surface soils should be scarified and moisture conditioned to -1 to +3 percent optimum moisture content and compacted to a minimum of 95 percent of the maximum dry density as determined by the Standard Proctor test (ASTM D-698) prior to placing structural fill.

Moisture-conditioned structural fill placed on slopes should be benched into the slope. Maximum bench heights should not exceed 4 feet, and bench widths should be wide enough to accommodate compaction equipment.

Moisture conditioned structural fill shall consist of a moisture-conditioned, on-site cohesive fill material. The bedrock encountered on site is not suitable to be used as moisture conditioned structural fill. The fill material shall be moisture conditioned and replaced as follows:

- Fill shall be free of deleterious material and shall not contain rocks or cobbles greater than 6 inches in diameter.
- Fill materials do not require processing in a stockpile, but shall be moisture-conditioned to -1 to +3 percent optimum moisture content (as determined by the Standard Proctor test, ASTM D-698), with an average of not less than optimum moisture content.
- The moisture-conditioned materials should be placed in maximum 6" compacted lifts. These materials should be compacted to a minimum of 95 percent of the maximum dry density as determined by the Standard Proctor test (ASTM D-698). Material not meeting the above requirements shall be reprocessed.

Materials used for moisture-conditioned structural fill should be approved by RMG prior to use. Moisture-conditioned structural fill should not be placed on frozen subgrade or allowed to freeze during moisture conditioning and placement.

To verify the condition of the compacted soils, density tests should be performed during placement. The first density tests should be conducted when 24 inches of fill have been placed.

FOUNDATION OPTIONS

Anticipated Foundation Systems

A spread footing foundation system may be utilized at this site bearing on the appropriate material as determined during the Open Hole Excavation. A maximum allowable bearing pressure of 1,500 psf with a minimum dead load of 500 psf may be used for design purposes. Foundation components must be below all organic material and should extend 30 inches or more below the lowest exterior finished grade for frost protection. The foundation design should be prepared by a qualified Colorado Registered Professional Engineer using the recommendations presented in this report. This foundation system should be designed to span a minimum of 10 feet under the design loads.

Open Excavation Observations

During construction, foundation excavations should be observed by RMG prior to placing structural fill, forms or concrete to verify the foundation bearing conditions for each structure.

INTERIOR FLOOR SYSTEMS

Interior Floor Slabs

Vertical slab movement of one to two inches is considered possible for all soil types. In some cases, vertical movement may exceed this range. If movement and associated damage to floors and finishes cannot be tolerated, a structural floor system should be used.

Floor slabs should be separated from structural components to allow for vertical movement. Control and construction joints should be placed in accordance with the latest guidelines and standards published by the American Concrete Institute (ACI) and applicable local Building Code requirements.

Interior Partitions

Interior non-bearing partitions and attached furnishings (e.g., cabinets, shower stalls, etc.) on concrete slabs should be constructed with a void so that they do not transmit floor slab movement to the roof or overlying floor. A void of at least 1-1/2 inches is recommended beneath non-bearing partitions. The void may require reconstruction over the life of the structure to re-establish the void due to vertical slab movement.

LATERAL EARTH PRESSURES

Foundation walls should be designed to resist lateral earth pressures. For cohesive, non-expansive backfill materials such as the on-site clay soils (native and fill), we recommend an active fluid pressure of 50 pcf, an at-rest fluid pressure of 70 pcf, and a passive pressure of 240 pcf be used for design. Expansive soils or bedrock should not be used as backfill against foundation walls.

The above lateral earth pressure applies to level, drained backfill conditions. Equivalent Fluid Pressures for sloping/undrained conditions should be determined on an individual basis.

SURFACE GRADING AND DRAINAGE

Grading and Irrigation

The ground surface should be sloped from the building with a minimum gradient of 10 percent for the first 10 feet. This is equivalent to 12 inches of fall across this 10-foot zone. If a 10-foot zone is not possible on the upslope side of the structure, then a well-defined swale should be created a minimum 5 feet from the foundation and sloped parallel with the wall with a minimum slope of 2 percent to intercept the surface water and transport it around and away from the structure. Roof drains should extend across backfill zones and landscaped areas to a region that is graded to direct flow away from the structure. Homeowners should maintain the surface grading and drainage recommended in this report to help prevent water from being directed toward and/or ponding near the foundations.

Landscaping should be selected to reduce irrigation requirements. Plants used close to foundation walls should be limited to those with low moisture requirements and irrigated grass should not be located within 5 feet of the foundation. To help control weed growth, geotextiles should be used below landscaped areas adjacent to foundations. Impervious plastic membranes are not recommended.

Irrigation devices should not be placed within 5 feet of the foundation. Irrigation should be limited to the amount sufficient to maintain vegetation. Application of more water will increase the likelihood of slab and foundation movements.

The recommendations listed in this report are intended to address normal surface drainage conditions, assuming the presence of groundcover (established vegetation, paved surfaces, and/or structures) throughout the regions upslope from this structure. However, groundcover may not be present due to a variety of factors (ongoing construction/development, wildfires, etc.). During periods when groundcover is not present in the "upslope" regions, higher than normal surface drainage conditions may occur, resulting in perched water tables, excess runoff, flash floods, etc. In these cases, the surface drainage recommendations presented herein (even if properly maintained) may not mitigate all groundwater problems or moisture intrusion into the structure. We recommend that the site plan be prepared with consideration of increased runoff during periods when groundcover is not present on the upslope areas.

Perimeter Drain

A subsurface perimeter drain is recommended around portions of the structure which will have habitable or storage space located below the finished ground surface. This includes crawlspace areas but not the walkout trench, if applicable.

The perimeter drain can be installed as an interior (if a minimum of six inches of free draining aggregate is placed beneath the slab) or exterior perimeter drain system. The perforated drainage pipe should be installed so the top of the pipe is not above the top of the footing and should be surrounded by material to reduce the infiltration of silt into the drainage pipe. The pipe should be installed in one of the following manners:

1) The pipe may be installed as level as possible as long as the pipe is placed in a minimum of six inches of gravel or crushed stone and exits into a sump pit with mechanical means to remove the water.

Or

2) The pipe may be installed as a gravity system with a minimum 1/8 inch fall per 1 foot length surrounded by a minimum six inches of gravel or crushed stone that either daylights to allow free flow drainage or exits into a sump pit with mechanical means to remove the water.

A subsurface perimeter drain is designed to intercept some types of subsurface moisture and not others. Therefore, the drain could operate properly and not mitigate all moisture problems relating to foundation performance or moisture intrusion into the basement area.

CONCRETE

Sulfate testing was performed on selected samples based on ASTM C1580. Test results yielded 0.04% to 0.37% sulfate by weight, indicating the soils present medium sulfate exposure. Based on these results Type V or equivalent cement is recommended for concrete in contact with the subsurface materials. Calcium chloride should be used with caution for soils with high sulfate contents. The concrete should not be placed on frozen ground. If placed during periods of cold temperatures, the concrete should be kept from freezing. This may require covering the concrete with insulated blankets and heating. Concrete work should be completed in accordance with the latest applicable guidelines and standards published by ACI.

Recommendations for exterior concrete slabs, such as patios, driveways, and sidewalks, are not included in this report.

CLOSING

This report has been prepared for the exclusive purpose of providing geotechnical engineering information and recommendations for development described in this report. RMG should be

retained to review the final construction documents prior to construction to verify our findings, conclusions and recommendations have been appropriately implemented.

This report has been prepared for the exclusive use by **Journey Homes** for application as an aid in the design and construction of the proposed development in accordance with generally accepted geotechnical engineering practices. The analyses and recommendations in this report are based in part upon data obtained from test borings and site observations. The nature and extent of variations may not become evident until construction. If variations then become evident, RMG should be retained to review the recommendations presented in this report considering the varied condition, and either verify or modify them in writing.

Our professional services were performed using that degree of care and skill ordinarily exercised, under similar circumstances, by geotechnical engineers practicing in this or similar localities. RMG does not warrant the work of regulatory agencies or other third parties supplying information which may have been used during the preparation of this report. No warranty, express or implied is made by the preparation of this report. Third parties reviewing this report should draw their own conclusions regarding site conditions and specific construction techniques to be used on this project.


The scope of services for this project does not include, either specifically or by implication, environmental assessment of the site or identification of contaminated or hazardous materials or conditions. Development of recommendations for the mitigation of environmentally related conditions, including but not limited to biological or toxicological issues, are beyond the scope of this report. If the Client desires investigation into the potential for such contamination or conditions, other studies should be undertaken.

If we can be of further assistance in discussing the contents of this report or analysis of the proposed development, from a geotechnical engineering point-of-view, please feel free to contact us.

FIGURES



SITE




VICINITY MAP
SUNSET RIDGE
SUBDIVISION
THIRD FILING
SEVERANCE, COLORADO

CLIENT :
JOURNEY HOMES, LLC
7251 W. 20th ST., BLDG. L, STE. 200
GREELEY, CO. 80634
RMG PROJECT #180135
DATE: 3/3/21



ROCKY MOUNTAIN
GROUP
1601 37th STREET
EVANS, CO. 80620
PHONE: (970) 330-1071
FAX: (970) 330-1252



0 100 200
SCALE: 1" = 200'

BORE LOCATION PLAN

SUNSET RIDGE
SUBDIVISION
THIRD FILING
SEVERANCE, COLORADO

CLIENT :
JOURNEY HOMES, LLC
7251 W. 20th ST., BLDG. L, STE. 200
GREELEY, CO. 80634
RMG PROJECT #180135
DATE: 3/3/21



ROCKY MOUNTAIN
GROUP

















1601 37th STREET
EVANS, CO. 80620
PHONE: (970) 330-1071
FAX: (970) 330-1252

DATE Mar/30/2021

DATE Mar/30/2021

DATE Mar/30/2021

DATE Mar/30/2021

LOT No.: Block 01 Lot 09 DATE DRILLED: 1/22/21 ELEVATION (FT): 4921.46 GROUNDWATER @ Dry ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 10 DATE DRILLED: 1/22/21 ELEVATION (FT): 4921.95 GROUNDWATER @ Dry ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey brown, fine grained, very loose to loose, moist	5			9	6.9	SAND, silty, clayey brown, fine grained, loose, moist	5			16	6.2
SILTSTONE, tan and brown, hard, moist	10			6	13.8	SILTSTONE, tan and brown, hard, moist	10			17	7.8
	15			5	10.3		15			10	8.4
	20			50/6"	16.8		20			50/8"	23.5

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS













JOB No. 180135

FIGURE No. 7

DATE Mar/30/2021

DATE Mar/30/2021

DATE Mar/30/2021

LOT No.: Block 01 Lot 15 DATE DRILLED: 1/22/21 ELEVATION (FT): 4926.02 GROUNDWATER @ 18.0 ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 16 DATE DRILLED: 1/22/21 ELEVATION (FT): 4926.43 GROUNDWATER @ 18.5 ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, silty, sandy brown, medium stiff, moist	5			16	7.4	CLAY, silty, sandy brown, medium stiff, moist	5			18	7.1
SILTSTONE, tan and brown, medium hard to hard, moist	15			50/9"	20.8	SILTSTONE, tan and brown, medium hard, moist	15			50/10"	13.7
	20			50/5"	23.1		20			50/12"	26.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO











Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 10

DATE Mar/30/2021

LOT No.: Block 01 Lot 17 DATE DRILLED: 1/22/21 ELEVATION (FT): 4925.64 GROUNDWATER @ Dry ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 18 DATE DRILLED: 1/22/21 ELEVATION (FT): 4924.82 GROUNDWATER @ Dry ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey brown, fine grained, loose, dry	5			18	7.9	SAND, silty, clayey brown, fine grained, loose, dry	5			14	6.2
SILTSTONE, tan and brown, medium hard to hard, moist	15			50/9"	20.5	SILTSTONE, tan, orange and brown, hard, moist	15			50/6"	12.8
with orange mottling	20			50/7"	19.6	with claystone lens	20			50/10"	26.5

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 11

DATE Mar/30/2021

LOT No.: Block 01 Lot 19 DATE DRILLED: 1/22/21 ELEVATION (FT): 4923.41 GROUNDWATER @ Dry ' 1/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 20 DATE DRILLED: 1/23/21 ELEVATION (FT): 4922.45 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey brown, fine grained, loose, dry	5			17	7.5	SAND, silty, clayey brown, fine grained, loose, moist	5			16	7.0
SILTSTONE, tan and brown, medium hard to hard, moist	10			12	7.9		10			15	7.9
	15			50/10"	15.7	SILTSTONE, tan and brown, medium hard to hard, moist	15			50/11"	12.6
	20			50/6"	16.1		20			50/6"	19.1

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 12

DATE Mar/30/2021

LOT No.: Block 01 Lot 21 DATE DRILLED: 1/23/21 ELEVATION (FT): 4921.15 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 22 DATE DRILLED: 1/23/21 ELEVATION (FT): 4920.16 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, silty, sandy brown, stiff, moist	5			17	9.0	CLAY, silty, sandy brown, stiff, moist	5			16	7.0
SILTSTONE, tan and brown, medium hard to very hard, moist	10			10	8.5	SILTSTONE, tan and brown, medium hard to hard, moist	10			11	9.6
	15			50/7"	17.0		15			50/7"	11.8
	20			50/0"	2.7		20			50/10"	25.8

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 13

DATE Mar/30/2021

LOT No.: Block 01 Lot 23 DATE DRILLED: 1/23/21 ELEVATION (FT): 4919.11 GROUNDWATER @ 20.0 ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 01 Lot 24 DATE DRILLED: 1/23/21 ELEVATION (FT): 4918.29 GROUNDWATER @ 19.5 ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, silty, sandy brown, stiff, moist	5			14	7.8	SAND, silty, clayey brown, fine grained, loose to medium dense, moist	5			16	8.1
	10			14	9.1		10			15	6.6
SILTSTONE, tan and brown, medium hard to hard, moist	15			50/9"	16.3		15			21	10.6
	20			50/5"	20.5	SILTSTONE, tan and brown, medium hard to hard, moist	20			50/5"	21.7

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 14

DATE Mar/30/2021

DATE Mar/30/2021

LOT No.: Block 02 Lot 02 DATE DRILLED: 2/26/21 ELEVATION (FT): 4918.91 GROUNDWATER @ Dry ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 02 Lot 03 DATE DRILLED: 2/26/21 ELEVATION (FT): 4918.79 GROUNDWATER @ Dry ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy, brown, stiff, dry	5			19	8.7	CLAY, sandy, brown, stiff, dry	5			14	7.9
SAND, clayey, silty brown, fine to coarse grained, loose, dry	10			6	6.0	SILTSTONE brown and orange, medium hard to hard, dry	10			50/11"	7.9
SILTSTONE brown and orange, hard, dry	15			50/6"	10.1		15			50/5"	13.0
moist	20			50/5"	15.3	moist	20			50/6"	18.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 17

DATE Mar/30/2021

LOT No.: Block 02 Lot 04 DATE DRILLED: 2/26/21 ELEVATION (FT): 4918.00 GROUNDWATER @ Dry ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 02 Lot 05 DATE DRILLED: 2/26/21 ELEVATION (FT): 4917.08 GROUNDWATER @ Dry ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty white and brown, fine grained, loose, dry	5			11	8.5	CLAY, sandy, silty brown, stiff, dry	5			18	14.0
SILTSTONE brown and orange, hard, dry	10			50/6"	9.9	SILTSTONE brown and orange, hard, dry	10			50/5"	7.7
moist	15			50/6"	12.4	moist	15			50/5"	12.0
	20			50/4"	17.8		20			50/6"	20.6

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 18

DATE Mar/30/2021

LOT No.: Block 02 Lot 06 DATE DRILLED: 2/26/21 ELEVATION (FT): 4915.72 GROUNDWATER @ Dry ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 02 Lot 07 DATE DRILLED: 2/26/21 ELEVATION (FT): 4913.13 GROUNDWATER @ 20.0 ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy, silty brown, stiff, dry	5			12	10.6	SAND, clayey, silty brown, fine grained, loose, dry	5			12	10.7
SILTSTONE brown and orange, very hard to hard, dry	10			50/3"		SILTSTONE brown and orange, hard to very hard, dry	10			50/5"	8.5
moist	15			50/5"	16.5		15			50/5"	22.0
	20			50/6	21.7	moist	20			50/0"	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 19

DATE Mar/30/2021

LOT No.: Block 02 Lot 08 DATE DRILLED: 2/26/21 ELEVATION (FT): 4911.73 GROUNDWATER @ 19.5 ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 02 Lot 09 DATE DRILLED: 2/26/21 ELEVATION (FT): 4910.62 GROUNDWATER @ 18.5 ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty with gravel brown, fine grained, loose, dry	5			14	9.1	SAND, clayey, silty brown, fine grained, loose, dry	5			12	8.3
SILTSTONE brown and orange, medium hard to hard, dry	10			50/6"	11.0	SILTSTONE brown and orange, hard, dry	10			50/11"	15.8
	15			50/5"	21.8	moist	15			50/8"	19.5
moist	20			50/6"	28.6		20			50/5"	24.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 20

DATE Mar/30/2021

LOT No.: Block 02 Lot 10 DATE DRILLED: 2/26/21 ELEVATION (FT): 4909.69 GROUNDWATER @ 18.0 ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 02 Lot 11 DATE DRILLED: 2/26/21 ELEVATION (FT): 4908.12 GROUNDWATER @ 17.0 ' 3/1/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose to very loose, dry	5			19	5.2	CLAY, sandy, silty brown, stiff, dry	5			12	12.0
SILTSTONE brown and orange, hard, dry moist	10			5	22.5	SILTSTONE brown and orange, hard, dry moist	10			6	14.8
15 	15			50/6"	19.6	moist with claystone lense	15			50/9"	11.9
20	20			50/5"	20.7		20			39	16.5

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 21

DATE Mar/30/2021

LOT No.: Block 03 Lot 01 DATE DRILLED: 2/22/21 ELEVATION (FT): 4919.66 GROUNDWATER @ Dry ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 02 DATE DRILLED: 2/22/21 ELEVATION (FT): 4919.09 GROUNDWATER @ Dry ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey brown, fine grained, very loose to loose, dry	5			5	11.7	SAND, clayey, silty brown, fine grained, very loose to loose, dry	5			13	10.6
SILTSTONE brown and orange, hard, dry	10			10	11.5	SILTSTONE brown and orange, hard, dry	10			14	11.7
	15			10	10.4		15			50/4"	11.1
	20			50/7"	18.6		20			50/6"	26.5

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 22

DATE Mar/30/2021

Architectural
Structural
Forensics



Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

SOUTHERN COLORADO. DENVER METRO. NORTHERN COLORADO















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 23

DATE Mar/30/2021

LOT No.: Block 03 Lot 05 DATE DRILLED: 1/29/21 ELEVATION (FT): 4916.06 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 06 DATE DRILLED: 1/29/21 ELEVATION (FT): 4914.84 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine to coarse grained, loose, dry	5			15	8.3	SAND, silty brown, fine grained, loose, dry	5			14	7.8
SILTSTONE brown and orange, hard, dry	10			50/5"	5.8	SILTSTONE brown and orange, firm to hard, dry	10			37	8.2
moist	15			50/7"	22.4		15			50/6"	15.4
	20			50/7"	22.0		20			50/5"	18.4

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 24

DATE Mar/30/2021

LOT No.: Block 03 Lot 07 DATE DRILLED: 2/22/21 ELEVATION (FT): 4913.69 GROUNDWATER @ Dry ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 08 DATE DRILLED: 2/22/21 ELEVATION (FT): 4912.50 GROUNDWATER @ 20.0 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			17	9.2	SAND, clayey, silty brown, fine grained, loose, dry	5			16	8.5
SILTSTONE brown and orange, firm to hard, dry	10			18	8.7	SILTSTONE brown and orange, medium hard to hard, dry	10			17	5.1
	15			46	23.4		15			50/10"	20.8
	20			50/6"	19.7		20			50/5"	23.6

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 25

DATE Mar/30/2021

LOT No.: Block 03 Lot 09 DATE DRILLED: 2/22/21 ELEVATION (FT): 4911.10 GROUNDWATER @ 18.5 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 10 DATE DRILLED: 2/22/21 ELEVATION (FT): 4910.34 GROUNDWATER @ 18.0 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			15	7.8	CLAY, sandy brown, stiff, dry	5			10	9.6
SILTSTONE brown and orange, medium hard to hard, dry	10			19	9.8	SILTSTONE brown and orange, firm to hard, dry	10			30	10.4
	15			50/6"	14.1		15			50/6"	21.4
	20			50/10"	16.7		20			50/5"	20.4

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 26

DATE Mar/30/2021

LOT No.: Block 03 Lot 11 DATE DRILLED: 2/22/21 ELEVATION (FT): 4909.32 GROUNDWATER @ 17.0 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 12 DATE DRILLED: 2/22/21 ELEVATION (FT): 4908.74 GROUNDWATER @ 16.0 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			11	10.1	SAND, clayey brown, fine grained, loose, dry	5			7	9.8
SILTSTONE with claystone brown, grey and orange, very hard to medium hard, dry	10			8	11.6	tanish white	10			7	12.3
	15			50/1"	9.7	SILTSTONE brown and orange, medium hard, dry	15			50/11"	24.4
	20			50/9"	22.5		20			50/11"	20.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning























TEST BORING LOGS

JOB No. 180135

FIGURE No. 27

DATE Mar/30/2021

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

LOT No.: Block 03 Lot 15 DATE DRILLED: 2/22/21 ELEVATION (FT): 4913.26 GROUNDWATER @ 18.5 ' 2/17/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 16 DATE DRILLED: 1/29/21 ELEVATION (FT): 4914.41 GROUNDWATER @ 20.0 ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			15	6.9	CLAY, sandy brown, stiff to very stiff, dry	5			13	7.9
moist	10			10	10.3		10			15	9.3
	15			11	9.9	with orange mottling	15			21	6.2
SILTSTONE brown and orange, hard, dry				50/5"	20.8	SILTSTONE brown, tan and orange, hard, dry				50/6"	20.7
	20						20				

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 29

DATE Mar/30/2021

LOT No.: Block 03 Lot 17 DATE DRILLED: 1/29/21 ELEVATION (FT): 4915.22 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 18 DATE DRILLED: 1/29/21 ELEVATION (FT): 4916.26 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy brown, stiff, dry	5			12	9.7	CLAY, sandy brown, stiff, dry	5			16	7.9
SILTSTONE brown and orange, weathered to hard, dry	10			14	6.2	SILTSTONE brown and orange, hard, dry	10			10	9.3
	15			23	13.0		15			13	6.2
	20			50/6"	19.4		20			50/8"	20.7

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 30

DATE Mar/30/2021

LOT No.: Block 03 Lot 19 DATE DRILLED: 1/29/21 ELEVATION (FT): 4917.37 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 20 DATE DRILLED: 1/29/21 ELEVATION (FT): 4918.19 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			15	7.6	SAND, clayey, silty brown, fine grained, loose, dry	5			18	6.8
	10			12	8.3	moist	10			13	9.4
	15			11	10.9		15			6	13.3
SILTSTONE brown and orange, weathered to hard, dry	20			50/7"	17.9	SILTSTONE brown and orange, hard, dry	20			50/8'	23.2

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 31

DATE Mar/30/2021

LOT No.: Block 03 Lot 21 DATE DRILLED: 1/29/21 ELEVATION (FT): 4919.11 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 22 DATE DRILLED: 1/29/21 ELEVATION (FT): 4920.22 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, loose, dry	5			18	6.3	SAND, clayey, silty brown, fine grained, loose, dry	5			18	7.4
SILTSTONE brown and orange, firm to hard, dry	10			15	7.6	SILTSTONE brown and orange, weathered to hard, moist	10			15	6.1
	15			45	13.3		15			24	7.9
	20			50/7"	18.0		20			50/6"	15.8

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 32

DATE Mar/30/2021

LOT No.: Block 03 Lot 23 DATE DRILLED: 1/29/21 ELEVATION (FT): 4921.04 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 03 Lot 24 DATE DRILLED: 1/29/21 ELEVATION (FT): 4921.44 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, clayey, silty brown, fine grained, dense to loose, dry	5			20	8.8	SAND, clayey, silty brown, fine to coarse grained, loose, dry	5			13	6.7
SILTSTONE brown and orange, medium hard to hard, dry	10			17	5.7	SILTSTONE brown and orange, hard, dry	10			17	7.6
	15			50/10"	10.3		15			50/7"	10.9
	20			50/5"	13.0		20			50/6"	8.4

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

















TEST BORING LOGS

JOB No. 180135

FIGURE No. 33

DATE Mar/30/2021

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

LOT No.: Block 04 Lot 02 DATE DRILLED: 1/27/21 ELEVATION (FT): 4922.60 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 03 DATE DRILLED: 1/27/21 ELEVATION (FT): 4921.82 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist	5			17	6.4	SAND, silty, clayey tan, fine grained, loose, moist	5			18	5.5
SILTSTONE, tan and orange, hard, moist	10			10	10.0	CLAY, sandy, silty tan and grey, very stiff, moist	10			10	10.8
	15			50/6"	15.5		15			39	14.4
	20			50/6"	18.1		20			50/7"	19.8

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 35

DATE Mar/30/2021

LOT No.: Block 04 Lot 04 DATE DRILLED: 1/27/21 ELEVATION (FT): 4920.50 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 05 DATE DRILLED: 1/27/21 ELEVATION (FT): 4919.45 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose to medium dense, moist	5			17	6.2	SAND, silty, clayey tan, fine grained, loose, moist	5			14	6.5
SILTSTONE, orange, hard, moist	10			10	9.2		10			11	8.7
	15			39	17.8	SILTSTONE, brown and orange, firm to medium hard, moist	15			50/10"	20.3
	20			50/8"	22.4		20			46	19.5

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO









Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 36

DATE Mar/30/2021

LOT No.: Block 04 Lot 06 DATE DRILLED: 1/27/21 ELEVATION (FT): 4918.43 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 07 DATE DRILLED: 1/27/21 ELEVATION (FT): 4917.41 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy brown, stiff, dry	5			12	6.2	CLAY, sandy brown, stiff, dry	5			11	6.1
	10			10	10.2		10			8	14.8
SILTSTONE, brown and orange, medium hard, moist	15			50/10"	15.0	SILTSTONE, brown and orange, medium hard to very hard, moist	15			50/10"	20.2
	20			50/9"	21.1		20			50/3"	16.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 37

DATE Mar/30/2021

LOT No.: Block 04 Lot 08 DATE DRILLED: 1/27/21 ELEVATION (FT): 4916.42 GROUNDWATER @ 20.0 ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 09 DATE DRILLED: 1/27/21 ELEVATION (FT): 4915.31 GROUNDWATER @ 18.5 ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy brown, stiff, moist	5			20	5.8	SAND, silty, clayey tan, fine grained, loose, moist	5			17	6.7
SILTSTONE, brown and orange, medium hard to hard, moist	10			10	10.8	SILTSTONE, grey and orange, hard, moist	10			11	9.1
	15			50/11"	20.2		15			50/7"	33.9
	20			50/6"	18.5		20			50/5"	16.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 38

DATE Mar/30/2021

LOT No.: Block 04 Lot 10 DATE DRILLED: 1/27/21 ELEVATION (FT): 4914.37 GROUNDWATER @ 18.0 ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 11 DATE DRILLED: 1/27/21 ELEVATION (FT): 4913.79 GROUNDWATER @ 17.0 ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist						SAND, silty, clayey tan, fine grained, loose, moist					
	5			13	7.7		5			12	9.4
	10			12	7.5		10			8	10.7
	15			12	14.3		15			41	21.6
wet						SILTSTONE, brown and orange, firm, moist					
	20			9	16.6		20			39	22.2

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

















FIGURE No. 39

DATE Mar/30/2021

DATE Mar/30/2021

DATE Mar/30/2021

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

LOT No.: Block 04 Lot 18 DATE DRILLED: 1/27/21 ELEVATION (FT): 4918.24 GROUNDWATER @ Dry ' 1/28/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 19 DATE DRILLED: 1/26/21 ELEVATION (FT): 4918.97 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist	5			18	6.9	SAND, silty, clayey tan, fine grained, loose, moist	5			16	7.8
SILTSTONE, tan and grey, medium hard to hard, moist	10			13	8.7	SILTSTONE, tan and grey, medium hard to hard, moist	10			14	9.8
	15			50/12"	16.0					50/9"	14.8
	20			50/6"	23.1		20			50/6"	21.8

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 43

DATE Mar/30/2021

LOT No.: Block 04 Lot 20 DATE DRILLED: 1/26/21 ELEVATION (FT): 4920.01 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 21 DATE DRILLED: 1/26/21 ELEVATION (FT): 4921.03 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist	5			18	6.7	CLAY, sandy tan, stiff, moist	5			16	6.7
	10			14	8.9		10			16	9.4
SILTSTONE, tan and grey, medium hard to hard, moist	15			50/11"	18.9	SILTSTONE, brown, firm to medium hard, moist	15			41	20.2
with claystone lense	20			50/7"	17.2		20			50/12"	21.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 44

DATE Mar/30/2021

LOT No.: Block 04 Lot 22 DATE DRILLED: 1/26/21 ELEVATION (FT): 4922.07 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 23 DATE DRILLED: 1/26/21 ELEVATION (FT): 4923.02 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist	5			16	5.7	SAND, silty, clayey tan, fine grained, loose, moist	5			16	7.2
SILTSTONE, brown, medium hard to hard, moist	10			14	8.3	SILTSTONE, brown, medium hard, moist	10			17	7.9
	15			50/10"	11.5		15			50/8"	11.7
	20			50/6"	18.3		20			50/10"	18.1

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO









Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 45

DATE Mar/30/2021

LOT No.: Block 04 Lot 24 DATE DRILLED: 1/26/21 ELEVATION (FT): 4924.24 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 04 Lot 25 DATE DRILLED: 1/26/21 ELEVATION (FT): 4925.03 GROUNDWATER @ Dry ' 1/27/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, loose, moist	5			15	6.1	SAND, silty, clayey tan, fine grained, loose, moist	5			17	6.3
	10			15	7.8		10			15	8.9
SILTSTONE, brown, firm to hard, moist	15			36	27.3	SILTSTONE, brown, medium hard to hard, moist	15			50/9"	12.8
	20			50/4"	20.3		20			50/6"	17.8

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 46

DATE Mar/30/2021

Architectural
Structural
Forensics

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

















Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 47

DATE Mar/30/2021

LOT No.: Block 05 Lot 03 DATE DRILLED: 2/10/21 ELEVATION (FT): 4906.37 GROUNDWATER @ 15.5 ' 2/11/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 05 Lot 04 DATE DRILLED: 2/10/21 ELEVATION (FT): 4907.15 GROUNDWATER @ 16.0 ' 2/11/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy tan, stiff, dry	5			10	14.1	CLAY, sandy tan, stiff to very stiff, dry	5			24	8.8
	10			7	14.4	moist	10			8	12.5
	15			8	19.6		15			9	15.5
SILTSTONE, brown, hard, moist	20			50/6"	21.9	wet	20			15	15.2

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS



















JOB No. 180135

FIGURE No. 48

DATE Mar/30/2021

DATE Mar/30/2021

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Spings, CO 80918
(719) 548-0600

LOT No.: Block 05 Lot 09 DATE DRILLED: 2/23/21 ELEVATION (FT): 4909.55 GROUNDWATER @ 17.0 ' 2/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 05 Lot 10 DATE DRILLED: 2/23/21 ELEVATION (FT): 4910.26 GROUNDWATER @ 17.0 ' 2/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
SAND, silty, clayey tan, fine grained, medium dense to loose, dry	5			20	8.5	SAND, silty, clayey tan, fine grained, medium dense to loose, dry	5			27	7.1
	10			9	16.1	moist	10			9	8.2
moist	15			17	14.8		15			19	16.9
											
SILTSTONE, tan and brown, hard, moist	20			50/6"	8.5	wet	20			17	23.4

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS















JOB No. 180135

FIGURE No. 51

DATE Mar/30/2021

DATE Mar/30/2021

DATE Mar/30/2021

LOT No.: Block 05 Lot 15 DATE DRILLED: 2/23/21 ELEVATION (FT): 4912.75 GROUNDWATER @ 16.0 ' 2/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	LOT No.: Block 05 Lot 16 DATE DRILLED: 2/23/21 ELEVATION (FT): 4913.40 GROUNDWATER @ 15.5 ' 2/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %
CLAY, sandy tan, very stiff, dry	5			31	6.8	SAND, silty, clayey tan, fine grained, medium dense to loose, dry	5			15	8.5
SAND, silty, clayey tan, fine grained, medium dense to loose, moist	10			17	9.6	moist	10			9	11.8
	15			16	15.7		15			16	16.8
	20			21	21.2	wet	20			14	20.3

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO









Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 54

DATE Mar/30/2021

LOT No.: Block 05 Lot 17 DATE DRILLED: 2/23/21 ELEVATION (FT): 4913.85 GROUNDWATER @ 15.0 ' 2/26/21	DEPTH (FT)	SYMBOL	SAMPLES	BLOWS PER FT.	WATER CONTENT %	
FILL, sandy, silty, clayey dark brown and white, medium dense, dry	5			18	11.8	
SAND, silty, clayey tan, fine grained, medium dense to loose, moist	10			9	14.0	
	15			13	18.8	
	20			34	20.0	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

TEST BORING LOGS

JOB No. 180135

FIGURE No. 55

DATE Mar/30/2021

SOILS DESCRIPTION



CLAYEY SAND



FILL: SAND, SILTY TO CLAYEY



SANDY CLAY



SILTSTONE



SILTY SAND

UNLESS NOTED OTHERWISE, ALL LABORATORY
TESTS PRESENTED HEREIN WERE PERFORMED BY:
RMG - ROCKY MOUNTAIN GROUP
1601 37TH ST.
EVANS, COLORADO

SYMBOLS AND NOTES



XX

STANDARD PENETRATION TEST - MADE BY DRIVING A SPLIT-BARREL SAMPLER INTO THE SOIL BY DROPPING A 140 LB. HAMMER 30", IN GENERAL ACCORDANCE WITH ASTM D-1586. NUMBER INDICATES NUMBER OF HAMMER BLOWS PER FOOT (UNLESS OTHERWISE INDICATED).



XX

UNDISTURBED CALIFORNIA SAMPLE - MADE BY DRIVING A RING-LINED SAMPLER INTO THE SOIL BY DROPPING A 140 LB. HAMMER 30", IN GENERAL ACCORDANCE WITH ASTM D-3550. NUMBER INDICATES NUMBER OF HAMMER BLOWS PER FOOT (UNLESS OTHERWISE INDICATED).



FREE WATER TABLE



DEPTH AT WHICH BORING CAVED



BULK DISTURBED BULK SAMPLE



AUG AUGER "CUTTINGS"

4.5

WATER CONTENT (%)

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Geotechnical
Materials Testing
Civil, Planning

Colorado Springs: (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0800

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

EXPLANATION OF TEST BORING LOGS

JOB No. 180135

FIGURE No. 56

DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 01 Lot 01	4.0	7.5	89.3						
Block 01 Lot 01	9.0	8.5	90.8						
Block 01 Lot 01	14.0	9.3	98.0						
Block 01 Lot 01	19.0	22.3	90.2						
Block 01 Lot 02	4.0	7.0	95.6						
Block 01 Lot 02	9.0	7.9	89.9	26	9		47.3	- 5.9	1000
Block 01 Lot 02	14.0	11.0	90.9						
Block 01 Lot 02	19.0	21.0	100.2						
Block 01 Lot 03	4.0	6.3	89.3						
Block 01 Lot 03	9.0	9.0	92.8						
Block 01 Lot 03	14.0	11.6	100.5						
Block 01 Lot 03	19.0	19.6							
Block 01 Lot 04	4.0	6.1	98.6	28	12		35.9	- 2.6	1000
Block 01 Lot 04	9.0	13.4	97.5						
Block 01 Lot 04	14.0	7.3	103.8						
Block 01 Lot 04	19.0	25.4	91.4						
Block 01 Lot 05	4.0	6.6	93.3						
Block 01 Lot 05	9.0	10.8	84.7						
Block 01 Lot 05	14.0	7.3							
Block 01 Lot 05	19.0	22.6	102.3						
Block 01 Lot 06	4.0	11.1	102.3						
Block 01 Lot 06	9.0	17.8	100.3						
Block 01 Lot 06	14.0	11.8	104.9						
Block 01 Lot 06	19.0	22.4	103.5						
Block 01 Lot 07	4.0	7.1							
Block 01 Lot 07	9.0	47.4	102.8	29	13		70.6	- 0.8	1000
Block 01 Lot 07	14.0	11.5							
Block 01 Lot 07	19.0	22.1	103.3						
Block 01 Lot 08	4.0	10.1	80.8						
Block 01 Lot 08	9.0	8.8	86.7						
Block 01 Lot 08	14.0	10.9	108.9						
Block 01 Lot 08	19.0	22.5	97.9						
Block 01 Lot 09	4.0	6.9	96.4						
Block 01 Lot 09	9.0	13.8	105.6						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 1 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 01 Lot 09	14.0	10.3	97.1						
Block 01 Lot 09	19.0	16.8	93.7						
Block 01 Lot 10	4.0	6.2							
Block 01 Lot 10	9.0	7.8	99.3						
Block 01 Lot 10	14.0	8.4	95.4						
Block 01 Lot 10	19.0	23.5	95.2						
Block 01 Lot 11	4.0	6.9	87.7						
Block 01 Lot 11	9.0	10.1	78.8						
Block 01 Lot 11	14.0	10.0	93.3						
Block 01 Lot 11	19.0	23.3	85.7						
Block 01 Lot 12	4.0	5.3	94.9	25	9		27.3	- 6.6	1000
Block 01 Lot 12	9.0	8.5	89.1						
Block 01 Lot 12	14.0	13.5	91.3						
Block 01 Lot 12	19.0	23.5	93.5						
Block 01 Lot 13	4.0	7.2	95.3						
Block 01 Lot 13	9.0	10.2	93.4						
Block 01 Lot 13	14.0	21.6	94.7						
Block 01 Lot 13	19.0	20.3	83.4						
Block 01 Lot 14	4.0	6.3	89.2						
Block 01 Lot 14	9.0	12.1	103.6						
Block 01 Lot 14	14.0	16.1	104.8						
Block 01 Lot 14	19.0	20.7	94.4						
Block 01 Lot 15	4.0	7.4	90.2						
Block 01 Lot 15	9.0	9.2	96.7	26	14		50.0	- 3.5	1000
Block 01 Lot 15	14.0	20.8	88.7						
Block 01 Lot 15	19.0	23.1	84.3						
Block 01 Lot 16	4.0	7.1	101.0						
Block 01 Lot 16	9.0	7.4	91.0						
Block 01 Lot 16	14.0	13.7	89.5						
Block 01 Lot 16	19.0	26.3							
Block 01 Lot 17	4.0	7.9	90.4						
Block 01 Lot 17	9.0	7.9	90.3						
Block 01 Lot 17	14.0	20.5	96.9						
Block 01 Lot 17	19.0	19.6	82.6						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 2 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 01 Lot 18	4.0	6.2	95.2						
Block 01 Lot 18	9.0	6.6	94.2						
Block 01 Lot 18	14.0	12.8	80.0	NP	NP		59.6		1000
Block 01 Lot 18	19.0	26.5	96.6						
Block 01 Lot 19	4.0	7.5	92.0						
Block 01 Lot 19	9.0	7.9	98.3						
Block 01 Lot 19	14.0	15.7	86.1						
Block 01 Lot 19	19.0	16.1	91.1						
Block 01 Lot 20	4.0	7.0	97.7						
Block 01 Lot 20	9.0	7.9	90.3						
Block 01 Lot 20	14.0	12.6	89.8						
Block 01 Lot 20	19.0	19.1	88.8						
Block 01 Lot 21	4.0	9.0	90.9						
Block 01 Lot 21	9.0	8.5	86.8						
Block 01 Lot 21	14.0	17.0	78.4						
Block 01 Lot 21	19.0	2.7							
Block 01 Lot 22	4.0	7.0	91.9	26	9		52.1	- 5.0	1000
Block 01 Lot 22	9.0	9.6	93.1						
Block 01 Lot 22	14.0	11.8							
Block 01 Lot 22	19.0	25.8	82.0						
Block 01 Lot 23	4.0	7.8	97.7						
Block 01 Lot 23	9.0	9.1	95.3						
Block 01 Lot 23	14.0	16.3	92.0						
Block 01 Lot 23	19.0	20.5	78.5						
Block 01 Lot 24	4.0	8.1							
Block 01 Lot 24	9.0	6.6	109.2						
Block 01 Lot 24	14.0	10.6	110.4						
Block 01 Lot 24	19.0	21.7	82.0						
Block 01 Lot 25	4.0	9.1	88.0						
Block 01 Lot 25	9.0	5.7	99.7						
Block 01 Lot 25	14.0	8.8	102.4						
Block 01 Lot 25	19.0	24.9	95.5						
Block 01 Lot 26	4.0	9.5	86.8						
Block 01 Lot 26	9.0	9.6	97.3	24	5		42.5	- 3.2	1000

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 3 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 01 Lot 26	14.0	11.9	80.0						
Block 01 Lot 26	19.0	23.9	97.3						
Block 01 Lot 27	4.0	7.2	100.0						
Block 01 Lot 27	9.0	5.7	100.8						
Block 01 Lot 27	14.0	19.9	102.5						
Block 01 Lot 27	19.0	28.3							
Block 02 Lot 01	4.0	8.1	93.0						
Block 02 Lot 01	9.0	12.3	93.3						
Block 02 Lot 01	14.0	9.5	86.3						
Block 02 Lot 01	19.0	16.7	94.0						
Block 02 Lot 02	4.0	8.7	93.6	28	11		52.4	- 4.1	1000
Block 02 Lot 02	9.0	6.0	111.7						
Block 02 Lot 02	14.0	10.1							
Block 02 Lot 02	19.0	15.3	88.3						
Block 02 Lot 03	4.0	7.9	87.4						
Block 02 Lot 03	9.0	7.9	90.0						
Block 02 Lot 03	14.0	13.0	88.2						
Block 02 Lot 03	19.0	18.3	90.3						
Block 02 Lot 04	4.0	8.5	85.5						
Block 02 Lot 04	9.0	9.9	90.0						
Block 02 Lot 04	14.0	12.4	91.6						
Block 02 Lot 04	19.0	17.8							
Block 02 Lot 05	4.0	14.0	73.4						
Block 02 Lot 05	9.0	7.7	78.2	26	6		69.1	- 1.9	1000
Block 02 Lot 05	14.0	12.0	87.8						
Block 02 Lot 05	19.0	20.6							
Block 02 Lot 06	4.0	10.6	84.4						
Block 02 Lot 06	14.0	16.5	78.0						
Block 02 Lot 06	19.0	21.7	86.4						
Block 02 Lot 07	4.0	10.7	77.0						
Block 02 Lot 07	9.0	8.5	105.9						
Block 02 Lot 07	14.0	22.0							
Block 02 Lot 08	4.0	9.1	86.5	NP	NP	15.3	29.6	- 2.0	1000
Block 02 Lot 08	9.0	11.0	89.5						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 4 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 02 Lot 08	14.0	21.8	73.7						
Block 02 Lot 08	19.0	28.6	78.7						
Block 02 Lot 09	4.0	8.3	90.3						
Block 02 Lot 09	9.0	15.8	95.1						
Block 02 Lot 09	14.0	19.5							
Block 02 Lot 09	19.0	24.3							
Block 02 Lot 10	4.0	5.2	93.0						
Block 02 Lot 10	9.0	22.5	82.8						
Block 02 Lot 10	14.0	19.6	76.9						
Block 02 Lot 10	19.0	20.7	92.1						
Block 02 Lot 11	4.0	12.0	90.3						
Block 02 Lot 11	9.0	14.8	94.8	26	7		57.8	- 0.2	1000
Block 02 Lot 11	14.0	11.9							
Block 02 Lot 11	19.0	16.5	102.3						
Block 03 Lot 01	4.0	11.7	92.6	27	9		42.5		
Block 03 Lot 01	9.0	11.5	94.3						
Block 03 Lot 01	14.0	10.4	95.6						
Block 03 Lot 01	19.0	18.6	94.9						
Block 03 Lot 02	4.0	10.6	86.6						
Block 03 Lot 02	9.0	11.7	116.4						
Block 03 Lot 02	14.0	11.1							
Block 03 Lot 02	19.0	26.5	97.6						
Block 03 Lot 03	4.0	8.0	93.5						
Block 03 Lot 03	9.0	8.8	100.2						
Block 03 Lot 03	14.0	20.1	89.3						
Block 03 Lot 03	19.0	17.7	81.9						
Block 03 Lot 04	4.0	7.1	102.1						
Block 03 Lot 04	9.0	4.4	92.2	NP	NP	0.0	40.1	- 1.3	1000
Block 03 Lot 04	14.0	14.0	91.8						
Block 03 Lot 04	19.0	18.6	88.7						
Block 03 Lot 05	4.0	8.3	94.9						
Block 03 Lot 05	9.0	5.8	100.7						
Block 03 Lot 05	14.0	22.4	93.0						
Block 03 Lot 05	19.0	22.0	88.7						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 5 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 03 Lot 06	4.0	7.8	93.5						
Block 03 Lot 06	9.0	8.2	93.7	NP	NP		26.3	- 0.9	1000
Block 03 Lot 06	14.0	15.4	83.7						
Block 03 Lot 06	19.0	18.4	79.5						
Block 03 Lot 07	4.0	9.2	91.6						
Block 03 Lot 07	9.0	8.7	92.4						
Block 03 Lot 07	14.0	23.4	91.6						
Block 03 Lot 07	19.0	19.7	90.5						
Block 03 Lot 08	4.0	8.5	94.8						
Block 03 Lot 08	9.0	5.1	100.4						
Block 03 Lot 08	14.0	20.8	95.2						
Block 03 Lot 08	19.0	23.6	90.5						
Block 03 Lot 09	4.0	7.8	93.6						
Block 03 Lot 09	9.0	9.8	104.5						
Block 03 Lot 09	14.0	14.1	69.3						
Block 03 Lot 09	19.0	16.7	100.4						
Block 03 Lot 10	4.0	9.6	81.9	32	19	0.0	62.5	- 8.8	1000
Block 03 Lot 10	9.0	10.4	93.6						
Block 03 Lot 10	14.0	21.4	87.9						
Block 03 Lot 10	19.0	20.4							
Block 03 Lot 11	4.0	10.1	96.6						
Block 03 Lot 11	9.0	11.6	101.1						
Block 03 Lot 11	14.0	9.7							
Block 03 Lot 11	19.0	22.5	94.3						
Block 03 Lot 12	4.0	9.8	90.0						
Block 03 Lot 12	9.0	12.3	96.6	24	11	0.9	41.1	- 1.9	1000
Block 03 Lot 12	14.0	24.4							
Block 03 Lot 12	19.0	20.3	96.9						
Block 03 Lot 13	4.0	8.1	100.2						
Block 03 Lot 13	9.0	10.7							
Block 03 Lot 13	14.0	16.5	99.4						
Block 03 Lot 13	19.0	23.7	100.4						
Block 03 Lot 14	4.0	6.1	95.4						
Block 03 Lot 14	9.0	9.1	88.2						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 6 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 03 Lot 14	14.0	11.5	100.7						
Block 03 Lot 14	19.0	23.1	92.8						
Block 03 Lot 15	4.0	6.9	82.9						
Block 03 Lot 15	9.0	10.3	89.2						
Block 03 Lot 15	14.0	9.9	94.5						
Block 03 Lot 15	19.0	20.8							
Block 03 Lot 16	4.0	7.9	88.3						
Block 03 Lot 16	9.0	9.3	95.9						
Block 03 Lot 16	14.0	6.2	104.3						
Block 03 Lot 16	19.0	20.7							
Block 03 Lot 17	4.0	9.7	96.1	31	17		62.7	- 1.8	1000
Block 03 Lot 17	9.0	6.2	87.4						
Block 03 Lot 17	14.0	13.0	94.1						
Block 03 Lot 17	19.0	19.4	96.2						
Block 03 Lot 18	4.0	7.9	88.3						
Block 03 Lot 18	9.0	9.3	95.9						
Block 03 Lot 18	14.0	6.2	104.3						
Block 03 Lot 18	19.0	20.7							
Block 03 Lot 19	4.0	7.6	93.6						
Block 03 Lot 19	9.0	8.3	96.4						
Block 03 Lot 19	14.0	10.9	89.1					- 1.1	1000
Block 03 Lot 19	19.0	17.9	79.7						
Block 03 Lot 20	4.0	6.8	93.8						
Block 03 Lot 20	9.0	9.4	98.8						
Block 03 Lot 20	14.0	13.3	99.0						
Block 03 Lot 20	19.0	23.2	88.6						
Block 03 Lot 21	4.0	6.3	94.4						
Block 03 Lot 21	9.0	7.6							
Block 03 Lot 21	14.0	13.3	95.1						
Block 03 Lot 21	19.0	18.0	95.1						
Block 03 Lot 22	4.0	7.4							
Block 03 Lot 22	9.0	6.1	97.5						
Block 03 Lot 22	14.0	7.9	87.8						
Block 03 Lot 22	19.0	15.8							

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 7 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 03 Lot 23	4.0	8.8	88.4						
Block 03 Lot 23	9.0	5.7	99.1						
Block 03 Lot 23	14.0	10.3	90.9						
Block 03 Lot 23	19.0	13.0							
Block 03 Lot 24	4.0	6.7	92.2						
Block 03 Lot 24	9.0	7.6	95.4						
Block 03 Lot 24	14.0	10.9	93.5						
Block 03 Lot 24	19.0	8.4	92.1						
Block 03 Lot 25	4.0	6.3	94.6						
Block 03 Lot 25	9.0	8.0	101.9	26	8		47.3	- 2.7	1000
Block 03 Lot 25	14.0	12.2							
Block 03 Lot 25	19.0	18.6	89.7						
Block 04 Lot 01	4.0	6.6	89.9						
Block 04 Lot 01	9.0	8.6	83.4						
Block 04 Lot 01	14.0	15.3	81.7						
Block 04 Lot 01	19.0	19.4	72.3						
Block 04 Lot 02	4.0	6.4	94.3						
Block 04 Lot 02	9.0	10.0	93.9						
Block 04 Lot 02	14.0	15.5	90.5						
Block 04 Lot 02	19.0	18.1	89.1						
Block 04 Lot 03	4.0	5.5	86.9						
Block 04 Lot 03	9.0	10.8	94.7						
Block 04 Lot 03	14.0	14.4	85.6	31	6	0.0	63.2	0.2	1000
Block 04 Lot 03	19.0	19.8	86.0						
Block 04 Lot 04	4.0	6.2	89.6						
Block 04 Lot 04	9.0	9.2	81.6						
Block 04 Lot 04	14.0	17.8	87.9						
Block 04 Lot 04	19.0	22.4	89.4						
Block 04 Lot 05	4.0	6.5	95.1						
Block 04 Lot 05	9.0	8.7	94.7						
Block 04 Lot 05	14.0	20.3	92.1						
Block 04 Lot 05	19.0	19.5	91.7						
Block 04 Lot 06	4.0	6.2	89.5	28	14		55.6	- 6.9	1000
Block 04 Lot 06	9.0	10.2	96.1						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 8 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 04 Lot 06	14.0	15.0	82.7						
Block 04 Lot 06	19.0	21.1	95.2						
Block 04 Lot 07	4.0	6.1	91.0						
Block 04 Lot 07	9.0	14.8	95.3	30	15		65.0	- 1.5	1000
Block 04 Lot 07	14.0	20.2	83.4						
Block 04 Lot 07	19.0	16.3	81.8						
Block 04 Lot 08	4.0	5.8	100.2						
Block 04 Lot 08	9.0	10.8	87.0						
Block 04 Lot 08	14.0	20.2	94.1						
Block 04 Lot 08	19.0	18.5	90.0						
Block 04 Lot 09	4.0	6.7	99.0						
Block 04 Lot 09	9.0	9.1	94.3						
Block 04 Lot 09	14.0	33.9	96.5						
Block 04 Lot 09	19.0	16.3	87.5						
Block 04 Lot 10	4.0	7.7	89.3						
Block 04 Lot 10	9.0	7.5	90.3						
Block 04 Lot 10	14.0	14.3	90.7						
Block 04 Lot 10	19.0	16.6	102.3						
Block 04 Lot 11	4.0	9.4	92.4						
Block 04 Lot 11	9.0	10.7	89.5						
Block 04 Lot 11	14.0	21.6	86.5						
Block 04 Lot 11	19.0	22.2	83.8						
Block 04 Lot 12	4.0	8.2	103.2						
Block 04 Lot 12	9.0	9.9	89.8						
Block 04 Lot 12	14.0	16.8	98.2					- 0.1	1000
Block 04 Lot 12	19.0	28.2	86.0						
Block 04 Lot 13	4.0	9.3	83.3						
Block 04 Lot 13	9.0	5.5	105.6						
Block 04 Lot 13	14.0	15.6	100.5						
Block 04 Lot 13	19.0	21.8	103.6						
Block 04 Lot 14	4.0	12.8	86.5						
Block 04 Lot 14	9.0	14.2	93.3	33	17		30.6	- 2.1	1000
Block 04 Lot 14	14.0	12.0	101.3						
Block 04 Lot 14	19.0	22.9	109.2						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 9 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 04 Lot 15	4.0	11.2	96.6						
Block 04 Lot 15	9.0	7.8	89.8						
Block 04 Lot 15	14.0	14.2	102.5						
Block 04 Lot 15	19.0	18.9							
Block 04 Lot 16	4.0	9.3	103.6	31	19	0.0	48.3	0.2	1000
Block 04 Lot 16	9.0	9.4	97.9						
Block 04 Lot 16	14.0	12.4	106.0						
Block 04 Lot 16	19.0	27.6							
Block 04 Lot 17	4.0	6.9	97.2						
Block 04 Lot 17	9.0	8.0	99.4						
Block 04 Lot 17	14.0	15.2	81.2						
Block 04 Lot 17	19.0	21.9	95.8						
Block 04 Lot 18	4.0	6.9	97.8						
Block 04 Lot 18	9.0	8.7	95.5						
Block 04 Lot 18	14.0	16.0	96.2						
Block 04 Lot 18	19.0	23.1	91.5						
Block 04 Lot 19	4.0	7.8	91.6						
Block 04 Lot 19	9.0	9.8	92.3						
Block 04 Lot 19	14.0	14.8							
Block 04 Lot 19	19.0	21.8							
Block 04 Lot 20	4.0	6.7	85.1						
Block 04 Lot 20	9.0	8.9	86.5						
Block 04 Lot 20	14.0	18.9	93.7						
Block 04 Lot 20	19.0	17.2	110.0						
Block 04 Lot 21	4.0	6.7	87.5						
Block 04 Lot 21	9.0	9.4	93.8	30	16		67.2	- 2.3	1000
Block 04 Lot 21	14.0	20.2	93.4						
Block 04 Lot 21	19.0	21.3	96.3						
Block 04 Lot 22	4.0	5.7	89.4						
Block 04 Lot 22	9.0	8.3	86.4						
Block 04 Lot 22	14.0	11.5							
Block 04 Lot 22	19.0	18.3							
Block 04 Lot 23	4.0	7.2	98.3						
Block 04 Lot 23	9.0	7.9	77.5						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 10 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 04 Lot 23	14.0	11.7	89.2						
Block 04 Lot 23	19.0	18.1	99.0						
Block 04 Lot 24	4.0	6.1	91.6	26	9		48.6	- 7.2	1000
Block 04 Lot 24	9.0	7.8	93.9						
Block 04 Lot 24	14.0	27.3	96.7						
Block 04 Lot 24	19.0	20.3	88.0						
Block 04 Lot 25	4.0	6.3	96.1						
Block 04 Lot 25	9.0	8.9	92.8						
Block 04 Lot 25	14.0	12.8	91.4						
Block 04 Lot 25	19.0	17.8							
Block 05 Lot 01	4.0	11.7	114.9	33	20		73.4	0.0	1000
Block 05 Lot 01	9.0	21.5	98.3						
Block 05 Lot 01	14.0	26.2	95.9						
Block 05 Lot 01	19.0	30.1	87.9						
Block 05 Lot 02	4.0	13.2	112.6						
Block 05 Lot 02	9.0	13.8	110.5						
Block 05 Lot 03	4.0	14.1	107.6						
Block 05 Lot 03	9.0	14.4	109.7						
Block 05 Lot 03	14.0	19.6	105.6						
Block 05 Lot 03	19.0	21.9	92.7						
Block 05 Lot 04	4.0	8.8							
Block 05 Lot 04	9.0	12.5	110.3	29	13		60.5	- 0.9	1000
Block 05 Lot 04	14.0	15.5	109.3						
Block 05 Lot 04	19.0	15.2	110.6						
Block 05 Lot 05	4.0	7.9	110.1					- 3.9	1000
Block 05 Lot 05	9.0	11.5	115.1						
Block 05 Lot 05	14.0	16.8	107.6						
Block 05 Lot 05	19.0	21.2	99.5						
Block 05 Lot 06	4.0	9.7	105.7	41	25		78.8	5.4	1000
Block 05 Lot 06	9.0	13.4	114.8						
Block 05 Lot 06	14.0	13.3	114.4						
Block 05 Lot 06	19.0	21.8	105.2						
Block 05 Lot 07	4.0	8.2	106.8						
Block 05 Lot 07	9.0	14.5	113.0						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 11 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 05 Lot 07	14.0	18.7	106.2						
Block 05 Lot 07	19.0	18.8							
Block 05 Lot 08	4.0	10.8	98.6						
Block 05 Lot 08	9.0	16.7	122.5						
Block 05 Lot 08	14.0	14.4	113.6						
Block 05 Lot 08	19.0	21.0	99.8						
Block 05 Lot 09	4.0	8.5	109.4						
Block 05 Lot 09	9.0	16.1	106.9						
Block 05 Lot 09	14.0	14.8	111.3						
Block 05 Lot 09	19.0	8.5	114.5						
Block 05 Lot 10	4.0	7.1	112.0					- 6.3	
Block 05 Lot 10	9.0	8.2	113.7						
Block 05 Lot 10	14.0	16.9	108.0						
Block 05 Lot 10	19.0	23.4	102.6						
Block 05 Lot 11	4.0	8.5	109.7						
Block 05 Lot 11	9.0	9.6	108.9	25	7		45.2	- 0.8	1000
Block 05 Lot 11	14.0	14.8	111.5						
Block 05 Lot 11	19.0	21.6	105.0						
Block 05 Lot 12	4.0	8.8	106.9						
Block 05 Lot 12	9.0	9.2	108.7						
Block 05 Lot 12	14.0	14.4	113.0						
Block 05 Lot 12	19.0	19.5	101.0						
Block 05 Lot 13	4.0	8.3	100.0						
Block 05 Lot 13	9.0	8.9	115.9						
Block 05 Lot 13	14.0	9.3	116.4						
Block 05 Lot 13	19.0	19.4	109.2						
Block 05 Lot 14	4.0	5.6	111.5						
Block 05 Lot 14	9.0	12.5	112.7						
Block 05 Lot 14	14.0	14.7	107.2						
Block 05 Lot 14	19.0	20.9	103.9						
Block 05 Lot 15	4.0	6.8	113.8	33	16		54.7	0.2	1000
Block 05 Lot 15	9.0	9.6	113.0						
Block 05 Lot 15	14.0	15.7	110.4						
Block 05 Lot 15	19.0	21.2	104.7						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 12 OF 13
DATE Mar/30/2021

Test Boring No.	Depth	Water Content (%)	Dry Density (pcf)	Liquid Limit	Plasticity Index	% Retained No.4 Sieve	% Passing No. 200 Sieve	% Swell/ Collapse	Load (psf)
Block 05 Lot 16	4.0	8.5	103.9						
Block 05 Lot 16	9.0	11.8	114.4						
Block 05 Lot 16	14.0	16.8	113.1						
Block 05 Lot 16	19.0	20.3	107.2						
Block 05 Lot 17	4.0	11.8	107.2						
Block 05 Lot 17	9.0	14.0	111.1						
Block 05 Lot 17	14.0	18.8	118.6						
Block 05 Lot 17	19.0	20.0	106.6						

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics




Geotechnical
Materials Testing
Civil, Planning

Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

SUMMARY OF LABORATORY TEST RESULTS

JOB No. 180135
FIGURE No. 57
PAGE 13 OF 13
DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 01 Lot 02	9.0	CLAYEY SAND(SC)	26	17	9
⊠ Block 01 Lot 04	4.0	CLAYEY SAND(SC)	28	16	12
▲ Block 01 Lot 07	9.0	LEAN CLAY with SAND(CL)	29	16	13
★ Block 01 Lot 12	4.0	CLAYEY SAND(SC)	25	16	9
⊙ Block 01 Lot 15	9.0	SANDY LEAN CLAY(CL)	26	12	14

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 01 Lot 02	9.0	0.0	52.7	47.3	
⊠ Block 01 Lot 04	4.0	0.0	64.1	35.9	
▲ Block 01 Lot 07	9.0	0.0	29.4	70.6	
★ Block 01 Lot 12	4.0	0.0	72.7	27.3	
⊙ Block 01 Lot 15	9.0	0.0	50.0	50.0	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)

2910 Austin Bluffs Parkway

Colorado Springs, CO 80918

(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 58

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 01 Lot 18	14.0	SANDY SILT (ML)	NP	NP	NP
⊠ Block 01 Lot 22	4.0	SANDY LEAN CLAY (CL)	26	17	9
▲ Block 01 Lot 26	9.0	SILTY, CLAYEY SAND (SC-SM)	24	19	5
★ Block 02 Lot 02	4.0	SANDY LEAN CLAY (CL)	28	17	11
⊙ Block 02 Lot 05	9.0	SANDY SILTY CLAY (CL-ML)	26	20	6

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 01 Lot 18	14.0	0.0	40.4	59.6	
⊠ Block 01 Lot 22	4.0	0.0	47.9	52.1	
▲ Block 01 Lot 26	9.0	0.0	57.5	42.5	
★ Block 02 Lot 02	4.0	0.0	47.6	52.4	
⊙ Block 02 Lot 05	9.0	0.0	30.9	69.1	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)

2910 Austin Bluffs Parkway

Colorado Springs, CO 80918

(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 59

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 02 Lot 08	4.0	SILTY SAND with GRAVEL(SM)	NP	NP	NP
⊠ Block 02 Lot 11	9.0	SANDY SILTY CLAY(CL-ML)	26	19	7
▲ Block 03 Lot 01	4.0	CLAYEY SAND(SC)	27	18	9
★ Block 03 Lot 04	9.0	SILTY SAND(SM)	NP	NP	NP
⊙ Block 03 Lot 06	9.0	SILTY SAND(SM)	NP	NP	NP

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 02 Lot 08	4.0	15.3	55.1	29.6	
⊠ Block 02 Lot 11	9.0	0.0	42.2	57.8	
▲ Block 03 Lot 01	4.0	0.0	57.5	42.5	
★ Block 03 Lot 04	9.0	0.0	59.9	40.1	
⊙ Block 03 Lot 06	9.0	0.0	73.7	26.3	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 60

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 03 Lot 10	4.0	SANDY LEAN CLAY(CL)	32	13	19
⊠ Block 03 Lot 12	9.0	CLAYEY SAND(SC)	24	13	11
▲ Block 03 Lot 17	4.0	SANDY LEAN CLAY(CL)	31	14	17
★ Block 03 Lot 25	9.0	CLAYEY SAND(SC)	26	18	8
⊙ Block 04 Lot 03	14.0	SANDY SILT(ML)	31	25	6

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 03 Lot 10	4.0	0.0	37.5	62.5	
⊠ Block 03 Lot 12	9.0	0.9	58.0	41.1	
▲ Block 03 Lot 17	4.0	0.0	37.3	62.7	
★ Block 03 Lot 25	9.0	0.0	52.7	47.3	
⊙ Block 04 Lot 03	14.0	0.0	36.8	63.2	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)

2910 Austin Bluffs Parkway

Colorado Springs, CO 80918

(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 61

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 04 Lot 06	4.0	SANDY LEAN CLAY(CL)	28	14	14
⊠ Block 04 Lot 07	9.0	SANDY LEAN CLAY(CL)	30	15	15
▲ Block 04 Lot 14	9.0	CLAYEY SAND(SC)	33	16	17
★ Block 04 Lot 16	4.0	CLAYEY SAND(SC)	31	12	19
⊙ Block 04 Lot 21	9.0	SANDY LEAN CLAY(CL)	30	14	16

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 04 Lot 06	4.0	0.0	44.4	55.6	
⊠ Block 04 Lot 07	9.0	0.0	35.0	65.0	
▲ Block 04 Lot 14	9.0	0.0	69.4	30.6	
★ Block 04 Lot 16	4.0	0.0	51.7	48.3	
⊙ Block 04 Lot 21	9.0	0.0	32.8	67.2	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 62

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 04 Lot 24	4.0	CLAYEY SAND(SC)	26	17	9
⊠ Block 05 Lot 01	4.0	LEAN CLAY with SAND(CL)	33	13	20
▲ Block 05 Lot 04	9.0	SANDY LEAN CLAY(CL)	29	16	13
★ Block 05 Lot 06	4.0	LEAN CLAY with SAND(CL)	41	16	25
⊙ Block 05 Lot 11	9.0	SILTY, CLAYEY SAND(SC-SM)	25	18	7

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 04 Lot 24	4.0	0.0	51.4	48.6	
⊠ Block 05 Lot 01	4.0	0.0	26.6	73.4	
▲ Block 05 Lot 04	9.0	0.0	39.5	60.5	
★ Block 05 Lot 06	4.0	0.0	21.2	78.8	
⊙ Block 05 Lot 11	9.0	0.0	54.8	45.2	

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs, (Corporate Office)

2910 Austin Bluffs Parkway

Colorado Springs, CO 80918

(719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SOIL CLASSIFICATION DATA

JOB No. 180135

FIGURE No. 63

DATE Mar/30/2021



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Test Boring	Depth (ft)	Classification	LL	PL	PI
● Block 05 Lot 15	4.0	SANDY LEAN CLAY(CL)	33	17	16

Test Boring	Depth (ft)	%Gravel	%Sand	%Silt	%Clay
● Block 05 Lot 15	4.0	0.0	45.3	54.7	

ROCKY MOUNTAIN GROUP



Architectural
Structural
Forensics

Geotechnical
Materials Testing
Civil, Planning

Colorado Springs, (Corporate Office)
2910 Austin Bluffs Parkway
Colorado Springs, CO 80918
(719) 548-0600


SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

SOIL CLASSIFICATION DATA

JOB No. 180135


FIGURE No. 64

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 02 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **90.9 PCF**
 NATURAL MOISTURE CONTENT: **8.6%**
 PERCENT SWELL/COMPRESSION: **- 5.9**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 04 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **94.2 PCF**
 NATURAL MOISTURE CONTENT: **6.0%**
 PERCENT SWELL/COMPRESSION: **- 2.6**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 65

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sandy Clay**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 07 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **102.8 PCF**
 NATURAL MOISTURE CONTENT: **14.2%**
 PERCENT SWELL/COMPRESSION: **- 0.8**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 12 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **92.9 PCF**
 NATURAL MOISTURE CONTENT: **6.7%**
 PERCENT SWELL/COMPRESSION: **- 6.6**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 66

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sandy Clay**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 15 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **95.4 PCF**
 NATURAL MOISTURE CONTENT: **9.0%**
 PERCENT SWELL/COMPRESSION: **- 3.5**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, Sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 22 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **93.2 PCF**
 NATURAL MOISTURE CONTENT: **7.6%**
 PERCENT SWELL/COMPRESSION: **- 5.0**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 67

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, silty, clayey**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 01 Lot 26 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **96.6 PCF**
 NATURAL MOISTURE CONTENT: **8.4%**
 PERCENT SWELL/COMPRESSION: **- 3.2**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 02 Lot 02 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **91.7 PCF**
 NATURAL MOISTURE CONTENT: **8.4%**
 PERCENT SWELL/COMPRESSION: **- 4.1**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 68

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy, silty**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 02 Lot 05 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **86.3 PCF**
 NATURAL MOISTURE CONTENT: **7.0%**
 PERCENT SWELL/COMPRESSION: **- 1.9**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, silty**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 02 Lot 08 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **87.7 PCF**
 NATURAL MOISTURE CONTENT: **9.3%**
 PERCENT SWELL/COMPRESSION: **- 2.0**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 69

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy, silty**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 02 Lot 11 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **98.8 PCF**
 NATURAL MOISTURE CONTENT: **13.7%**
 PERCENT SWELL/COMPRESSION: **- 0.2**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Siltstone**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 04 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **94.8 PCF**
 NATURAL MOISTURE CONTENT: **7.1%**
 PERCENT SWELL/COMPRESSION: **- 1.3**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs: (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 70

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Silty Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 06 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **90.4 PCF**
 NATURAL MOISTURE CONTENT: **8.1%**
 PERCENT SWELL/COMPRESSION: **- 0.9**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 10 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **89.7 PCF**
 NATURAL MOISTURE CONTENT: **9.8%**
 PERCENT SWELL/COMPRESSION: **- 8.8**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 71

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey, sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 12 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **104.9 PCF**
 NATURAL MOISTURE CONTENT: **10.6%**
 PERCENT SWELL/COMPRESSION: **- 1.9**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 17 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **98.3 PCF**
 NATURAL MOISTURE CONTENT: **9.6%**
 PERCENT SWELL/COMPRESSION: **- 1.8**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 72

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Silty Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 19 @ 14 FT**
 NATURAL DRY UNIT WEIGHT: **88.4 PCF**
 NATURAL MOISTURE CONTENT: **11.0%**
 PERCENT SWELL/COMPRESSION: **- 1.1**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, clayey**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 03 Lot 25 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **94.9 PCF**
 NATURAL MOISTURE CONTENT: **9.0%**
 PERCENT SWELL/COMPRESSION: **- 2.7**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 73

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, silty**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 03 @ 14 FT**
 NATURAL DRY UNIT WEIGHT: **107.5 PCF**
 NATURAL MOISTURE CONTENT: **14.1%**
 PERCENT SWELL/COMPRESSION: **0.2**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 06 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **88.5 PCF**
 NATURAL MOISTURE CONTENT: **8.2%**
 PERCENT SWELL/COMPRESSION: **- 6.9**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 74

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 07 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **98.5 PCF**
 NATURAL MOISTURE CONTENT: **15.1%**
 PERCENT SWELL/COMPRESSION: **- 1.5**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sandy Clayey Silt**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 12 @ 14 FT**
 NATURAL DRY UNIT WEIGHT: **110.5 PCF**
 NATURAL MOISTURE CONTENT: **16.1%**
 PERCENT SWELL/COMPRESSION: **- 0.1**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 75

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 14 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **94.9 PCF**
 NATURAL MOISTURE CONTENT: **11.8%**
 PERCENT SWELL/COMPRESSION: **- 2.1**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clayey Sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 16 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **106.0 PCF**
 NATURAL MOISTURE CONTENT: **10.1%**
 PERCENT SWELL/COMPRESSION: **0.2**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 76

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 21 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **95.1 PCF**
 NATURAL MOISTURE CONTENT: **8.5%**
 PERCENT SWELL/COMPRESSION: **- 2.3**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, Clayey**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 04 Lot 24 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **92.9 PCF**
 NATURAL MOISTURE CONTENT: **6.0%**
 PERCENT SWELL/COMPRESSION: **- 7.2**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 77

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 01 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **115.7 PCF**
 NATURAL MOISTURE CONTENT: **11.4%**
 PERCENT SWELL/COMPRESSION: **0.0**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sand**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 04 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **108.4 PCF**
 NATURAL MOISTURE CONTENT: **11.5%**
 PERCENT SWELL/COMPRESSION: **- 0.9**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 78

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 05 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **97.9 PCF**
 NATURAL MOISTURE CONTENT: **6.1%**
 PERCENT SWELL/COMPRESSION: **- 3.9**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 06 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **116.1 PCF**
 NATURAL MOISTURE CONTENT: **10.7%**
 PERCENT SWELL/COMPRESSION: **5.4**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135


FIGURE No. 79

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 10 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **90.3 PCF**
 NATURAL MOISTURE CONTENT: **6.8%**
 PERCENT SWELL/COMPRESSION: **- 6.3**



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Sand, silty, clayey**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 11 @ 9 FT**
 NATURAL DRY UNIT WEIGHT: **107.6 PCF**
 NATURAL MOISTURE CONTENT: **9.1%**
 PERCENT SWELL/COMPRESSION: **- 0.8**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO


Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135

FIGURE No. 80

DATE Mar/30/2021



PROJECT: **Sunset Ridge Severance**
 SAMPLE DESCRIPTION: **Clay, sandy**
 NOTE: **SAMPLE WAS INUNDATED WITH WATER AT 1000 PSF**

SAMPLE LOCATION: **Block 05 Lot 15 @ 4 FT**
 NATURAL DRY UNIT WEIGHT: **121.0 PCF**
 NATURAL MOISTURE CONTENT: **7.0%**
 PERCENT SWELL/COMPRESSION: **0.2**

ROCKY MOUNTAIN GROUP

Architectural
Structural
Forensics



Colorado Springs - (Corporate Office)
 2910 Austin Bluffs Parkway
 Colorado Springs, CO 80918
 (719) 548-0600

SOUTHERN COLORADO, DENVER METRO, NORTHERN COLORADO

Geotechnical
Materials Testing
Civil, Planning

SWELL/CONSOLIDATION TEST RESULTS

JOB No. 180135

FIGURE No. 81

DATE Mar/30/2021