



POST FRAME GARAGE 24' x 32' x 8'

\$37,374.00

PRICING VALID
UNTIL: 03/31/26

TOTAL ESTIMATED COST INCLUDES:

- | | |
|--|---|
| 24' x 8' porch with metal ceiling | #1 - 26 Gauge Standing Seam Roof |
| 24' x 24' area to be enclosed | #1 - 29 Gauge Ag-Panel Sides |
| 2 - 9' x 7' Insulated Overhead Doors | 3' Metal Wainscot on two sides |
| 1 - 3' Steel Walk Door with Lockset | 3' Stone Wainscot on two sides |
| 2 - 32" x 36" Single Hung Windows | 1' Overhang with Soffit and Fascia |
| Trusses 4' o.c. with 4/12 pitch | 5" Gutters and Downspouts |
| Treated 6x6 - Ground Contact Posts | 4" Concrete Floor with Wire and Plastic |
| Roof Insulated with 1/4" Solar Eclipse | 2" Fill Rock under Concrete floor |
| Walls Insulated with 1/2" Ox-Board | 1 - 4" x 6' Trench Drain in Concrete |

**STOP IN TO
SEE OUR
DISPLAY
BUILDINGS
ON SITE!**

OPTIONS AND AVAILABLE UPGRADES

- | | |
|---------------------------------|------------|
| Row of Glass in Overhead Doors | \$789.00 |
| 2 - Overhead Door Openers | \$1,470.00 |
| 3' Stone Wainscot on all Sides | \$6,860.00 |
| 9-Lite Glass in Walk Door | \$250.00 |
| Metal Interior Ceiling Liner | \$1,896.00 |
| 2' x 2' Cupola with weathervane | \$897.00 |

(812) 683 - 4600

2875 US 231 HUNTINGBURG, IN 47542

website - www.banda-construction.com

email - info@banda-construction.com

