A D D E N D U M N O. 3

SHAWNEE OAKS SANITARY SEWER SYSTEM

ALLEN COUNTY, OHIO

Project No. C25073.4A

Index of Contents

Addendum No. 3, 2 Item, 2 pages total (including attachments)

Attachments
None

November 12, 2026

I hereby certify that this Addendum was prepared by me or under my direct supervision and that I am a duly registered Engineer under the Laws of the State of Ohio.

ACCESS ENGINEERING SOLUTIONS, LLC



11-12-2026

TO: ALL BIDDERS OF RECORD

ADDENDUM NO. 3 to Drawings and Specifications for the Shawnee Oaks Sanitary Sewer System Project, Allen County Ohio; as prepared by Access Engineering Solutions, Celina, Ohio.

This Addendum shall hereby be and become a part of the Contract Documents the same as if originally bound thereto.

The following clarifications, amendments, additions, revisions, changes, and modifications change the original Contract Documents only in the amount and to the extent hereinafter specified in this Addendum.

NOTE: Bidders are responsible for becoming familiar with every item of this Addendum and acknowledge the receipt of said addendum on the bid forms.

ITEM NO. 1 - Specification Section 16220– Engine Generators

Part 1 – General
1.2 Summary

Delete: 1. Propane Gas

Insert: 1. Natural Gas

Part 2 – Products
2.3 Engine

Delete: A. Fuel: Diesel

Insert: A. Fuel: Natural Gas

C. Engine Fuel System

Delete: 1. Main Fuel pump: Mounted on engine. Pump ensures adequate primary fuel flow under starting and load conditions.
2. Relief bypass valve: Automatically regulatespressure in the fuel line and returns excess fuel to source.

Insert: 1. Provide regulator and gas shut off valve for natural gas.

2.5 Generator Overcurrent and Fault Protection

Delete: A. Generator 250 amp

Insert: A. Generator 200 amp

ITEM NO. 2 – Construction Drawings – Shawnee Oaks Sanitary Sewer System

Sheet 32 of 44

The concrete pad around the lift station is 34’ x 25’ wide. The concrete pad thickness and rebar requirements shall follow the detail for concrete commercial drive shown on sheet 40 of 44.