

PROVIDENCE REVOLVING FUND
Contractor Bid Form - Windows
49 Central Ave, North Providence, RI 02911

By submitting this bid, the contractor attests that they will be available to begin work within 30 days of the bid due date.

ITEM	COST
<u>GENERAL REQUIREMENTS:</u> Contractor shall be responsible for obtaining any necessary permits for any and all work as is required by local and national and local code or jurisdiction requirements. Contractor shall also be responsible for any necessary drawings that may be required to obtain permits. Contractor shall be responsible for any required submittal to local authorities. Contractor shall be responsible for maintaining copies of any required permits at the job - site, and to supply Consultant copies of as requested. Contractor shall be responsible for supplying any bonds, insurance cert's, sub - contractor licenses, EPA licenses, specialty licenses to building departments and consultant. All documents shall be delivered in a timely fashion. Contractor shall apply for permits as soon as possible.	\$
<u>WINDOWS:</u> (21 Windows) Install new replacement windows in existing openings. Windows shall be; new white vinyl thermal with Argon filled vapor barrier, with welded corners (no mechanical fasteners), with half screens. Work shall include but not be limited to; windows shall be properly shimmed, caulked, insulated, secured into the framed opening for proper operation, interior/exterior trim removed and reinstalled, pre-finished aluminum cladding on exterior trim.	\$
<u>WINDOWS:</u> (4 basement windows) Install new replacement basement windows in existing openings. Windows shall be; new white vinyl thermal with Argon filled vapor barrier, with welded corners (no mechanical fasteners), with half screens. Work shall include but not be limited to; windows shall be properly shimmed, caulked, insulated, secured into the framed opening for proper operation, exterior trim removed and reinstalled, pre-finished aluminum cladding on exterior trim.	\$
<u>ASBESTOS INSULATION:</u> Contractor shall remove existing asbestos pipe insulation in basement area. Work shall be completed in accordance with EPA requirements. Contractor shall be a licensed asbestos remediation company and shall remove or wrap asbestos in accordance with; HUD, EPA, State of RI, OSHA requirements. Contractors shall remove all debris from the job-site and dispose of in accordance with required disposal methods	\$
TOTAL:	\$

All repairs must be performed in conformance with local zoning ordinances, codes, and jurisdictional requirements. All work is to be completed in accordance with manufacturer's instructions and specifications, to industry standards, and in a good workmanship like fashion. All material and labor shall be warranted, and written warranties shall be given to the homeowner at the end of the job.

Contractor: _____

Date: _____

License No: _____