

PROVIDENCE REVOLVING FUND
Contractor Bid Form - Heating/Plumbing
52 Intervale Rd, Cranston, RI 02910

By submitting this bid, the contractor attests that they will be available to begin work within 30 days of the bid due date.

| ITEM | COST |
|---|------|
| <u>GENERAL REQUIREMENTS:</u> Contractor shall be responsible for obtaining any necessary permits for any and all work as is required by local and national and local code or jurisdiction requirements. Contractor shall also be responsible for any necessary drawings that may be required to obtain permits. Contractor shall be responsible for any required submittal to local authorities. Contractor shall be responsible for maintaining copies of any required permits at the job - site, and to supply Consultant copies of as requested. Contractor shall be responsible for supplying any bonds, insurance cert's, sub - contractor licenses, EPA licenses, specialty licenses to building departments and consultant. All documents shall be delivered in a timely fashion. Contractor shall apply for permits as soon as possible. | \$ |
| <u>THERMOSTAT (2):</u> Contractor shall furnish and install new digital thermostat in place of existing. Contractor shall make sure new thermostat is functioning properly with HVAC system and properly interfaces. Work shall include any necessary wiring and wiring harness as necessary for proper operation of new thermostat. Contractor shall install any necessary batteries in unit. Contractor shall program unit if necessary for proper operation of HVAC system. Contractor shall orientate homeowner on proper operation of thermostat, and give him units instruction manual. | \$ |
| <u>DIRECT VENT HEATING:</u> Contractor shall furnish and install furnace/hot water direct vent system in basement (2 zones). Contractor shall remove the existing gas fired heat/hot water boiler system (DV) and replace with a direct vent boiler system. Work shall include removing the existing boiler system and replacing all heating elements in rooms. Contractor responsible for removal and clean out the existing heating units and feeder. | \$ |
| <u>HEATING - BASEBOARDS:</u> Contractor shall furnish and supply new heating baseboards where existing is already located. Contractor shall be responsible for correct sizing per location. Contractor to remove and dispose of existing baseboards. | \$ |
| <u>GAS LINE:</u> Contractor shall furnish and install gas line from exterior to interior of basement. | \$ |
| <u>PLUMBING WASTE:</u> Contractor shall remove all damaged waste systems and replace with new PVC system. Work shall include but not be limited to; new waste lines to existing toilet, vanity and shower fixtures. Line size shall be determined by a licensed plumber in accordance with national and local code and jurisdictional requirements. | \$ |
| <u>COMMODE:</u> Contractor shall remove the old toilet (1) and install new toilet in existing bathroom. Each fixture shall have its own shut off valve at the fixtures. Contractor shall make sure installation is level, and properly secure to the floor. Contractor shall install with new wax ring Contractor shall test all units work properly, with no leaks. Contractor shall caulk the base of the toilet to the tile floor after proper operation is confirmed | \$ |
| TOTAL: | \$ |

All repairs must be performed in conformance with local zoning ordinances, codes, and jurisdictional requirements. All work is to be completed in accordance with manufacturer's instructions and specifications, to industry standards, and in a good workmanship like fashion. All material and labor shall be warranted, and written warranties shall be given to the homeowner at the end of the job.

Contractor: _____

Date: _____

License No: _____