Pre-Travel Checklist

INTERIOR	☐ Cushions have been laid down	Jacks and support legs raised.
Locking Bolts on Fridge tray slides and Kitchen slides are locked in place before moving your trailer Dead lock on Entry door engaged	prior to closing the camper trailer. Camper trailer has been packed to ensure correct weight distribution Batteries have been fully charged	Release handbrake - remove wheel chocks if used. Safety chains secured to the tow vehicle in a cross over pattern
and locked before moving trailer. Roof closed and locked. Make sure there is no canvas tent sticking out underneath the seals.	Navigator models with internal toilet/shower raise the mirror before lowering the roof	under the hitch. Adjust towing mirrors if used. Air Con Vent Covers are closed (located underneath the camper
All lockers and drawers securely closed and dead bolts engaged. Secure all appliances.	EXTERIOR Tyres - check pressure and adjust	trailer) 240v electrical extension lead disconnected.
Refrigerator packed securely – door locked.	including spares Check whether wheel nuts are present and tightened to	Positive Pressure system has been turned on (if fitted)
Fire extinguisher is located inside the camper trailer and correctly secured	manufacturers specifications. Brakes checked and adjusted. Water tank filled. Note- rear water	Boat loaders and/or items located on top of the camper trailer have been loaded to ensure correct
All large and heavy items in drawers and compartments are secured properly to prevent movement in transport	tank can be filled to help set correct ball weight, it is customers responsibility to check and set ball weight correct before each trip.	weight distribution. Winch strap secured correctly 7Pin trailer plug and anderson plug have been correctly attached
Strip lighting cables have not been damaged during closure of the Camper Trailer	Lights operating correctly. Wheel bearings checked for no loose abnormal movement of the wheel	to tow vehicle and electric brakes function correctly Registration plate has not been
Stereo power has been switched off and power isolated at Batteries	Jockey wheel has been raised and secured.	obscured by objects installed in the rear bike carrier receiver
Air conditioner has been turned off Gas bottles turned off - Gas cooker locked, and stove top lid secured	Trailer coupling attached to the tow vehicle securely locked in position.	Grey water tanks have been emptied (if required) Toilet canister has been emptied (if
TV removed from roof of camper and secured (Navigators only)	Doors locked - steps raised and locked in place. Deadlock on main door engaged.	required)