

- Monolithic tank meets ASTM C-1227 Spec. for water and wastewater structures.
- Butyl rubber sealant meets Fed. Spec. SS-S-210A. (Provided with tank)
- All plumbing shown in diagram is 4" SDR 35. (Provided with tank)
- Follow standard practice for installation of underground precast concrete structures. (See page 2 for ASTM C-891 Summary)

Part #	Discharge /	Approximate Weights			
	Cycle	Tank	Lid	Total	
PCA-000-294	7.8 Gal. / Vertical inch.	4,850 lbs	1,520 lbs	6,370 lbs	

True Monolithic

Tank


Note: N.T.S.



Front Range Precast Concrete, Inc.

5901 Dexter Street, Unit 102, Commerce City, CO 80022 Phone (303) 442-3207 - (800) 783-3207 - Fax (303) 442-3209 www.flxx.com

500 Gal. Electric Lift Station



Note: N.T.S.

Part #	Discharge / Cycle	Approximate Weights			
T GITE II		Bottom Section	Top Section	Lid	Total
PCA-000-295	7.8 Gal / Vertical Inch	4,850 lbs	1,740 lbs	1,525 lbs	8,115 lbs

Ø4'-10" -




Front Range Precast Concrete, Inc.

• Follow standard practice for installation of underground precast concrete

5901 Dexter Street, Unit 102, Commerce City, CO 80022 Phone (303) 442-3207 - (800) 783-3207 - Fax (303) 442-3209 www.flxx.com





Part #	Discharge / Cycle	Approximate Weights			
		Tank	Lid	Total	
PCA-000-298	21.5 Gal. / Vertical inch.	6,995 lbs	2,550 lbs	9,545 lbs	

Note: N.T.S.



Front Range Precast Concrete, Inc.

5901 Dexter Street, Unit 102, Commerce City, CO 80022 Phone (303) 442-3207 - (800) 783-3207 - Fax (303) 442-3209 www.flxx.com

