

SUMMARY

This bulletin provides guidelines and best practices for inspecting, storing, and handling Brava roof system materials at job sites and distribution facilities. Proper inspection upon arrival and adherence to storage recommendations ensure product integrity and performance. Store materials on a flat, level surface and remain covered if stored for an extended period. Safe handling practices, including proper lifting procedures and equipment use, must be used to ensure personnel safety and prevent damage during transportation, storage, and installation.

MATERIAL INSPECTION

All Brava Roof System field tiles and accessories must be inspected upon arrival and before installation. Ensure that all materials conform to manufacturer specifications and fit project requirements. Any tiles that exhibit the following issues should be set aside and not installed:

- Deviations from the manufacturer's dimensional specifications
- Damage incurred during shipping or storage
- Any characteristics that do not meet project needs

STORAGE GUIDELINES

- Store materials as they were shipped, keeping them on their original pallet when possible.
- Place pallets on a flat, level surface to maintain product integrity.
- Double stacking of pallets is permitted; use caution to avoid causing damage to the tiles below.
- Do not stack pallets in a manner that deforms the tile.
- Covering material may be required if masonry dust, paint, or other debris is typical or expected nearby.

HANDLING PRECAUTIONS

- Exercise caution during loading, unloading, and storage to ensure safety and prevent material damage from construction vehicles or loading equipment.
- Utilize appropriate safety and lifting procedures and equipment when handling pallets and materials.
- Employ proper lifting equipment and techniques to ensure safe material transport.

CONTENTS

- Material Inspection
- Storage Guidelines
- Handling Precautions
- Resources
- Questions



RESOURCES

Check for updates to this and other [Technical Bulletins](#) on our [Resources Page](#).

Complete Installation Training, View Resources, and Contact Technical Support by visiting our [Technical Support Portal](#).

Revision 2: 6 August 2025 - Allow Double Stacking

QUESTIONS

If you have any questions regarding Brava Roof Tile products and accessories, call 844-290-4196 and ask for Technical Support.

Or contact us through the [Technical Support Portal](#).

