

3.15 MAIN HOUSE: PROPOSED GROUND FLOOR

Proposed Alterations:

To allow for a detailed historic appraisal of the alterations that are proposed to the heritage fabric of Amport House, we have produced a schedule highlighting each amendment and including photographs to allow these to be fully understood, this is included as a separate document as part of this submission.

We have also compiled existing, demolition and proposed drawings which describe these alterations. At the end of this section of the document we have also included a number of details and sketches to describe the alterations to key historic areas of the house.

Proposed Ground Floor:

The ground floor will be sensitively restored, removing the existing bar installed by the MOD and some internal kitchen partitions to reinstate Lord Winchester's Room. Non-original toilets will be rearranged to provide new guest WC's and the non-original garage and oil tanks enclosure will be re-used, using the existing structure to create a new water storage area and staff room. The later addition concrete rendered lean-to structure on the west elevation will be refurbished to create a new glazed garden room.

In the 1990's extension the internal partitions and ceilings will be removed to create family suites with double height spaces that look out over the historic gardens.

