


<b>JOB No.</b>	<b>MASTER</b>
<b>DATE DRAWN</b>	<b>8/14/2018</b>
<b>DATE PRINTED</b>	<b>1/21/2021</b>



GENERAL TRUSS ENGINEERING CRITERIA & DESIGN LOADS	
DESIGN CODE	FBC2020/TP12014
WIND CODE	MWFRS (Directional)/C-C HYBRID WIND ASCE 7-16
WIND LOAD	160 MPH
EXPOSURE CATEGORY	C
OCCUPANCY CATEGORY	II
IMPORTANCE FACTOR	1.0
WIND DURATION FACTOR	1.60
OPENING CONDITIONS	ENCLOSED
TRUSSES HAVE BEEN DESIGNED FOR A 10.0 PSF BOTTOM CHORD LIVE LOAD NONCONCURRENT WITH ANY OTHER LIVE LOADS	
TRUSS LOADING	ROOF
TCLL	20 PSF
TCDL	20 PSF
BCLL	0 PSF
BCDL	10 PSF
TOTAL	50 PSF
DURATION	1.25
TCDL / TO RESIST UPLIFT	5 PSF
BCDL / TO RESIST UPLIFT	5 PSF

**CAUTION!!**

**DO NOT ATTEMPT TO ERECT TRUSSES WITHOUT REFERRING TO THE ENGINEERING DRAWINGS AND BSCI-B1 SUMMARY SHEETS.**

**ALL PERMANENT BRACING MUST BE IN PLACE PRIOR TO LOADING TRUSSES. (ie. SHEATHING, SHINGLES, ETC.)**

**ALL INTERIOR BEARING WALLS MUST BE IN PLACE PRIOR TO INSTALLING TRUSSES.**

**REFER TO FINAL ENGINEERING SHEETS FOR THE FOLLOWING.**

- 1) NUMBER OF GIRDER PLIES AND NAILING SCHEDULE.**
- 2) BEARING BLOCK REQUIREMENTS.**
- 3) SCAB DETAILS (IF REQUIRED)**
- 4) UPLIFT AND GRAVITY REACTIONS.**

**WARNING**  
BACK CHARGES WILL NOT BE  
ACCEPTED REGARDLESS OF FAULT  
WITHOUT PRIOR NOTIFICATION BY  
CUSTOMER WITHIN 48 HOURS AND  
INVESTIGATION BY Builders FirstSource.  
NO EXCEPTIONS.

THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ALL CONNECTIONS OTHER THAN TRUSS TO TRUSS, GABLE SHEAR WALL, AND CONNECTIONS. TEMPORARY AND PERMANENT BRACING, AND CEILING AND ROOF DIAPHRAM CONNECTIONS.

ROOF PITCH	5/12
CEILING PITCH	FLAT
TOP CHORD SIZE	2 x 4 MIN.
BOTTOM CHORD SIZE	2 x 4 MIN.
OVERHANG LENGTH	12"
CANTILEVER	N/A
END CUT	PLUMB
FLOOR TRUSS SPACING	N/A
ROOF TRUSS SPACING	24"

BUILDER	DR Horton
PROJECT	1541 A 160 C RH
MODEL	1541
ADDRESS	--
CITY, STATE	--, FL.
LOT	--
COUNTY	--
DRAWN BY	D.W.
ENG. BY	D.W.


REVISIONS			
No.	DATE	NOTES	BY





























1	1/21/2021	Updated code to FBC2020/TPI2014	D.W.
---	-----------	---------------------------------	------

**IMPORTANT**  
 This Drawing Must Be Approved And Returned  
 Before Fabrication Will Begin. For Your Protection  
 Check All Dimensions And Conditions Prior To  
 Approval Of Plan.  
 SIGNATURE BELOW INDICATES ALL NOTES  
 AND DIMENSIONS HAVE BEEN ACCEPTED.

By \_\_\_\_\_ Date \_\_\_\_\_


6850 Taylor Road Punta Gorda, Fl. 33950  
Phone: 941-575-2250 / Fax:941-575-0319




SIMPSON ROOF AND FLOOR TRUSS HANGER SCHEDULE							
ID	QTY/R	QTY/FL	MODEL	FLOOR	ROOF	UPLIFT	SYMBOL
A*	0	0	LUS24	725	895	490	 A*
A	0	0	HTU26	2940	3200 / 3600	1250 / 1555	 A
B	0	0	HTU28	2820	3895 / 4680	1235 / 2140	 B
C	0	0	HTU26-2	2940	3600	1515 / 2175	 C
D	0	0	HTU28-2	3820	4310 / 4680	1530 / 3485	 D
E	0	0	HGUS26-2	4355	5320	2155	 E
F	0	0	HGUS28-2	7460	7460	3235	 F
G	0	0	HGUS26-3	4355	5230	2155	 G
H	0	0	HGUS28-3	7460	7460	3235	 H
I	0	0	HGUS210-4	9100	9100	4095	 I
J	0	0	SUL26	865	1055	765	 J
K	0	0	SUR26	865	1055	765	 K
L	0	0	SUL210	1440	1760	1250	 L
M	0	0	SUR210	1440	1760	1250	 M
N	0	0	THJA26	2680	3265	960	 N
O	0	0	HJC26	2385	2980	1840	 O
P	N/A	0	HHU546	2790	3410	1550	 P
Q	N/A	0	THA422	2245	2245	1855	 Q
R	N/A	0	THAC422	2245	2245	1855	 R
S	N/A	0	THA426	2435	2435	1855	 S
NOTE: UPLIFT VALUE FOR THA422, THAC422, THA426 HANGERS APPLY ONLY TO FACE MOUNT INSTALLATION							
(1) PLY	(1) PLY	(2) PLY	CORNER HIP		CORNER HIP	(1) PLY FLR. TRUSS	(1) PLY FLR. TRUSS
 LUS24	 HTU26, HTU28	 HTU26-2, HTU28-2	 HGUS26-2, HGUS28-2, HGUS24-3, HGUS28-3	 THJA26	 HJC26	 HHU546	 THA422, THAC422, THA426

- NOTES:
- 1) ALL DIMENSIONS ARE FEET-INCHES-SIXTEENTHS.
  - 2) DO NOT CUT OR ALTER TRUSSES IN ANY WAY.
  - 3) ALL REACTIONS ARE UNDER 5000 LBS. UNLESS NOTE OTHERWISE.
  - 4) ALL UPLIFTS ARE UNDER 1000 LBS. UNLESS NOTED OTHERWISE.
  - 5) FRAMING REQUIRED BELOW TRUSSES TO GET DESIRED CEILING CONDITIONS.
  - 6) ONLY TRUSS TO TRUSS CONNECTIONS SUPPLIED W/ TRUSS PACKAGE.

L:\O-New Data\1 - MASTER 2019\2019-BUILDERS\DK HORTON  
2019\SUBDIVISIONS\BRIGHTWATER\2210 LOT 34 BLK 1 1541 AR\REVIT\2210 1541  
AR.rvt




REAR ELEVATION "AR"  
1/4" = 1'-0"




FRONT ELEVATION "AR"  
1/4" = 1'-0"

- 1 MID-WALL WEEP SCREED AT WOOD MASONRY INTERFACE. INSTALL STRICTLY PER MFG. INSTRUCTIONS
- 2 ROOF / WALL SCREED INSTALL STRICTLY PER MFG. INSTRUCTIONS



LEFT ELEVATION "AR"  
1/4" = 1'-0"



RIGHT ELEVATION "AR"  
1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION



Gulf Coast  
Drafting & Design, Inc.  
EMAIL: PLANS@GULFCOASTDRAFTING.COM  
PHONE: 239-540-8223  
1515 SE 47th ST. CAPE CORAL, FL 33904

LOT: 34 BLOCK: 1  
SUBDIVISION: BRIGHTWATER 40s  
ADDRESS: 8756 SWELL BROOKS COURT  
D.R.H. #: 579330042

MODEL  
1541  
GCD JOB # 12210

DATE: 01/28/21

DRAWN BY: JSL

CHECKED BY: JWC

REVISED:




PLAN: ELEVATION

SCALE: As indicated

A-1 AR



L:\0-New Data\1 -MASTER 2019\2019-BUILDERS\DK HORTON  
2019\SUBDIVISIONS\BRIGHTWATER\2210 LOT 34 BLK I 1541 AR\REVIT\2210 1541  
AR.rvt



DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION



**Gulf Coast**  
Drafting & Design, Inc.  
EMAIL: PLANS@GULFCOASTDRAFTING.COM  
PHONE: 239-540-8222  
1515 SE 47th ST. CAPE CORAL, FL 33904

LOT: 34  
SUBDIVISION: BRIGHTWATER 40s  
ADDRESS: 8756 SWELL BROOKS COURT  
D.R.H. #: 579330042

MODEL  
1541  
GCD JOB # 12210

DATE: 01/28/21

DRAWN BY: JSL

CHECKED BY: JWC

REVISED:

PLAN:  
SLAB & PLUMBING PLAN

SCALE:  
As indicated

A-2 AR

DOOR SCHEDULE						
MARK	DESCRIPTION	MANUFACTURER	HEIGHT	WIDTH	COMMENTS	QTY
1	1 6070 OHGD	GARAGE DOOR	7'-0"	16'-0"		1
2	3068 ENTRY	DISTINCTION	6'-8"	3'-0"		1
3	2-3068 SL. GL. DR.		6'-8"	6'-0"		1

WINDOW SCHEDULE						
MARK	DESCRIPTION	MANUFACTURER	HEIGHT	WIDTH	COMMENTS	QTY
A	25 SH		5'-1"	2'-1 1/4"		2
B	23 SH		3'-0"	2'-1 1/4"		1
C	2-25 SH		5'-1"	6'-2"		2

OPT IMPACT GLASS MAY BE INSTALLED IN LIEU OF SHUTTERS VERIFY W/ CONTRACT



DOOR HEADERS		
6'-8" BI-FOLD	HEADER HEIGHT	82" A.F.F.
6'-8" SWING	HEADER HEIGHT	82 1/2" A.F.F.
8'-0" SWING	HEADER HEIGHT	98 1/2" A.F.F.

PLAN NOTES	
1)	VERIFY ALL ROUGH OPENING DIMENSIONS FOR ALL WINDOWS AND DOORS
2)	PROVIDE SAFETY GLAZING WITHIN 24" FROM EXIT PER FLORIDA BUILDING CODE R 308.4.2.
3)	PROVIDE SAFETY GLAZING AT BATH/ SHOWER PER FLORIDA BUILDING CODE R 308.4.5.
4)	NON BEARING INTERIOR FRAME WALLS SHALL BE FRAMED W/ WOOD OR METAL STUDS. SPACING SHALL NOT EXCEED 24" O.C. (NON BEARING WALLS ONLY)
5)	PROVIDE DEAD WOOD IN ATTIC FOR OVERHEAD GARAGE DOOR HARDWARE
6)	KITCHEN KNEE WALL TO BE FRAMED W/ TOP @ 34 1/2" A.F.F.
7)	INSTALL SMOOTH WALLS IN KITCHEN AND ALL BATHROOM AREAS
8)	WHERE DRYWALL CEILING IS APPLIED TO TRUSSES @ 24" O.C. USE 5/8" DRYWALL OR 1/2" SAG RESISTANT PER SEC. R702.3.5
9)	THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE & ATTIC BY NOT LESS THEN 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. GARAGES BENEATH HABITABLE ROOMS SHALL BE SEPARATED WITH NOT LESS THAN 5/8" TYPE "X" GYPSUM BOARD OR EQUIVALENT. WHERE THE SEPARATION IS A FLOOR - CEILING ASSEMBLY, THE STRUCTURE SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED BY NOT LESS THAN 1/2" GYPSUM BOARD OR EQUIVALENT
10)	INSTALL 1 3/8" THICK SOLID WOOD DOOR BETWEEN LIVING AND GARAGE PER FLORIDA BUILDING CODE R302.5.1.
11)	ALL WINDOWS INSTALLED 72" ABOVE GRADE MUST COMPLY WITH RS12.2 MIN 24" SILL HEIGHT OR PROVIDED WITH AN APPROVED WINDOW FALL PREVENTION DEVICE
12)	ALL CLOSET SHELVES TO BE 12". ALL PANTRY & LINEN TO BE (4)-16" SHELVES 18" O.F.F. W/ 15" INCREMENT.
13)	ALL MECHANICAL AND ELECTRICAL EQUIPMENT TO BE INSTALLED AT OR ABOVE FLOOD PLUS 1'-0" FREEBOARD.



CABINET BACKING		
KITCHEN	UPPER TOP @ 84"	BASE TOP @ 35"
MASTER BATH	UPPER	BASE TOP @ 35"
GUEST BATH	UPPER	BASE TOP @ 31"
LAUNDRY ROOM	UPPER TOP @ 84"	BASE

SQUARE FOOTAGE		
LANAI AREA		102 SF
LIVING AREA		1544 SF
GARAGE AREA		383 SF
ENTRY AREA		74 SF
TOTAL AREA		2102 SF

INTERIOR DOOR SCHEDULE		
MARK	DOOR WIDTH	NOTES
1	3'-0"	P.K. = POCKET DOOR
2	2'-10"	B.F. = BI-FOLD DOOR
3	2'-8"	
4	2'-6"	B.P. = BI-PASS DOOR
5	2'-4"	
6	2'-0"	L.V. = LOUVERED DOOR
7	1'-8"	
8	1'-6"	



GREAT ROOM DETAIL A ELEV  
1/4" = 1'-0"



FLOOR PLAN "AR"  
1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL FLORIDA BUILDING CODE 2020 - 7TH EDITION



Gulf Coast Drafting & Design, Inc.  
EMAIL: PLANS@GULFCOASTDRAFTING.COM  
PHONE: 239-540-1823  
1515 SE 47th ST. CAPE CORAL, FL 33904

LOT: 34	BLOCK: 1
SUBDIVISION: BRIGHTWATER 40s	
ADDRS: 8756 SWELL BROOKS COURT	
D.R.H. #: 579330042	


MODEL	1541
GCD JOB #	12210
DATE:	01/28/21
DRAWN BY:	JSL
CHECKED BY:	JWC
REVISED:	
PLAN:	FLOOR
SCALE:	As indicated
A-3 AR	



L:\O-New Data\1 -MASTER 2019\2019-BUILDERS\DK HORTON  
2019\SUBDIVISIONS\BRIGHTWATER\2210 LOT 34 BLK 1 1541 AR\REVIT\2210 1541  
AR.rvt

MODEL 1541 A: ATTIC VENTILATION FBCR R806									
COORDINATE VENTING REQUIREMENTS WITH ENERGY CALCULATIONS									
AREAS (SQ. FT.)			SOFFIT ONLY (1/150) (NO ROOF VENTS)			WITH ROOF VENTS (1/300) (R.V.)			
			ATTIC VENTILATION REQUIRED			ATTIC VENTILATION REQUIRED			
MARK	ATTIC	SOFFIT	ATTIC AREA/150	ROOF AIR FLOW OF SOFFIT	QUAD 4 SOFFIT HAS	ATTIC AREA/300	QUANTITY OF ROOF VENTS	MIN AIR FLOW OF SOFFIT	
1st STORY	2317.8 SQ. FT.	212.5 SQ. FT.	15.42 SQ. FT.	7.26%	0.15%	~ SQ. FT.	-	~%	
			"SOFFIT ONLY" QUALIFIES			ROOF VENTS ARE NOT REQUIRED			
			SOFFIT MODEL  ACM QUAD 4, FULL VENT, NARROW PATTERN, 0.15% FREE AIR FLOW			ROOF VENT MODEL  32" BASE  22-3/8" BASE  LOMANCO 770-D 0.97 SQ. FT. FREE AIR			

BEARING HEIGHT	
<div></div>	=BEARING @ 8'-8"



ROOF PLAN "AR"  
1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION

EMAIL: [PLANS@GULFCOASTDRAFTING.COM](mailto:PLANS@GULFCOASTDRAFTING.COM)  
PHONE: 239-540-1822  
1515 SE 47th ST. CAPE CORAL, FL 33904

LOT: 34

SUBDIVISION: BRIGHTWATER 40s

ADDRS: 8756 SWELL BROOKS COURT

D.R.H. #: 579330042

MODEL 1541

GCD JOB # 12210

DATE: 01/28/21

DRAWN BY: JSL






























CHECKED BY: JWC


REVISED:

PLAN: ROOF


SCALE: As indicated

A-4 AR

ELECTRICAL LEGEND	
	ELECTRICAL METER
	ELECTRICAL PANEL
	120 V JUNCTION BOX
	SINGLE RECEPTACLE OUTLET
	220 V RECEPTACLE OUTLET
	4-PLEX RECEPTACLE OUTLET
	DUPLEX RECEPTACLE OUTLET
	1/2 SWITCHED DUPLEX OUTLET
	DUPLEX RECEPTACLE AT ELEV. A.F.F.
	DUPLEX RECEPTACLE - ABOVE COUNTER
	SINGLE POLE SWITCH
	3 WAY SWITCH
	DIMMER SWITCH
	MOTION SENSOR SWITCH
	AC/DC SMOKE DETECTOR TO BE INTERCONNECTED ANY RESIDENT HAVING A FOSSIL-BURNING HEATER OR APPLANCE, A FIREPLACE, OR AN ATTACHED GARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE ALARM INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING PERPOSES, PER RULE 9B-3.04.72 SD (SMOKE DETECTOR) SCD (CARBON MONOXIDE/ SMOKE DETECTOR)
	TELEPHONE OUTLET
	TELEVISION RECEPTION OUTLET
	SURFACE MOUNTED CEILING LIGHT
	FLUSH MOUNTED LIGHT
	WALL MTD. BRACKET LIGHT
	DUPLEX FLOOD LIGHT
	EXHAUST FAN
	TRACK MTD. LIGHTS
	A/C DISCONNECT
	PUSH BUTTON (PB) / DOOR BELL (DB)
	INTERCOM
	KEYPAD
	4' FLUORESCENT LIGHT
	2' UNDER COUNTER LIGHT
<p>NOTE: NOT ALL SYMBOLS ARE USED FOR THIS PROJECT.</p> <p>ELECTRICAL NOTES:</p> <p>ARC-FAULT CIRCUIT-INTERRUPTERS AND TAMPER RESISTANT RECEPTACLES SHALL BE INSTALLED</p> <p>IN DWELLING UNITS PER N.E.C 210.12 AND 406.11</p> <p>ALL ELECTRIC, ELECTRICAL EQUIPMENT AND APPLIANCES TO BE SET AT OR ABOVE BASE FLOOR ELEVATIONS PLUS 1'-0" FREEBOARD.</p> <p>ALL OUTLETS IN WET AREAS AND ALL EXTERIOR OUTLETS TO BE GFI'S.</p> <p>INSTALL PHONE AND T.V PER CONTRACT.</p> <p>INSTALL ALL ELECTRICAL PER NEC 201.4</p>	



ELECTRICAL PLAN 1541		
150 AMP SERVICE		
TAG	QUANTITY	PRODUCT
A	(X)	(FLUSH MOUNTED LT)
B	(1)	(VAPOR)
C	(X)	(PENDANT LIGHT
D	(10)	(10" MUSHROOMS)
E	(2)	(24" 3 LT)
F	(X)	(36" 4 LT)
G	(X)	(NOT USED)
H	(1)	(COACH LIGHTS)
I	(X)	(COACH LIGHTS)
J	(1)	(J BOX)
K	(1)	(4' FLUORESCENT)
L	(X)	(2' FLUORESCENT)
M	(X)	(5LT CHANDELIER)
N	(X)	(3 LT)
O	(X)	(PENDANT/ NOOK)
P	(X)	
Q	(X)	(X)



ELECTRICAL PLAN "AR"


---

1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION



L:\O-New Data\1 - MASTER 2019\2019-BUILDERS\DK HORTON  
-2019\SUBDIVISIONS\BRIGHTWATER\ 2210 LOT 34 BLK 1 1541 ARREV\1 2210 1541  
AR.vt



WEEP SCREED DETAIL  
INSTALL AT ALL EXTERIOR WALL LOCATIONS WHERE  
WOOD STUD FRAMING IS ABOVE MASONRY WALLS.

## RESIDENTIAL SPECIFICATIONS

### GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT THE JOB SITE PRIOR TO COMMENCING WORK. THE CONTRACTOR SHALL REPORT ALL DISCREPANCIES BETWEEN THE DRAWINGS AND EXISTING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- THE CONTRACTOR SHALL SUPPLY, LOCATE AND BUILD INTO THE WORK ALL INSERTS, ANCHORS, ANGLES, PLATES, OPENINGS, SLEEVES, HANGERS, SLAB DEPRESSIONS AND PITCHES AS MAY BE REQUIRED TO ATTACH AND ACCOMMODATE OTHER WORK.
- ALL DETAILS AND SECTIONS SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL BE CONSTRUCTED TO APPLY TO ANY SIMILAR SITUATION ELSEWHERE IN THE WORK EXCEPT WHERE A DIFFERENT DETAIL IS SHOWN.
- FOR REQUIRED SOIL BEARING, SEE STRUCTURAL. THE CONTRACTOR SHALL REPORT ANY DIFFERING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH JOB SPECIFICATION AND HOUSE PLANS, MECHANICAL, ELECTRICAL, PLUMBING, AND SITE DRAWINGS, CONSULT THESE DRAWINGS FOR SLEEVES, DEPRESSIONS AND OTHER DETAILS NOT SHOWN ON STRUCTURAL DRAWINGS.
- ALL SPECIFIED FASTENERS MAY ONLY BE SUBSTITUTED IF APPROVED BY THE ENGINEER IN WRITING, THE INSTALLATION OF THE FASTENERS SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. SIMPSON FASTENERS SPECIFIED MAY BE SUBSTITUTED WITH THE SAME QUANTITY AND EQUIVALENT STRENGTH PRODUCT. ALL BOLTS, NUTS, WASHERS, STRAPS AND FASTENERS INCLUDING NAILS, SHALL BE HOT MOPED DIPPED GALVANIZED OR STAINLESS STEEL CONTINUOUS ANCHORAGE SHALL BE PROVIDED BETWEEN ALL TRUSSES, WALL SECTIONS, BEAMS, POSTS AND FOOTINGS WITH USE OF STRAPS AND CONNECTORS AS SPECIFIED HEREIN.
- TREATED WOOD REQUIREMENTS:- ALL TREATED WOOD EXPOSED TO WEATHER SHALL BE PROTECTED, PRESSURE TREATED, OR NATURALLY RESISTANT TO DECAY. ALL WOOD TOUCHING MASONRY OR CONCRETE SHALL BE ISOLATED, OR PRESSURE TREATED.
- THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS COMPLETE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURES AND SEQUENCES TO ENSURE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING ERECTION. THIS INCLUDES THE NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS, OR TIE DOWNS.
- CEILING DRYWALL INSTALLED WITHIN THE HOUSE TO TRUSSES SPACED 24" O.C. SHALL BE 5/8" DRYWALL OR 1/2" SAG RESISTANT PER SEC. 702.3.5
- LANAI CEILINGS & COVERED ENTRY CEILINGS  
1X4 STRIPPING @ 16" O.C. FASTENED WITH 2-8d NAILS TO EACH TRUSS. 5/8" EXTERIOR GYP. BOARD CEILING FASTENED WITH 8d NAILS OR 1-5/8" DRYWALL SCREWS @ 6" O.C. EDGE AND FIELD.

### DOOR AND WINDOW ANCHORAGE


ANCHORAGE REQUIREMENTS- ALL PASS AND SLIDING GLASS DOORS AND ALL WINDOW ASSEMBLIES SHALL BE ANCHORED TO THE MAIN WIND FORCE RESISTING SYSTEM IN A MANNER SPECIFIED BY THE PUBLISHED MANUFACTURERS LITERATURE. THERE SHALL BE NO SUBSTITUTION OF ALTERNATE FASTENINGS UNLESS PROVIDED BY THE MANUFACTURER AND APPROVED BY THE BUILDING DESIGN ENGINEER.

#### MASONRY OPENING

WHERE WINDOW FRAME IS DESIGN TO FASTEN WITH SCREWS THROUGH THE FRAME AND INTO THE MASONRY, THE BUCK MATERIAL IS SIMPLY A SPACER. THE BUCK MAY BE FASTENED WITH THE T NAILS OR ANY SUITABLE FASTENER TO TACK IT INTO POSITION PRIOR TO WINDOW INSTALLATION. FASTEN WINDOW FRAME PER MFR INSTRUCTIONS. A WINDOW FASTENER SHALL PENETRATE MASONRY BY 2 1/4" MIN.

WHERE WINDOW FRAME IS DESIGNED TO FASTEN ONLY TO THE WOOD BUCK (IE, FLANGED FRAME WITH WOOD SCREWS) THE BUCKS SHALL BE 2X WOOD WITH STRUCTURAL FASTENING TO THE MASONRY WITH 1/4 X 3 3/4 MASONRY SCREWS @ 24" OC AND 6" FROM EACH END.

WOOD FRAMED OPENING- ALL DOORS AND WINDOWS SHALL BE INSTALLED ACCORDING TO THE PUBLISHED MANUFACTURERS LITERATURE OF THE ASSEMBLY BEING INSTALLED TO THE ROUGH SUBSTRATE OPENING. SHIMS SHALL BE MADE OF MATERIALS CAPABLE OF RESISTING THE APPLIED LOADS AND SHALL BE LOCATED NEAR EACH FRAME FASTENER TO MINIMIZE DISTORTION OF THE FRAME AS THE FASTENERS ARE TIGHTENED .



PAN FLASHING PER R703.4  
SCALE: N.T.S.

### GENERAL ROOF ASSEMBLY

#### ROOF SHEATHING FBCR TABLE R203.2.2

SHALL BE 19/32 APA RATED SHEATHING, EXPOSURE 1, SPAN RATING 40/20 OR BETTER. INSTALL PANELS WITH LONG DIMENSION PLACED PERPENDICULAR TO TRUSSES A 1/8" SPACE BETWEEN ADJACENT SHEETS SHALL BE MAINTAINED . INSTALL "H" CLIPS AT UNSUPPORTED PANEL EDGES. FOR FASTENING, SEE STRUCTURAL.

#### FLASHING

FLASHING SHALL BE ALUMINUM, ALUMINUM ZINC COATED STEEL 0.0179" THICK, 26 GAUGE A250 ALUM ZINC, OR GALVANIZED STEEL 0.0179" THICK, 26 GAUGE ZINC COATED G90. FLASHING SHALL BE INSTALLED IN ACCORDANCE WITH THE ZIP SYSTEM ROOF SHEATHING MANUFACTURERS PUBLISHED REQUIREMENTS. ALL FLASHING AND INSTALLATION SHALL CONFORM TO SECTION R905.2.8 (1 TO 5).

#### DRIP EDGE

DRIP EDGE SHALL BE PROVIDED AT ALL EAVES AND GABLES OF SHINGLES ROOFS, LAPPED A MINIMUM OF 3" @ JOINTS. THE OUTSIDE EDGE SHALL EXTEND A MINIMUM OF 1/2" BELOW SHEATHING AND THE INSIDE EDGE SHALL EXTEND BACK A MINIMUM OF 2". DRIP EDGE SHALL BE FASTENED AT NO MORE THAN 4" CENTERS. THERE SHALL BE A MINIMUM OF 4" WIDTH OF ROOF CEMENT INSTALLED OVER THE DRIP EDGE FLANGE.

### ASPHALT SHINGLE ROOF SPECS

#### SHINGLES

30# FELT SHALL BE INSTALLED UNDER ASPHALT SHINGLES. ALL ASPHALT SHINGLES SHALL HAVE SELF-SEALING STRIPS OR BE INTERLOCKING AND COMPLY WITH ASTM D 225 OR D 3462. FOR FASTENING, SEE STRUCTURAL. INSTALLATION SHALL COMPLY WITH MANUFACTURERS REQUIREMENTS FOR INSTALLATION IN THE GIVEN FLORIDA WIND ZONE, AS DETERMINED BY ASTM D 3161.

### CLAY AND CONCRETE ROOF TILE SPECS

INSTALL PEEL AND STICK UNDERLAYMENT APPROVED FOR SINGLE LAYER APPLICATION UNDER TILE ROOF. THE INSTALLATION OF CLAY AND CONCRETE TILE SHALL COMPLY WITH THE PROVISIONS OF R905.3 F.B.C. MARKING: EACH ROOF TILE SHALL HAVE A PERMANENT MANUFACTURER'S IDENTIFICATION MARK. APPLICATION SPECIFICATIONS: THE TILE MANUFACTURER'S WRITTEN APPLICATION SPECIFICATIONS SHALL BE AVAILABLE AND SHALL INCLUDED BUT NOT BE LIMITED TO THE FOLLOWING:

- TILE PLACEMENT AND SPACING,
- ATTACHMENT SYSTEM NECESSARY TO COMPLY WITH CURRENT WIND CODE,
- A. AMOUNT AND PLACEMENT OF MORTAR
- B. AMOUNT AND PLACEMENT OF ADHESIVE
- C. TYPE, NUMBER, SIZE AND LENGTH OF FASTENERS AND CLIPS.
- UNDERLAYMENT
- SLOPE REQUIREMENT.

### FLOOR SHEATHNG AT 2ND FLOOR

A.P.A. RATED STURDI-FLOOR, EXPOSURE 1, TONGUE & GROOVE EDGES SPAN RATING 48/24 OR BETTER, SEE STRUCTURAL.

ROOF SHEATHING PER SCHEDULE 2/5-3.  
AND PER NOTES IN TABLE 3 ON A-6

SHINGLE ROOF PER NOTE 4 ON A-6

WOOD TRUSSES @ 24" O.C. (TYPICAL.)  
DESIGNED BY DELEGATED TRUSS  
ENGINEER.

EMBEDDED STRAP AT EACH  
TRUSS PER ROOF FRAMING PLAN.

FLASHING AND DRIP  
EDGE PER NOTES IN  
TABLE 2 ON A-6

2X6 MIN. SUB FASCIA

PROVIDE VENTILATION  
PER R806.1

ALUMINIUM VENTED  
SOFFIT SHALL MEET R704  
SEE TABLE 3 ON S-3

8X8 CONTINUOUS BOND  
BEAM W/ 1 #5, GROUT  
SOLID

SLOPE TO EXTERIOR

PRECAST CONCRETE SILL

DECO. CEMENT  
FINISH PER ASTM C-926

SEE ENERGY CODE FORMS FOR  
INSULATION R-VALUES

DRYWALL CEILING PER  
NOTE 9 IN TABLE 1 ON A-6


1X4 P.T. STRIP

PRECAST LINTEL SEE FRAMING PLAN  
PER R806.1  
WINDOW BUCKS SEE TABLE 2 ON A-6  
1X4 P.T. BUCK W. BED OF  
CONTINUOUS CAULK UNDER

PROVIDE TERMITE TREATMENT  
WITH "BORA CARE".

SILL SET IN MORTAR


1/2" DRYWALL W/  
TEXTURED WALLS  
1X2 P.T. FURRING STRIPS @ 24"  
O.C. W/ INSULATION (MIN. R4.1)



CONC. FOOTING  
SEE FOUNDATION PLAN  
FOR SIZE AND  
REINFORCING.

4" CONC. SLAB ON 6 MIL.  
VISQUEEN VAPOR BARRIER ON  
MECHANICALLY COMPACTED FILL  
@ 95%.

### TYPICAL WALL SECTION



R310.2.1 MINIMUM OPENING AREA- ALL EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5.7 SQUARE FEET (0.530 m²).

EXCEPTION- GRADE FLOOR OPENINGS SHALL HAVE A MINIMUM NET CLEAR OPENING OF 5 SQUARE FEET (0.465 m²).

R310.2.1 MINIMUM OPENING HEIGHT- THE MINIMUM NET CLEAR OPENING HEIGHT SHALL BE 24 INCHES (610mm).


R310.2.1 MINIMUM OPENING WIDTH- THE MINIMUM NET CLEAR OPENING WIDTH SHALL BE 20 INCHES (508mm).

R310.1.1 OPERATIONAL CONSTRAINTS- EMERGENCY ESCAPE AND RESCUE OPENINGS SHALL BE OPERATIONAL FROM THE INSIDE OF THE ROOM WITHOUT THE USE OF KEYS OR TOOLS.

R310.2.3 WINDOW WELLS- THE MINIMUM HORIZONTAL AREA OF THE WINDOW WELL SHALL BE 9 SQUARE FEET (0.84 m²), WITH A MINIMUM HORIZONTAL PROJECTION AND WIDTH OF 36 INCHES (914mm). THE AREA OF THE WINDOW WELL SHALL ALLOW THE EMERGENCY ESCAPE AND RESCUE OPENING TO BE FULLY OPENED.

### MINIMUM EGRESS WINDOW DETAIL

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION




LOT: 34	BLOCK: 1
SUBDIVISION: BRIGHTWATER 40s	
ADDRESS: 8756 SWELL BROOKS COURT	
D.R.H. #: 579330042	

MODEL 1541	GCD JOB # 12210
---------------	-----------------


DATE:	01/28/21
DRAWN BY:	JSL
CHECKED BY:	JWC
REVISED:	
PLAN:	SECTIONS
SCALE:	As indicated

A-6







"F3" FOOTING  
1/2" = 1'-0"




"F3" WITH CURB AT GARAGE  
1/2" = 1'-0"



"FGA" STEP DOWN  
1/2" = 1'-0"



"P" PAVERS DETAIL ENTRY/ LANAI  
1/2" = 1'-0"



GARAGE DOOR RECESS A  
1/2" = 1'-0"

## FOUNDATION PLAN

SCALE: 1/4" = 1'-0"

### PLAN NOTES:

- TOP OF GROUND FLOOR SLAB DATUM ELEVATION 0'-0"
- "F#" DENOTES CONTINUOUS WALL FOOTING TYPE PER SCHEDULE THIS SHEET.
- PROVIDE #5 VERTICAL REINFORCING AT DOT LOCATIONS SHOWN ON PLAN FROM FOOTING TO BOND BEAM.
- ALL DIMENSIONS ARE TO OUTSIDE FACE OF MASONRY WALLS. SOME SLAB EDGES MAY EXTEND BEYOND FACE OF WALL.
- FOR DIMENSIONS OF ROUGH OPENINGS IN MASONRY WALLS, COORDINATE WITH WINDOW/ DOOR SUPPLIER.
- PROVIDE PRESSURE TREATED BUCKS AT WINDOWS/ DOORS PER DETAIL 7/S-3.

## WALL FOOTING SCHEDULE

USED	TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REINFORCING	SHAPE
	F1	CONT.	1'-4"	0'-8"	2-#5	
	F2	CONT.	1'-8"	0'-10"	2-#5	
X	F3	CONT.	1'-0"	1'-8"	2-#5	
	F4	CONT.	1'-4"	1'-8"	2-#5	
	F5	CONT.	1'-4"	1'-0"	2-#5	
	F6	CONT.	1'-4"	1'-0"	2-#5	
X	F6A	CONT.	0'-8"	0'-8"	1-#5	
	TE	CONT.	0'-8"	0'-8"	1-#5	

PROVIDE CORNER BARS IN FOOTING, PER 6/S-3


## PAD FOOTING SCHEDULE

USED	TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REIN.		REMARKS
					LONG WAY	SHORT WAY	
X	A	2'-6"	2'-6"	1'-0"	3-#5	3-#5	-
	B	3'-0"	3'-0"	1'-0"	4-#5	4-#5	-
	C	3'-6"	3'-6"	1'-0"	4-#5	4-#5	-
	D	4'-0"	4'-0"	1'-2"	5-#5	5-#5	-
	E	5'-0"	5'-0"	1'-2"	6-#5	6-#5	-

16" SQUARE  
MASONRY  
COLUMN W/ 4 #5  
VERTICAL AND #3  
TIES @ 8" O.C.

16" SQUARE  
MASONRY  
COLUMN W/ 4 #5  
VERTICAL AND #3  
TIES @ 8" O.C.

FOUNDATION PLAN "AR"  
1/4" = 1'-0"



This item has been digitally signed by Raul Reyes on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed. The signature and the signature must be validated on any electronic copies.



LOT: 34	BLOCK: 1
SUBDIVISION: BRIGHTWATER 40s	
ADDRESS: 8756 SWELL BROOKS COURT	
D.R.H. #: 579330042	
GCD JOB # 12210	

MODEL  
1541

DATE: 01/28/21

DRAWN BY: JSL

CHECKED BY: JWC

REVISED:

PLAN: FOUNDATION PLAN

SCALE: As indicated

S-I AR

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION




L:\O-New Data\1-MASTER 2019\2019-BUILDERS\DK HORTON  
2019\SUBDIVISIONS\BRIGHTWATER\2210 LOT 34 BLK 1 1541 ARREV\12210 1541  
AR.rvt

TRUSS STRAPPING TO MASONRY		
MAX TRUSS UPLIFT @ 24" OC (LBS)	CONNECTOR	FASTENER
1450	(1) META16 TO 40	(8) O.148x1 1/2", EMBED 4"
1810	(1) META16 TO 40	(9) O.148x1 1/2", EMBED 4"
2120	(1) HHETA16 TO 40	(10) O.148x1 1/2", EMBED 4"
1875 (1 PLY)	(2) META16 TO 40	(10) O.148x1 1/2", EMBED 4"
1795 (2 PLY)	(2) META16 TO 40	(14) O.162x3 1/2", EMBED 4"
2365 (2 PLY)	(2) META16 TO 40	(12) O.162x3 1/2", EMBED 4"
2365 (2 PLY)	(2) HHETA12 TO 40	(12) O.162x3 1/2", EMBED 4"
3965/5YP 3330/5PF	MG2 (2 PLY)	(22) O148x3" ATR, EPOXY 12"
4235/5YP 3640/5PF	HTT4	(18) O.162x2 1/2", 5/8", ATR, EPOXY 12"
4670/5YP 4015/5PF	HTT5	(26) O.148x3", 5/8", ATR, EPOXY 12"
5445/5YP 5360/5PF	HTT5KT	(26) 5D#10x2 1/2", 5/8", ATR, EPOXY 12"
10690/5YP 10690/5PF	(1)HGT - 2	(26) O.148x3" TO GIRDER
		(2) 3/4" Ø ATR, EPOXY 12"
		(16) O.148x3" TO GIRDER,
		(2) 3/4" Ø ATR, EPOXY 12"
10790/5YP 10790/5PF	(1)HGT - 3	

NOTES:

- PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE AND SUITABLE FOR THE GEOMETRY. EMBED STRAP ON .C. OF WALL.
- CONNECTORS ARE SIMPSON STRUCTURAL CONNECTORS. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS. SUBSTITUTIONS MUST BE APPROVED IN WRITING BY THE ENGINEER OF RECORD.
- WHERE EMBEDDED STRAPS ARE MISSING, OR MIS-LOCATED, INSTALL RETROFIT STRAP PER 10S-3.

SIMPSON CATALOG C-C- 2019




TRUSS STRAPPING TO STUDWALL/ WOOD BEAM		
MAX TRUSS UPLIFT @ 24" OC (LBS)	CONNECTOR	FASTENER
850	(1)MTS16 TO 20	(14) 10dk1-1/2"
1700	(2) MTS16 TO 20	(14) 10dk1-1/2"
2550	(3) MTS16 TO 20	(14) 10dk1-1/2"
1125	(1) HTS20 TO 30	(24) 10dk1-1/2"
2250	(2) HTS20 TO 30	(24) 10dk1-1/2"
3375	(3) HTS20 TO 30	(24) 10dk1-1/2"
4500	(4) HTS20 TO 30	(24) 10dk1-1/2"

NOTES:

- PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE.
- CONNECTORS ARE SIMPSON SRTONG TIE. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS.

SIMPSON CATALOG C-C- 2019




#### PLAN NOTES:

- ROOF TRUSS BEARING ELEVATION VARIES, SEE LEGEND.
- ROOF FRAMING SHALL BE WOOD TRUSSES DESIGNED BY A DELEGATED TRUSS ENGINEER PER DESIGN CRITERIA ON SHEET S-3.
- PROVIDE STRAPPING AT TRUSSES PER NOTES ON THIS SHEET.
- FOR NAILING OF ROOF DECK, SEE 1 AND 2 ON S-3.
- 8F8-1B etc., DENOTES PRECAST LINTEL ABOVE DOOR/WINDOW OPENING PER SCHEDULE THIS SHEET.
- AT TRUSS BEARING, PROVIDE 8x8 MASONRY BOND BEAM W/ 1 #5 CONTINUOUS, SEE DETAIL 11/5-3.

TRUSS BEARING CONDITIONS AND STRAPPING IS BASED ON TRUSS LAYOUT PREPARED BY BUILDERS FIRST SOURCE  
JOB# MASTER DATED: 08/14/18  
REVISED: 01/21/2021

#### BEARING HEIGHT

 = BEARING @ 8'-8"



#### ROOF FRAMING PLAN "AR"

1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL  
FLORIDA BUILDING CODE 2020 - 7TH EDITION



**Gulf Coast**  
Drafting & Design, Inc.  
EMAIL: PLANS@GULFCOASTDRAFTING.COM  
PHONE: 239-540-1822  
1515 SE 47th ST. CAPE CORAL, FL 33904

STRUCTURAL SYSTEMS  
OF NORTH FLORIDA  
1000 N. W. 10th Ave., Suite 100  
Fort Lauderdale, FL 33304  
(954) 574-4554  
Fax: (954) 574-4554

LOT: 34	BLOCK: 1
SUBDIVISION: BRIGHTWATER 40s	
ADDRESS: 8756 SWELL BROOKS COURT	
D.R.H. #: 579330042	
GCD JOB # 12210	


DATE:	01/28/21
DRAWN BY:	JSL
CHECKED BY:	JWC
REVISED:	
PLAN:	ROOF FRAMING PLAN
SCALE:	As indicated

S-2 AR



TABLE R803.2.3.1 – NAIL SPACING BASED ON SPECIFIC GRAVITY OF RAFTER/TRUSS: ALL TRUSS TOP CHORDS AND FIELD ROOF FRAMING SHALL BE SOUTHERN PINE, SPECIFIC GRAVITY=0.55 (EXCEEDS SG=0.42 AND 0.49 OF TABLE R803.2.3.1).

ENSURE THAT ALL NAILS PENETRATE THE TOP CHORD OF THE TRUSS WITHOUT SPLITTING.




NAIL SPACING (TABLE R803.2.3.1) WIND SPEED / EXPOSURE	NAIL TYPE (SECTION R803.2.3.1) 19/32 SHEATHING
160/B, 160/C, 170/B	2 1/2" x 0.131" RING SHANK OR
NAIL SPACING: 6" O.C. EDGE 6" O.C. FIELD	3" x 0.120" RING SHANK (PER ASTM F1667 RSRs-03 & 04)
170/C	
NAIL SPACING: 4" O.C. EDGE 4" O.C. FIELD	

EDGE NAIL TO FACIA BOARD


## 1 NAILING OF ROOF SHEATHING

SCALE: NTS



MONOLITHIC FOOTINGS  
SCALE: 3/4" = 1'-0"

4



## BUCK FASTENING

## GARAGE DOOR

NOTE: THIS BUCK FASTENING DETAIL IS INTENDED FOR FLANGED WINDOW/DOOR PRODUCTS THAT FASTEN THRU THE FLANGE WITH WOOD SCREWS TO THE BUCK. FOR WINDOW/DOOR PRODUCTS THAT DO NOT HAVE A FLANGE AND FASTEN INSTEAD OUTWARD THRU THE FRAME, USE MASONRY SCREWS PER MFR. THAT ARE LONG ENOUGH TO PENETRATE 2-1/4" INTO THE MASONRY. IN THIS CASE, THE BUCK MATERIAL IS SIMPLY A SPACER AND MAY BE 1x4 OR 1x6 OR OMITTED ENTIRELY AND THE SPACER MAY BE TACKED IN PLACE WITH MASONRY NAILS OR PINS.

7

## RETROFIT STRAPS TO CONCRETE/MASONRY

TRUSS UPLIFT (LBS) @ 24" OC	CONNECTOR
TO 840	1-MTSM16 or 20
TO 1045	1-HTSM16 or 20
TO 2090	2-HTSM16 or 20
TO 4300	2-LGT2
TO 3480	HTT16
TO 10530	HGT-2/3

NOTES:

1) WHERE EMBEDDED STRAP IS MISSING OR MIS-LOCATED, PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE.

2) CONNECTORS ARE SIMPSON STRONG TIE. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS.


## 10 RETROFIT UPLIFT CONNECTOR SCHEDULE

## SHEATHING SCHEDULE

EXTERIOR STUD WALL	FLOOR
7/16" ZIP SYSTEM WALL SHEATHING BY HUBER ENGINEERED WOODS LLC, NAILED W/ 8d COMMON WIRE @ 6" O.C. EDGE AND 6" O.C. FIELD. PROVIDE 2x4 BLOCKING AT ALL JOINTS. INSTALL SHEATHING AND SEAM TAPE IN STRICT ACCORDANCE WITH MFR. WRITTEN INSTRUCTIONS.	N/A
EXTERIOR CEILING	
ROOF – PER FBCR TABLE 803.2.2	1) 1x4 STRIPPING @ 16"OC w/ 2-8d NAILS TO EACH TRUSS, 3/8" EXTERIOR GYPBOARD CEILING, FASTEN W/8d NAILS OR 1 5/8" DRYWALL SCREWS @ 6"OC EDGE & FIELD. 2) 3/8" BC PLYWOOD NAILED w/ 6d COMMON @ 6" OC EDGE & FIELD.
SOFFIT	ALUMINUM PERFORATED SOFFIT INSTALLED PER MANUFACTURER INSTRUCTIONS TO MEET WIND PRESSURES PER R704.

NOTE: EXTERIOR CEILINGS SPECIFIED ABOVE MEET THE DESIGN WIND PRESSURES PER R703.1.2

2




NOTES:  
1) PROVIDE SAWCUTS TO CREATE APPROXIMATE 20' X 20' MAXIMUM SQUARES.  
2) SAWCUT CONCRETE SLAB WITHIN 4 TO 12 HOURS OF CONCRETE PLACEMENT.

## SLAB SAWCUT DETAIL

SCALE: NTS


5



## 8 CORNER BAR DETAIL IN BOND BEAMS

SCALE: 3/4" = 1'-0"

8



## 11 FULL HEIGHT WALL SECTION

SCALE: 3/4" = 1'-0"

11

## WINDOW/DOOR/SOFFIT DESIGN WIND PRESSURES

WIND PRESSURES PER ASCE7-16, 160 MPH, EXPOSURE C, AND CONVERTED TO ALLOWABLE STRESS DESIGN PRESSURES USING 0.6W LOAD FACTOR. (V=124 MPH, RISK CAT II, ENCLOSED, Kd=0.85, h=15')


TYPE	INTERIOR ZONE 4	END ZONE 5
SOFFIT (10 SQ. FT.)	+33.5 -36.3	+33.5 -44.8
WINDOWS & DOORS (10 SQ. FT.)	+33.5 -36.3	+33.5 -44.8
8' OR 9' GARAGE DOORS	+29.4 -33.1	+29.4 -33.1
16' OR 18' GARAGE DOORS	+28.2 -31.5	+28.2 -31.5

(SEE PLAN FOR OTHER SPECIFIC PRESSURES)


- TABLE MAY BE USED FOR ANY SIZE WINDOW OR DOOR IN EACH TYPE.
- USE "INTERIOR ZONE 4" PRESSURES UNLESS WINDOW OR DOOR IS LOCATED WITHIN THE "END ZONE 5" (SEE DIAGRAM BELOW), THEN USE THE HIGHER PRESSURES UNDER THE "END ZONE 5" COLUMN.
- ALL GLASS / GLAZING SHALL BE IMPACT RATED OR USE IMPACT RATED SHUTTERS.
- SUBMIT PRODUCT APPROVALS TO THE BUILDING DEPARTMENT AS REQUIRED BY THE LOCAL JURISDICTION.
- MANUFACTURED SOFFIT PRODUCTS SHALL BE INSTALLED PER MFR ENGINEERING SPEC SHEETS.

\* ON IRREGULAR SHAPED BUILDINGS, THERE IS NO GUIDANCE IN THE CODE FOR HOW FAR A CORNER MUST PROTRUDE FROM THE MAIN BUILDING TO BE CONSIDERED "ZONE 5". WE HAVE CHOSEN >15'. THIS IS SUBJECT TO JUDGEMENT CALL BY THE AUTHORITY HAVING JURISDICTION.

IN ZONE 5, MANUFACTURED SOFFIT PRODUCTS MAY REQUIRE ADDITIONAL BATTENS OR FASTENING PER MFR ENGINEERING SPEC SHEETS TO MEET THE PRESSURE REQUIREMENTS.



3




## STEP FOOTING

SCALE: NTS

6

## FOOTING CORNER BARS


SCALE: NTS



## 9 STEPPED BOND BEAM & REINFORCING

SCALE: 3/4" = 1'-0"

9



## 12 GABLE END BRACING

SCALE: N.T.S.

12

DESIGN CRITERIA:

DESIGN IN ACCORDANCE WITH REQUIREMENTS OF THE FLORIDA BUILDING CODE 7th EDITION (2020) RESIDENTIAL

- FLOOR & ROOF UNIFORM LOADS:  
ELEVATED FLOORS: LIVE LOAD 40 PSF, DEAD LOAD 20 PSF  
ROOF: LIVE TOP CHORD 20 PSF  
LIVE BOTTOM CHORD 10 PSF (NON-CONCURRENT w/ TOL)  
CEMENT ROOF TILE DEAD LOAD 25 PSF TOTAL  
SHINGLE/METAL ROOFING DEAD LOAD 15 PSF TOTAL  
MINIMUM DEAD LOAD FOR WIND: TC 5 PSF, BC 5 PSF

DEFLECTION CRITERIA:  
FLOOR L/480 LIVE, L/360 TOTAL  
ROOF L/240 LIVE, L/180 TOTAL

- WIND LOADS:  
WIND DESIGN PER, ASCE7-16  
BASIC WIND SPEED (ASCE7-16) 160 MPH  
NOMINAL WIND SPEED (Vasd TABLE R301.2.1.3) 124 MPH  
BUILDING CATEGORY II  
IMPORTANCE FACTOR 1.00  
EXPOSURE C  
MEAN ROOF HEIGHT = 15 FT  
ROOF PITCH 5/12  
ENCLOSURE CLASS +/- 0.18  
INTERNAL PRES. COEFF.  
WINDOW/DOOR DESIGN WIND PRESSURE PER TABLE R301.2(2), R301.2(3) AND R301.2(4). SEE DETAIL ON S-3.  
SOFFITS - PER R704, ALL SOFFITS & THEIR ATTACHMENTS SHALL BE CAPABLE OF RESISTING THE DESIGN PRESSURES SPECIFIED IN TABLE R301.2(2) FOR WALLS USING 10 SQ. FT.

- REINFORCED CONCRETE:  
DESIGN AS PER ACI 318-14  
REQUIRED COMPRESSIVE STRENGTH AT 28 DAYS:  
SLAB ON GRADE f'c = 2500 PSI  
3/4" MINIMUM THICKNESS REINFORCED WITH 6x6 w/1.4xw/1.4 WWF OR FIBERMESH.

CONVENTIONAL SHALLOW FOOTINGS f'c = 2500 PSI  
BEAMS AND COLUMNS f'c = 3000 PSI  
ALL OTHER CONCRETE (U.N.O.) f'c = 3000 PSI  
UNLESS OTHERWISE SHOWN ON DRAWINGS, MINIMUM CONCRETE COVER FOR REINFORCING SHALL BE AS FOLLOWS:  
FOOTINGS 3"  
SLAB ON GRADE CENTERED 3"  
BEAMS 1 1/2"  
COLUMNS 1 1/2"  
ALL REINFORCING STEEL SHALL BE PLACED IN ACCORDANCE WITH THE TYPICAL BENDING DIAGRAMS AND PLACING DETAILS OF ACI STANDARDS AND SPECIFICATIONS. ALL REINFORCING STEEL SHALL BE HELD SECURELY IN POSITION WITH STANDARD ACCESSORIES DURING PLACING OF CONCRETE.  
REINFORCING STEEL - ASTM A615 GRADE 40 FOR #3  
GRADE 60 FOR #4 TO #11

WELDED WIRE FABRIC - ASTM A185  
SPICES IN REINFORCING, SHALL BE 40 BAR DIAMETERS. NON-CONTACT LAP SPICES MAY BE USED PROVIDED REINFORCING IS NOT SPACED MORE THAN 5" APART FOR #5 BARS.

FORMWORK AND SHORING SHALL REMAIN IN PLACE UNTIL CONCRETE HAS REACHED AT LEAST 2/3 OF THE REQUIRED 28 DAY STRENGTH.

- REINFORCED MASONRY:  
DESIGN PER TMS 402/602-16  
REQUIRED COMPRESSIVE STRENGTHS:  
MASONRY WALLS f'm = 1500 PSI

REINFORCING STEEL - ASTM A615 GRADE 60.  
SPICES IN REINFORCING, SHALL BE 48 BAR DIAMETERS.  
ALL CONCRETE MASONRY UNITS SHALL BE COMPOSED OF ASTM C90, GRADE N-1 HOLLOW CONCRETE MASONRY UNITS WITH TYPE 'S' MORTAR. GROUT ALL CELLS CONTAINING VERTICAL REINFORCEMENT WITH 3000 PSI PEA ROCK CONCRETE GROUT. ALL CELLS BELOW FINISHED GRADE SHALL BE GROUTED SOLID. ALL EXTERIOR WALLS SHALL BE REINFORCED FULL HEIGHT AT DOT LOCATIONS ON PLAN.


- DELEGATED-ENGINEERED WOOD ROOF TRUSSES:  
ALL WOOD ROOF TRUSSES SHALL BE DESIGNED BY A DELEGATED TRUSS ENGINEER PER RULE 61G15-31.003 OF THE FLORIDA ADMINISTRATIVE CODE. ALL TRUSSES SHALL HAVE TEMPORARY BRACING PER "COMMENTARY AND RECOMMENDATIONS FOR HANDLING, INSTALLING AND BRACING METAL PLATE CONNECTED WOOD TRUSSES, HIB-91." FOR OTHER BRACING REQUIREMENTS, NOTIFY ENGINEER. PROVIDE PERMANENT BRACING PER TRUSS MFR. SHOP DRAWINGS. IF PERMANENT BRACING IS NOT SPECIFIED, CONTACT ENGINEER.

- FOUNDATION:  
CONVENTIONAL SHALLOW CONCRETE FOOTINGS  
SOIL BEARING CAPACITY 2000 PSF  
THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE SUITABILITY OF THE SOIL CONDITIONS FOR THE INTENDED STRUCTURE AND ASSUMED SOIL BEARING CAPACITY.  
IT IS RECOMMENDED THAT A GEOTECHNICAL FIRM BE HIRED TO PERFORM A SITE EVALUATION.

- DIMENSIONS: VERIFY ALL DIMENSIONS WITH HOUSE PLANS. SEE HOUSE PLANS, MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS FOR EMBEDS, OPENINGS, SLEEVES, ETC. WHICH ARE NOT SHOWN ON STRUCTURAL DRAWINGS.

- MEANS AND METHODS: THE STRUCTURAL ENGINEER SHALL NOT HAVE CONTROL OR BE RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, PROCEDURES OR SEQUENCES TEMPORARY BRACING, SHORING, GUYING OR OTHER MEANS TO SUPPORT STRUCTURAL ELEMENTS IN PLACE DURING CONSTRUCTION. FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR, OR ANY OTHER PERSONS PERFORMING THE WORK OR FOR THE FAILURE OF ANY OF THEM TO CONSTRUCT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS.

- SHOP DRAWINGS: SHOP DRAWINGS SHALL BE PREPARED AND SUBMITTED TO THE ENGINEER FOR REVIEW FOR ALL STRUCTURAL ELEMENTS UTILIZING PREFABRICATED COMPONENTS. ONE SET OF SIGNED & SEALED TRUSS ENGINEERING SHALL BE DELIVERED TO THE ENGINEER OF RECORD FOR THE STRUCTURE PER FLORIDA ADMINISTRATIVE CODE 61G15-30.005 AND 61G15-31.003.



THIS DETAIL ONLY USED ON ELEVATIONS B

## 13 OUTLOOKER DETAIL

SCALE: N.T.S.

13

REVISIONS	BY

STRUCTURAL ENGINEERING:  
**STRUCTURAL SYSTEMS OF NORTH FLORIDA**  
1634 S.E. 47th STREET, SUITE #3  
CAPE CORAL, FL 33904  
(239) 549-4554  
CA# 8829



**D. R. HOHON, P.E.**  
*America's Builder*

**STRUCTURAL DETAILS**  
**MODEL 1541 A**  
8756 SWELL BROOKS COURT  
NORTH FORT MYERS, FLORIDA  
LOT: 34 BLOCK: 1 SUBDIVISION: BRIGHTWATER

DESIGN/DRAWN  
DWB/DWB  
CHECKED  
DWB  
DATE  
01/29/21  
SCALE  
VARIES  
JOB NO.  
DR12210  
SHEET

**S-3**

SHEET 3 OF 3

FOR BUILDERS FIRST SOURCE TRUSSES, MODEL 1541, ELEVATION A, JOB # MASTER, DATE: 08/14/18, REVISED: 01/21/21