

Truss Connector Total List		
Manuf	Product	Qty
	HUS26	8
	LUS24	6

Wind Importance Factor	1
Occupancy/Risk Category	II
Lanai, Entry, Porch areas	EXPOSED TO WIND

TRUSSES DESIGNED FOR TILE OR SHINGLE APPLICATIONS

Truss List of <5000# reaction & <-1000# uplift

Truss	Qty	Span	Reactions		
A01A	1	52-05-00	1375.63 lb -607.61 lb	4313.49 lb -1535.22 lb	1898.77 lb -504.62 lb
A17L	1	52-05-00	1375.83 lb -386.45 lb	3743.17 lb -1101.66 lb	928.90 lb -253.39 lb
A18L	1	52-05-00	1376.53 lb -390.37 lb	3804.91 lb -1073.56 lb	906.26 lb -249.07 lb
A19L	1	52-05-00	1411.87 lb -400.54 lb	3665.54 lb -1050.34 lb	968.44 lb -262.12 lb
A24L	1	28-11-08	2864.10 lb -1553.81 lb	1918.50 lb -871.93 lb	
F04	1	33-05-00	967.73 lb -1048.97 lb	4324.82 lb -3538.20 lb	2202.18 lb -1718.62 lb
G01L	1	17-09-00	1488.12 lb -947.44 lb	1503.90 lb -1067.40 lb	

Engineer of Record for the Structure
Structural Systems of N. Fl, Inc.
Raul Reyes, PE 88925
1634 SE 47th Street #3
Cape Coral, FL 33904

This document has been reviewed for
conformance with the design intent of the
structure and specified design criteria.

☒ Accepted As-Is ☐ Accepted As Noted ☐ Revise and Resubmit

Hanger Notes

* Refer to Simpson Strong-Tie website
(www.strongtie.com/products/connectors),
or the USP website
(www.uspconnectors.com/us/products/conne
ctors), for proper use and attachment of the
specified hangers.

General Notes

* Required interior bearing walls shown
@ heights noted
* Trusses may not be cut or altered in
any way without prior authorization from
ABS, Inc.
* Any trusses that are cut or altered
without authorization will be repaired or
replaced at the customers expense
* No backcharges of any kind will be
accepted without prior review and written
consent from ABS, Inc.
* For proper truss handling and
bracing, refer to the "TPI" documents
"BCSI-B1 through B4"
* Any multi-ply trusses must be
attached together per the engineering
specifications prior to installation

* Permanent and temporary bracing is
the responsibility of the truss installer.
The "Engineer of Record" for the project
is responsible for the design of the
permanent bracing, the diaphrag system,
shear walls, and structural elements to
resist lateral loads from wind and or
seismic activity. The "EOR" is also
responsible to call out the required
strapping materials to sufficiently attach
the trusses to the load bearing structure
below, to verify truss design specifi-
cations (pitch, span, profiles, applied
loading, wind application, etc.), and for
the overall design and placement plan of
the truss system.

* If any job site accidents occur
involving trusses, the installer must
immediately stop work on the project and
notify a representative of ABS, Inc.. All
trusses involved in an accident must be
inspected by a licensed structural
engineer to determine the cause of the
accident. The builder assumes all
liability if trusses involved in an accident
are altered or moved in any way before
an inspection is completed. All de-
cisions regarding necessary repairs or
replacement of trusses will be based on
the recommendation of the report sub-
mitted by the structural engineer.

MULTI-PLY ATTACHMENT

* For 4-ply or 5-ply attachment, refer to the
Detail Packet Sheet:
"STANDARD BOLT TO SCREW
TRUSS CONNECTION DETAIL" -
"T-4PLY OR 5PLY SCREW"

*** CRITICAL ***

ATTN: FRAMER

For multi-ply girder attachments, refer to
engineering for specific instructions for
attaching plies. Each ply must be applied in
layers per the nailing specifications.

2-ply trusses may be nailed from one face.

For 3-ply trusses, the first two plies are
nailed together from one face, then third ply
is attached to either face of first two plies.

For 4 ply trusses, after assembling the first
three plies, attach fourth ply to either face.

For 5 ply trusses, after assembling the first
four plies, attach fifth ply to either face.

(Refer to engineering for additional bolts or
screw rqmmts and the "STANDARD BOLT
TO SCREW TRUSS CONNECTION
DETAIL" for substituting screws for bolts,
located in the engineering detail pkg.

NOTE: Bolts/Screws are intended to
provide clamping force to aid in allowing the
multi-ply assembly to act as a unit and are
not included in the calculation of ply-to-ply
load transfer.

Designed Per ASCE 7-16

Loading and Design Criteria

	Roof	Floor		
TC LL	20	40	Mean Hgt	15'
TC DL	20	10	Wind Speed	160
BC LL	0	0	Exposure	C
BC DL	10	5		
Duration	1.25	1.00		



Builder: DR Horton Ft Myers

Model: 2540 L

Options: Ext Lanai Tile/Shingle

Location: -

Date: 12/3/2020



Sales Rep: Carl F

Designer: Joe D

Job Number: A200219-20LX3



Revision

Page 1 of 1





-
- Architectural elevation drawing of the exterior wall and roof of a building. The drawing shows a gabled roof with a 12/5 pitch, labeled "TILE ROOF". The exterior wall is labeled "EXTERIOR PLASTER PER R703.7". There are two small square windows labeled "FIXED GLASS" and one larger double-hung window labeled "25 SH". The roofline is labeled "12/5" and "12/5". The wall is labeled "5'-4\" TYP. CANTILEVER TRUSS". The ground line is labeled "2880 DR." and "TOP OF FINISH FLOOR ELEV @ 0'-0\" A.F.F.". The roofline is labeled "TOP OF BOND BEAM ELEV @ 10'-0\" A.F.F.".

LEFT ELEVATION: "L" SCALE: 3/16" = 1'-0"



REVISIONS		
MARK	DATE	DESCRIPTION
	09-14-21	ADDED OUTDOOR KITCHEN ROUGH





SLAB & PLUMBING PLAN: "1" SCALE: 3/16"=1'-0"

REVISIONS		
MARK	DATE	DESCRIPTION
△	09-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020
FLORIDA BUILDING CODE- 7TH EDITION

**Gulf Coast Drafting
& Design**
Phone (239) 540-1822
Fax (239) 540-7759


LOT: 10	BLOCK :	MODEL:
SUBDIV: HERONS GLEN		2540 L W/EXT LANAI
ADDRESS: 21001 MYSTIC WAY	RESIDENCE FOR:	
G.C.D. # : 12396	D.R.H # : 579760010	SPEC

DATE:	05-18-21
DRAWN BY:	JSL
CHECKED BY:	JWC
REVISED:	
	09-14-21
PLAN:	
SLAB & PLUMBING	
SCALE:	
3/16" = 1'-0"	
SHEET#	


A-2 L

A-3 L

MODEL 2540 L: ATTIC VENTILATION FBCR R806									
COORDINATE VENTING REQUIREMENTS WITH ENERGY CALCULATIONS									
AREAS (SQ. FT.)			SOFFIT ONLY (1/150) (NO ROOF VENTS)				WITH ROOF VENTS (1/300) (R.V.)		
MARK	ATTIC	SOFFIT	ATTIC VENTILATION REQUIRED		ATTIC VENTILATION REQUIRED		ATTIC VENTILATION REQUIRED		
			REQ'D AIR FLOW OF SOFFIT	QUAD 4 SOFFIT HAS	ATTIC AREA/300	QUANTITY OF ROOF VENTS	MIN AIR FLOW OF SOFFIT		
1st STORY	4030.9 SQ. FT.	347.6 SQ. FT.	26.87 SQ. FT.	7.73%	8.15%	-- SQ. FT.	-	--%	
			SOFFIT ONLY QUALIFIES				ROOF VENTS ARE NOT REQUIRED		
			SOFFIT MODEL				ROOF VENT MODEL		
			ACM QUAD 4, FULL VENT, NARROW PATTERN, 8.15% FREE AIR FLOW				22" BASE LOMANCO 770-0 0.97 SQ. FT. FREE AIR		



BEARING HEIGHT	
	• BEARING @ 10'-0" A.F.F.
	• INTERIOR BEARING @ 10'-0" A.F.F.
	• BEARING @ 14'-0" A.F.F.



ROOF & CEILING PLAN: "L"

SCALE: 3/16" = 1'-0"

REVISIONS		
MARK	DATE	DESCRIPTION
△	08-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020
FLORIDA BUILDING CODE- 7TH EDITION

Gulf Coast Drafting
& Design

Phone (239) 540-1822
Fax (239) 540-7759


LOT: 10	BLOCK :	MODEL:	2540 L W/EXT LANAI
SUBDIV: HERONS GLEN		RESIDENCE FOR:	SPEC
ADDRESS: 21001 MYSTIC WAY			
G.C.D. # : 12396	D.R.H. # : 579760010		
DATE:	05-18-21		
DRAWN BY:	JSL		
CHECKED BY:	JWC		
REVISED:	09-14-21		
PLAN:	CEILING PLAN		
SCALE:	3/16"=1'-0"		
SHEET#	A-4L		

ELECTRICAL LEGEND


	ELECTRICAL METER
	ELECTRICAL PANEL
	120 V JUNCTION BOX
	SINGLE RECEPTACLE OUTLET
	220 V RECEPTACLE OUTLET
	4-PLEX RECEPTACLE OUTLET
	DUPLEX RECEPTACLE OUTLET
	1/2 SWITCHED DUPLEX OUTLET
	DUPLEX RECEPTACLE @ ELEV. A.F.F.
	TIMER SWITCH
	GFI SWITCH
	DIMMER SWITCH
	3 WAY SWITCH
	SINGLE POLE SWITCH
	AC/DC SMOKE DETECTOR TO BE INTERCONNECTED ANY RESIDENT HAVING A POSSIBLE-BURNING HEATER OR APPLIANCE, A FIREPLACE, OR AN ATTACHED GARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE ALARM INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING PURPOSES. PER RULE 88-3.04.72 SD SMOKE DETECTOR SCD CARBON MONOXIDE/SMOKE DETECTOR
	TELEPHONE OUTLET
	TELEVISION RECEPTION OUTLET
	SURFACE MOUNTED CEILING LIGHT
	FLUSH MOUNTED LIGHT
	WALL MTD. BRACKET LIGHT
	DUPLEX FLOOD LIGHT
	EXHAUST FAN
	TRACK MTD. LIGHTS
	A/C DISCONNECT
	PUSH BUTTON
	DB= DOOR BELL
	KEYPAD
	# FLUORESCENT LIGHT
	2' UNDER COUNTER LIGHT

Electrical Notes:

Install Arc-Fault circuit-Interruption & Tamper-Resistant Receptacles shall be installed in dwelling unit, per NEC 210.12 & 406.11
All electric, electrical equipment and appliances to be set at or above base flood elevations plus 1'-0" freeboard.
All outlets in wet areas and all exterior outlets to be GFI's
Install Phone & T.V. per contract .
INSTALL ALL ELECTRICAL PER NEC 2017



200 Amp Service			
TAG	QUANTITY	PRODUCT	PRODUCT #
A	(31)	Flush Mounted Lt	
B	(3)	Vapors	
C	(1)	Pendant/Nook	
D	(X)	10" Mushrooms	
E	(2)	24" 3 Lt	
F	(2)	36" 4 Lt	
G	(X)	NOT USED	
H	(2)	Coach Lights	
J	(X)	Coach Lights	
K	(1)	J BOX	
L	(2)	4' Fluorescent	
M	(2)	2' Fluorescent	
N	(1)	5lt Chandelier	
O	(X)	3 Lt	
P	(3)	Pendant Light	



REVISIONS		
MARK	DATE	DESCRIPTION
	08-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020
FLORIDA BUILDING CODE- 7TH EDITION

D. R. HOUGHTON
America's Builder


Gulf Coast Drafting
& Design
Phone (239) 540-1822
Fax (239) 540-7759

MODEL:
2540 L W/EXT LANAI
RESIDENCE FOR: SPEC


LOT: 10
BLOCK: HERONS GLEN
SUBDIV: 21001 MYSTIC WAY
ADDRESS: 21001 MYSTIC WAY
G.C.D. #: 12396 DR.H #: 579760010

DATE: 05-18-21
DRAWN BY: JSL
CHECKED BY: JWC
REVISED: 09-14-21
PLAN: ELECTRICAL
SCALE: 3/16" = 1'-0"
SHEET#

A-5 L



R703.7 EXTERIOR PLASTER
ASTM C926 AND ASTM C1063



MID WALL WEEP SCREED DETAIL

WEEP SCREED DETAIL
INSTALL AT ALL EXTERIOR WALL LOCATIONS WHERE WOOD STUD FRAMING IS ABOVE MASONRY WALLS.

RESIDENTIAL SPECIFICATIONS

GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT THE JOB SITE PRIOR TO COMMENCING WORK. THE CONTRACTOR SHALL REPORT ALL DISCREPANCIES BETWEEN THE DRAWINGS AND EXISTING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- THE CONTRACTOR SHALL SUPPLY, LOCATE AND BUILD INTO THE WORK ALL INSERTS, ANCHORS, ANGLES, PLATES, OPENINGS, SLEEVES, HANGERS, SLAB DEPRESSIONS AND PITCHES AS MAY BE REQUIRED TO ATTACH AND ACCOMMODATE OTHER WORK.
- ALL DETAILS AND SECTIONS SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL BE CONSTRUCTED TO APPLY TO ANY SIMILAR SITUATION ELSEWHERE IN THE WORK EXCEPT WHERE A DIFFERENT DETAIL IS SHOWN.
- SUBSURFACE SOIL CONDITION INFORMATION IS NOT AVAILABLE. FOUNDATIONS ARE DESIGNED FOR A SOIL BEARING CAPACITY OF 2,000 PSF. THE CONTRACTOR SHALL REPORT ANY DIFFERING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH JOB SPECIFICATION AND HOUSE PLANS, MECHANICAL, ELECTRICAL, PLUMBING, AND SITE DRAWINGS. CONSULT THESE DRAWINGS FOR SLEEVES, DEPRESSIONS AND OTHER DETAILS NOT SHOWN ON STRUCTURAL DRAWINGS.
- ALL SPECIFIED FASTENERS MAY ONLY BE SUBSTITUTED IF APPROVED BY THE ENGINEER IN WRITING. THE INSTALLATION OF THE FASTENERS SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS. SIMPSON FASTENERS SPECIFIED MAY BE SUBSTITUTED WITH THE SAME QUANTITY AND EQUIVALENT STRENGTH PRODUCT.
- TREATED WOOD REQUIREMENTS:- ALL WOOD EXPOSED TO WEATHER SHALL BE PROTECTED, PRESSURE TREATED, OR NATURALLY RESISTANT TO DECAY. ALL WOOD TOUCHING MASONRY OR CONCRETE SHALL BE ISOLATED, OR PRESSURE TREATED.
- THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS COMPLETE. IT IS THE CONTRACTORS SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURES AND SEQUENCES TO ENSURE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING ERECTION. THIS INCLUDES THE NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUTS, OR TIE DOWNS.
- CEILING DRYWALL INSTALLED WITHIN THE HOUSE TO TRUSSES SPACED 24" O.C. SHALL BE 5/8" DRYWALL OR 1/2" SAG RESISTANT PER SEC. 702.2.5
- LANAI CEILINGS & COVERED ENTRY CEILINGS 1X4 STRIPPING @ 16" O.C. FASTENED WITH 2-8d NAILS TO EACH TRUSS. 5/8" EXTERIOR GYPSUM BOARD CEILING FASTENED WITH 8d NAILS OR 1-5/8" DRYWALL SCREWS @ 8" OC. EDGE AND FIELD.

GENERAL ROOF ASSEMBLY

ROOF SHEATHING PER TABLE R803.2.2 SHALL BE 19/32 APA RATED SHEATHING, EXPOSURE 1, SPAN RATING 40/20 OR BETTER. INSTALL PANELS WITH LONG BETWEEN ADJACENT SHEETS SHALL BE MAINTAINED. INSTALL 1/4" CLIPS AT UNSUPPORTED PANEL EDGES. SEE STRUCTURAL.

FLASHING SHALL BE ALUMINUM ALUMINUM ZINC COATED STEEL .0179 INCHES THICK, 26 GAUGE AZ50 ALUM ZINC OR GALVANIZED STEEL .0178 INCHES THICK, 26 GAUGE ZINC COATED 880. FLASHING SHALL BE INSTALLED IN ACCORDANCE WITH THE ZIP SYSTEM ROOF SHEATHING MANUFACTURERS PUBLISHED REQUIREMENTS. ALL FLASHING AND INSTALLATION SHALL CONFORM TO SECTION R803.2.8 (1 TO 6).

DROP EDGE SHALL BE PROVIDED AT ALL EAVES AND GABLES OF SHINGLE ROOFS. LAPPED A MINIMUM OF 3" @ JOINTS. THE OUTSIDE EDGE SHALL EXTEND A MINIMUM OF 1/2" BELOW SHEATHING AND THE INSIDE EDGE SHALL EXTEND BACK A MINIMUM OF 2" Drip EDGE SHALL BE FASTENED AT NO MORE THAN 4" CENTERS. THERE SHALL BE A MINIMUM OF 4" WIDTH OF ROOF CEMENT INSTALLED OVER THE DROP EDGE FLANGE.



ASPHALT SHINGLE ROOF SPECS

SHINGLES 3/8" felt shall be installed under asphalt shingles. All asphalt shingles shall have self sealing strips or be interlocking and comply with ASTM D 225 or D3462. Installation shall comply with the manufacturer's requirements for installation in the given Florida wind zone, as determined by ASTM D 5161.


CLAY AND CONCRETE TILE ROOF SPECS

INSTALL PEEL AND STICK UNDERLAYMENT APPROVED FOR SINGLE LAYER APPLICATION UNDER TILE ROOF. THE INSTALLATION OF CLAY AND CONCRETE TILE SHALL COMPLY WITH THE PROVISIONS OF R803.3 F.C. MARKING EACH ROOF TILE SHALL HAVE A PERMANENT MANUFACTURERS IDENTIFICATION MARK. APPLICATION SPECIFICATIONS: THE TILE MANUFACTURERS WRITTEN APPLICATION SPECIFICATIONS SHALL BE AVAILABLE AND SHALL INCLUDE BUT NOT BE LIMITED TO THE FOLLOWING:

- TILE PLACEMENT AND SPACING.
- ATTACHMENT SYSTEM NECESSARY TO COMPLY WITH CURRENT WIND CODE.
- AMOUNT AND PLACEMENT OF MORTAR.
- AMOUNT AND PLACEMENT OF ADHESIVE.
- TYPE, NUMBER, SIZE, AND LENGTH OF FASTENERS AND CLIPS.
- UNDERLAYMENT.
- SLOPE REQUIREMENT.



TYPICAL WALL SECTION
SCALE: N.T.S.



REVISIONS		
MARK	DATE	DESCRIPTION
△	08-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020 FLORIDA BUILDING CODE- 7TH EDITION

Gulf Coast Drafting & Design

Phone (239) 540-1822

Fax (239) 540-7759

MODEL: 2540 L W/ EXT LANAI

BLOCK: HERON'S GLEN

LOT: 10

SUBDIV: 21001 MYSTIC WAY

RESIDENCE FOR: SPEC

G.C.D.#: 12396 D.R.H.#: 579760010

DATE: 05-18-21

DRAWN BY: JSL

CHECKED BY: JWC

REVISD: 09-14-21

PLAN: SECTION

SCALE: AS NOTED

SHEET# A-6L

FOUNDATION PLAN

SCALE: 3/16" = 1'-0"

PLAN NOTES:

- 1) TOP OF GROUND FLOOR SLAB DATUM ELEVATION 0'-0".
- 2) "F" DENOTES CONTINUOUS WALL FOOTING TYPE PER SCHEDULE THIS SHEET.
- 3) "P" DENOTES PAD FOOTING AT CONCENTRATED LOADS PER SCHEDULE THIS SHEET.
- 4) PROVIDE #5 VERTICAL REINFORCING AT DOT LOCATIONS SHOWN ON PLAN FROM FOOTING TO BOND BEAM.
- 5) ALL DIMENSIONS ARE TO OUTSIDE FACE OF MASONRY WALLS. SOME SLAB EDGES MAY EXTEND BEYOND FACE OF WALL.
- 6) FOR DIMENSIONS OF ROUGH OPENINGS IN MASONRY WALLS, COORDINATE WITH WINDOW/DOOR SUPPLIER.
- 7) PROVIDE PRESSURE TREATED BUCKS AT WINDOWS / DOORS PER DETAIL 7/S-3.










WALL FOOTING SCHEDULE

TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REINFORCING	SHAPE
F1	CONT.	1'-4"	0'-8"	2-#5	
F2	CONT.	1'-8"	0'-10"	2-#5	
F3	CONT.	1'-0"	1'-8"	2-#5	
F4	CONT.	1'-4"	1'-8"	2-#5	
F5	CONT.	1'-4"	1'-0"	2-#5	
F6	CONT.	1'-4"	1'-0"	2-#5	
F6A	CONT.	0'-8"	0'-8"	1-#5	
TE	CONT.	0'-8"	0'-8"	1-#5	

NOTE: REINFORCING IN FOOTINGS SHALL BE CONTINUOUS AT CORNERS AND INTERSECTIONS. ADD CORNER BAR 25"x25" AT EACH LONGITUDINAL BAR, SEE 6/S-3.

PAD FOOTING SCHEDULE

TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REINF.	REMARKS
P1	2'-6"	2'-6"	1'-0"	3-#5	3-#5
P2	3'-0"	3'-0"	1'-0"	4-#5	4-#5
P3	3'-6"	3'-6"	1'-0"	4-#5	4-#5
P4	4'-0"	4'-0"	1'-0"	5-#5	5-#5
P5	2'-6"	5'-0"	1'-0"	3-#5	6-#5



FOUNDATION PLAN: "L"

SCALE: 3/16"=1'-0"

MARK	DATE	DESCRIPTION
△	08-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020 FLORIDA BUILDING CODE- 7TH EDITION

D.R. HORTON
America's Builder

Gulf Coast Drafting
& Design
Phone (239) 540-1822
Fax (239) 540-7759

STRUCTURAL ENGINEERING
STRUCTURAL SYSTEMS
OF NORTH FLORIDA
1604 SE 47th ST, SUITE 605
FORT MYERS, FL 33905
CE 3955 5-9-1-7554
CA# 88829

RAUL REYES
No. 88925
STATE OF FLORIDA
PROFESSIONAL ENGINEER

MODEL: 2540 L W/ EXT LANAI
RESIDENCE FOR: SPEC

LOT: 10 BLOCK :
SUBDIV: HERON'S GLEN
ADDRESS: 21001 MYSTIC WAY
G.C.D.# : 12396 D.R.H.# : 579760010

DATE: 05-18-21

DRAWN BY: JSL

CHECKED BY: JWC

REVISED: 09-14-21


PLAN: FOUNDATION

SCALE: 3/16" = 1'-0"

SHEET#

S-1 L

TRUSS STRAPPING TO MASONRY			
MAX TRUSS UPLIFT (LBS)	STRAP/ANCHOR Valid lengths x/x/x	FASTENERS	
1450 (1 PLY)	(1) META16/18/20	(8) 0.148x1-1/2"	EMBED 4"
1810 (1 PLY)	(1) META16/20	(9) 0.148x1-1/2"	EMBED 4"
1875 (1 PLY)	(2) META16/18/20	(10) 0.148x1-1/2"	EMBED 4"
1920 (1 PLY)	(2) META16/20	(10) 0.148x1-1/2"	EMBED 4"
2120 (1 PLY)	(1) META16/20	(10) 0.148x1-1/2"	EMBED 4"
1795 (2 or 3 PLY)	(2) META16/18/20	(14) 0.162x3-1/2"	EMBED 4"
2365 (2 or 3 PLY)	(2) META16/20	(12) 0.162x3-1/2"	EMBED 4"
3965/DF/SP (2 PLY)	MTT4	(22) 0.148x3"	ATR, EPOXY 12"
3000/DF/SP (1 PLY 2x4)	HTT4	(18) 0.148x1-1/2"	5/8" ATR, EPOXY 12"
4455/DF/SP (1 PLY 2x6)	HTT4	(18) SD#10x1-1/2"	5/8" ATR, EPOXY 12"
4235/DF/SP (2 PLY 2x4)	HTT4	(18) 0.162x2-1/2"	5/8" ATR, EPOXY 12"
4555/DF/SP (1 PLY 2x6)	HTT5	(26) SD#10x1-1/2"	5/8" ATR, EPOXY 12"
4670/DF/SP (2 PLY 2x4)	HTT5	(26) 0.148x3"	5/8" ATR, EPOXY 12"
5445/DF/SP (2 PLY 2x4)	HTT5KT	(26) SD#10x2-1/2"	5/8" ATR, EPOXY 18"
10690/DF/SP (2 PLY)	(1) HGT-2	(16) 0.148x3"	(2) 3/4" ATR, EPOXY 12"
10790/SYP (3 PLY)	(1) HGT-3	(16) 0.148x3"	(2) 3/4" ATR, EPOXY 12"
NOTES: 1) PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE AND SUITABLE FOR THE GEOMETRY. EMBED STRAP ON 6" OF WALL. 2) ANY OF THE VALID LENGTHS SHOWN MAY BE USED IN PLACE OF THE LENGTH SPECIFIED ON PLAN. 3) CONNECTORS ARE SIMPSON STRONG TIE. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS. SUBSTITUTIONS MUST BE APPROVED IN WRITING BY THE ENGINEER OF RECORD. 4) WHERE EMBEDDED STRAPS ARE MISSING, OR MIS-LOCATED, INSTALL RETROFIT STRAP PER 10/S-3 PER UPLIFT IN TRUSS ENGINEERING.			



TRUSS STRAPPING TO STUD WALL/WOOD BEAM			
MAX TRUSS UPLIFT (LBS)	STRAP(S) Valid lengths x/x/x	FASTENERS	
850	(1) MTS16/20/30	(14) 0.148x1-1/2"	or 3"
1700	(2) MTS16/20/30	EACH STRAP	
2550	(3) MTS16/20/30	EACH STRAP	
1125	(1) HTS20/24/30	(24) 0.148x1-1/2"	
2250	(2) HTS20/24/30	OR	
3375	(3) HTS20/24/30	(20) 0.148x3"	
4500	(4) HTS20/24/30	EACH STRAP	

INSTALL AT ALL TRUSSES TO 850 lb UPLIFT. FOR HIGHER UPLIFTS, SEE NOTES ON PLAN.


NOTES:

- 1) PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE.
- 2) ANY OF THE VALID LENGTHS SHOWN MAY BE USED IN PLACE OF THE LENGTH SPECIFIED ON PLAN.
- 3) 1-1/2" NAIL SHALL BE USED IN 1 PLY LUMBER, 2 PLY LUMBER IS REQUIRED FOR 3" NAILS.
- 4) CONNECTORS ARE SIMPSON STRONG TIE. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS.

SIMPSON CATALOG C-C-2019

PLAN NOTES:


- 1) ROOF TRUSS BEARING ELEVATION VARIES, SEE LEGEND.
- 2) ROOF FRAMING SHALL BE WOOD TRUSSES DESIGNED BY A DELEGATED TRUSS ENGINEER PER DESIGN CRITERIA ON SHEET 9-3.
- 3) PROVIDE STRAPPING AT TRUSSES PER NOTES ON THIS SHEET.
- 4) FOR NAILING OF ROOF DECK, SEE 1 AND 2 ON 9-3.
- 5) 8F8-1B W/C DENOTES PRECAST LINTEL ABOVE DOOR/WINDOW OPENING PER SCHEDULE THIS SHEET.
- 6) AT TRUSS BEARING, PROVIDE 8x8 MASONRY BOND BEAM W/ 1 #6 CONTINUOUS, SEE DETAIL 11/S-3.



TRUSS BEARING CONDITIONS AND STRAPPING IS BASED ON TRUSS LAYOUT PREPARED BY AMERICAN BUILDERS SUPPLY, JOB #: M2000219-20LX3, DATED: 12/03/2020, REVISION: 04/28/21

BEARING HEIGHT

BEARING @ 10'-0" A.F.F.	
INTERIOR BEARING @ 10'-0" A.F.F.	
BEARING @ 14'-0" A.F.F.	



ROOF FRAMING PLAN: 11L SCALE: 3/16" = 1'-0"

REVISIONS		
MARK	DATE	DESCRIPTION
1	08-14-21	ADDED OUTDOOR KITCHEN ROUGH

DESIGN IN ACCORDANCE W/ THE 2020 FLORIDA BUILDING CODE- 7TH EDITION

D-R HORTON
America's Builder

Gulf Coast Drafting & Design
Phone (239) 540-1822
Fax (239) 540-7759



MODEL: 2540 L W/EXT LANAI
SUBDIV: HERONS GLEN
ADDRESS: 21001 MYSTIC WAY
G.C.D. #: 12396 D.R.H. #: 579760010

LOT: 10 BLOCK: 10
SUBDIV: HERONS GLEN
ADDRESS: 21001 MYSTIC WAY
G.C.D. #: 12396 D.R.H. #: 579760010

DATE: 05-18-21

DRAWN BY: JSL


CHECKED BY: JWC

REVISED: 09-14-21


PLAN: ROOF

SCALE: 3/16" = 1'-0"


SHEET# S-2 L




1 FALSE KNEEWALL AT ENTRY ONLY USED FOR ELEVATIONS F & M
SCALE: 3/4" = 1'-0"




2 FALSE KNEEWALL AT ENTRY ONLY USED FOR ELEVATION E & L
SCALE: 3/4" = 1'-0"




3 OUTLOOKER DETAIL AT DROP GABLE ONLY USED FOR ELEVATIONS E, F & L
SCALE: N.T.S.




4 OUTLOOKER DETAIL AT RAISED GABLE ONLY USED FOR ELEVATION M
SCALE: N.T.S.




5A SUSPENDED HEADER AT MITERED GLASS TRUSS PERPENDICULAR TO WINDOW
SCALE: 3/4" = 1'-0"



5B SUSPENDED HEADER AT MITERED GLASS TRUSS PARALLEL TO WINDOW
SCALE: 3/4" = 1'-0"



6 WOOD FRAMED ARCH
SCALE: 3/4" = 1'-0"



7 GABLE END BRACING ONLY USED FOR ELEVATION F
SCALE: N.T.S.

REVISIONS	BY
09/02/21	RR
NO CHANGES THIS SHEET	

STRUCTURAL ENGINEERING:
STRUCTURAL SYSTEMS OF NORTH FLORIDA
1634 S.E. 47th STREET, SUITE #3
CAPE CORAL, FL 33904
(239) 549-4554
CA # 8829



D.R. HORTON, P.E.
America's Builder

STRUCTURAL DETAILS
MODEL 2540 L
EXT LANAI
21001 MYSTIC WAY
NORTH FORT MYERS, FLORIDA
LOT: 10 SUBDIVISION: HERON'S GLEN

DESIGN/DRAWN
DWB/GH
CHECKED
DWB
DATE
05/21/21
SCALE
VARIES
JOB NO.
DR12396
SHEET

S-4

SHEET 4 OF 4

FOR AMERICAN BUILDERS SUPPLY TRUSSES, 160 MPH, EXPOSURE C, ELEVATION L w/ EXT LANAI, JOB # M2000219-20LX3, DATED: 12/03/20, REVISED: 04/29/21