



Community Development Department

18400 Murdock Circle, Port Charlotte, FL 33948
Building Phone: 941.743.1201 | Building Fax: 941.764.4907
Zoning Phone: 941.743.1964 | Zoning Fax: 941.743.1598
BuildingSvcs@CharlotteCountyFL.gov
www.CharlotteCountyFL.gov

For Office Use Only

Permit Number

20 _____

Application Date

CSR Initials _____

ONE AND TWO FAMILY DWELLING DATA SUMMARY SHEET

Florida Building Code 7th Edition (2020)

OWNER'S NAME: D. R. Horton, Inc CONTRACTOR'S NAME: D. R. Horton, Inc

PROJECT ADDRESS: 15707 APPLEWHITE CIRCLE PORT CHARLOTTE FL 33981
Number & Street City, State, & Zipcode

Applicable Codes: Building, Mechanical, Plumbing, Accessibility, & Energy Codes - 7th Edition (2020) Florida Building Code, Residential Volume. Electrical Code - NFPA 70 & NEC 2017

Manufacturer's Product Approvals

Doors: See Attached Overhead Doors: See Attached Windows: See Attached

Mitered Glass: See Attached Roof Coverings: See Attached **Protection of Openings:**

Soffit: See Attached Siding: See Attached Shutters: See Attached

Method of Design per Florida Building Code (FBC) R301:

☒ Florida Building Code, 7th Ed (2020) ☐ ICC 600 ☐ Other: _____

Designer's Name: Structural Systems of N. Florida Inc.

Design Data (Risk Category II):

Basic Wind Speed (Vult) 160 mph (Figure R301.2(4))

Nominal Design Wind Speed (Vasd) 124 m.p.h. Flood Design Data N/A Final Floor Elevation See Site Plan

Exposure Category Section (R301.2.1.4) ☐ B ☒ C ☐ D Soil Design Load-Bearing Value 2000 PSF

Structural Forces (Section R301.4 / 301.5 / 3601.6)

Floor Design: Live Load 40 p.s.f. Dead Load Slab on Grade p.s.f.

Roof Design: Live Load 20 p.s.f. Dead Load TC=20 BC=10 p.s.f. Roof Slope 5:12

Window and Door Wind Pressure Design Loading:

Mean roof height 15 ft Pressures are worst case only. See plan for actual.
Windows +33.5/-44.8 p.s.f. Doors +33.5/-44.8 p.s.f. Garage Doors +29.4/-33.3 p.s.f.

Components and Cladding Design Pressures: hip roof

Zone 1: 24.9/-44.8 p.s.f. Zone 2: +24.9/-61.7 p.s.f. Zone 3: +24.9/-61.7 p.s.f. Zone 4: 33.5/-36.3 p.s.f. Zone 5: 33.5/-44.8 p.s.f.

Area Tabulation: TOTAL (Sq. Ft): 2,780

Living (Sq. Ft.) 1982 Garage (Sq. Ft.) 446 Lanai (Sq. Ft.) 270


Entry (Sq. Ft.) 82 Storage (Sq. Ft.) _____ Other (Sq. Ft.) _____


I certify to the best of my knowledge and belief that these plans and specifications have been designed to comply with the structural portion of the Building Code for wind, flood and gravity loads as amended and enforced by the permitting jurisdiction.

Signature: _____ Date: _____


Designer's Printed Name: _____







This item has been digitally signed by Raul Reyes on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be validated on any electronic copies.





The diagram illustrates the relationship between different types of square cuts and bevels. It shows a series of horizontal and vertical lines representing the structure. A diagonal line is drawn from the bottom left to the top right. The area between the diagonal line and the top horizontal line is labeled "CJ DOUBLE BEVEL". The area between the diagonal line and the bottom horizontal line is labeled "J SQUARE CUT". The area to the right of the diagonal line is labeled "EJ SQUARE CUT". A note on the right side states "SEE ENGINEERING FOR FASTENING REQUIREMENTS".




9'~4' A.F.F.		0'~0'	ELEV.
12'~4' A.F.F.		+3'~0'	ELEV.
			ELEV.
			ELEV.
			ELEV.
			ELEV.
			ELEV.

(C) SIMPSON HUS 26 (M) SIMPSON HGUS 28-3
(F) SIMPSON HUS 28 (N) SIMPSON HHUS 48
(H) SIMPSON HGUS 28 (P) SIMPSON LUS 24
(I) SIMPSON HGUS 28-2 (B) SIMPSON THA 422
(W) SIMPSON THJA26 (X)

APPROVED BY: _____
DATE: _____ REQUESTED DELIVERY DATE: _____
JOBSITE CONTACT NAME: _____
PHONE #: _____
E-MAIL: _____

☒ Accepted As-Is ☐ Accepted As Noted ☐ Revise and Resubmit


SCOSTA CORP.			
WOOD, STEEL OR TIMBER ROOF & FLOOR TRUSSES			
3670 COMMERCE CENTER DRIVE SEBRING, FL 33870 (863) 385-8242			
SCALE: 1/4"=1'-0"	DATE: 02/10/21	REVISED BY:	DRAWN BY: KCD
JOB ADDRESS: 1989 B GARAGE RIGHT LEE/COLLIER/CHARLOTTE		1 OF 1	
CUSTOMER: D.R. HORTON		JOB # DR1989B	




FRONT ELEVATION "BR"

$$\overline{1/4'' = 1'-0''}$$


- 1 MID-WALL WEEP SCREED AT WOOD MASONRY INTERFACE. INSTALL STRICTLY PER MFG. INSTRUCTIONS
- 2 ROOF / WALL SCREED INSTALL STRICTLY PER MFG. INSTRUCTIONS



REAR ELEVATION "BR"

$$\overline{1/4'' = 1'-0''}$$





RIGHT ELEVATION "BR"

$$\overline{1/4'' = 1'-0''}$$


LEFT ELEVATION "BR"

$$1/4'' = 1'-0''$$

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION



DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION

[illegible]

1	16080 OHGD	8'-0"	16'-0"	1
2	3080 ENTRY	8'-0"	3'-0"	1
3	12" SIDE LITE	8'-0"	1'-0"	1
4	2-4080 SL. GL. DR.	8'-0"	8'-0"	1

WINDOW SCHEDULE						
MARK	DESCRIPTION	MANUFACTURER	WIDTH	HEIGHT	COMMENTS	QTY

A	25 SH		3'-4"	5'-5"		1
B	35 SH		4'-8"	5'-5"		4
C	2-25 SH		6'-4"	5'-3"		1
D	48" X 16"	FIXED GLASS	4'-2"	1'-6"		1

OPT IMPACT GLASS MAY BE INSTALLED IN LIEU OF SHUTTERS VERIFY W/ CONTRACT

DOOR HEADERS		
6'-8" BI-FOLD	HEADER HEIGHT	82" A.F.F.
6'-8" SWING	HEADER HEIGHT	82 1/2" A.F.F.
8'-0" SWING	HEADER HEIGHT	98 1/2" A.F.F.

CABINET BACKING		
KITCHEN	UPPER TOP @ 84"	BASE TOP @ 35"
MASTER BATH	UPPER	BASE TOP @ 35"
GUEST BATH	UPPER	BASE TOP @ 31"
LAUNDRY ROOM	UPPER TOP @ 84"	BASE

PLAN NOTES

- 1) VERIFY ALL ROUGH OPENING DIMENSIONS FOR ALL WINDOWS AND DOORS
- 2) PROVIDE SAFETY GLAZING WITHIN 24" FROM EXIT PER FLORIDA BUILDING CODE R 308.4.2.
- 3) PROVIDE SAFETY GLAZING AT BATH SHOWER PER FLORIDA BUILDING CODE R 308.4.5.
- 4) NON BEARING INTERIOR FRAME WALLS SHALL BE FRAMED W/ WOOD OR METAL STUDS. SPACING SHALL NOT EXCEED 24" O.C. (NON BEARING WALLS ONLY)
- 5) PROVIDE DEAD WOOD IN ATTIC FOR OVERHEAD GARAGE DOOR HARDWARE
- 6) KITCHEN KNEE WALL TO BE FRAMED W/ TOP @ 3/4 1/2" A.F.F..
- 7) INSTALL SMOOTH WALLS IN KITCHEN AND ALL BATHROOM AREAS
- 8) WHERE DRYWALL CEILING IS APPLIED TO TRUSSES @ 24" O.C. USE 5/8" DRYWALL OR 1/2" SAG RESISTANT PER SEC. R702.3.5
- 9) THE GARAGE SHALL BE SEPARATED FROM THE RESIDENCE + ATTIC BY NOT LESS THEN 1/2" GYPSUM BOARD APPLIED TO THE GARAGE SIDE. GARAGES BENEATH HABITABLE ROOMS SHALL BE SEPARATED WITH NOT LESS THAN 5/8" TYPE "X" GYPSUM BOARD OR EQUIVALENT. WHERE THE SEPARATION IS A FLOOR - CEILING ASSEMBLY, THE STRUCTURE SUPPORTING THE SEPARATION SHALL ALSO BE PROTECTED BY NOT LESS THAN 1/2" GYPSOM BOARD OR EQUIVALENT
- 10) INSTALL 1 3/8" THICK SOLID WOOD DOOR BETWEEN LIVING AND GARAGE PER FLORIDA BUILDING CODE R302.5.1.
- 11) ALL WINDOWS INSTALLED 72" ABOVE GRADE MUST COMPLY WITH R312.2 MIN 24" SILL HEIGHT OR PROVIDED WITH AN APPROVED WINDOW FALL PREVENTION DEVICE
- 12) ALL CLOSET SHELVES TO BE 12". ALL PANTRY + LINEN TO BE (4)-16" SHELVES 18" O.C.F.F. W/ 15" INCREMENT.
- 13) ALL MECHANICAL AND ELECTRICAL EQUIPMENT TO BE INSTALLED AT OR ABOVE FLOOD PLUS 1'-0" FREEBOARD



SQUARE FOOTAGE	
ENTRY AREA	82 SF
LANAI AREA	270 SF
GARAGE AREA	446 SF
LIVING AREA	1982 SF
TOTAL AREA	2780 SF

ENTRY AREA	82 SF
LANAI AREA	270 SF
GARAGE AREA	446 SF
LIVING AREA	1982 SF
TOTAL AREA	2780 SF

INTERIOR DOOR SCHEDULE		
MARK	DOOR WIDTH	NOTES
1	3'-0"	P.K. = POCKET DOOR
2	2'-1 0"	B.F. = BI-FOLD DOOR
3	2'-8"	B.P. = BI-PASS DOOR
4	2'-6"	
5	2'-4"	L.V. = LOUVERED DOOR
6	2'-0"	
7	1'-8"	
8	1'-6"	

MARK	DOOR WIDTH	NOTE5
1	3'-0"	P. K. = POCKET DOOR
2	2'-1 1/2"	B. F. = BI-FOLD DOOR
3	2'-0"	
4	2'-6"	B. P. = BI-PASS DOOR
5	2'-4"	
6	2'-0"	L. V. = LOUVERED DOOR
7	1'-8"	
8	1'-6"	

Diagram illustrating typical dimension string for exterior wall framing. The diagram shows three vertical wall sections. The first section is labeled "FACE OF EXTERIOR WALL". The second section is labeled "FACE OF OUTSIDE WALL TO FACE OF STUD WALL". The third section is labeled "FACE OF STUD TO FACE OF STUD". Dimensions are indicated: 3 1/2" for the total width of the first two sections, and 1 1/2" for the width of the third section.



FLOOR PLAN "BR"
1/4" = 1'-0"



DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION


Y:\0-New Data\1 -MASTER 2019\2019-BUILDERS\DR HORTON 2019\SUBDIVISIONS\GULF COVE SPOT LOTS\12522 LOT 18 BLK 4422 1989 BRREVIT\12522 1989 BR.rvt

MODEL 1989 B: ATTIC VENTILATION FBCR R806
COORDINATE VENTING REQUIREMENTS WITH ENERGY CALCULATIONS

AREAS (SQ. FT.)			SOFFIT ONLY (1/150) (NO ROOF VENTS)			WITH ROOF VENTS (1/300) (R.V.)		
ATTIC VENTILATION REQUIRED			ATTIC VENTILATION REQUIRED			ATTIC VENTILATION REQUIRED		
MARK	ATTIC	SOFFIT	ATTIC AREA/150	REC'D AIR FLOW OF SOFFIT	QUAD 4 SOFFIT HAS	ATTIC AREA/300	QUANTITY OF ROOF VENTS	MIN AIR FLOW OF SOFFIT
1st STORY	3102.1 SQ. FT.	320.4 SQ. FT.	20.68%	6.45%	0.15%	~ SQ. FT.	-	~%
			"SOFFIT ONLY" QUALIFIES			ROOF VENTS ARE NOT REQUIRED		
			SOFFIT MODEL ACM QUAD 4, FULL VENT, NARROW PATTERN, 8.15% FREE AIR FLOW			ROOF VENT MODEL 32" BASE 22-3/8" BASE LOMANCO 770-D 0.97 SQ. FT. FREE AIR		

WALL HEIGHT

	= MAIN WALL @ 9'-4"
	= ENTRY WALL @ 12'-4"





ROOF PLAN "BR"
1/4" = 1'-0"


DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION


Y:\0-New Data\1 -MASTER 2019\2019-BUILDERS\DR HORTON 2019\SUBDIVISIONS\GULF COVE SPOT LOTS\12522 LOT 18 BLK 4422 1989 BR\REVIT\12522 1989 BR.rvt


ELECTRICAL LEGEND


ELECTRICAL METER


ELECTRICAL PANEL


120 V JUNCTION BOX


SINGLE RECEPTACLE OUTLET


220 V RECEPTACLE OUTLET


4-PLEX RECEPTACLE OUTLET


DUPLEX RECEPTACLE OUTLET


1/2 SWITCHED DUPLEX OUTLET


DUPLEX RECEPTACLE AT ELEV. A.F.F.


DUPLEX RECEPTACLE - ABOVE COUNTER


SINGLE POLE SWITCH


3 WAY SWITCH


DIMMER SWITCH


MOTION SENSOR SWITCH


AC/DC SMOKE DETECTOR TO BE INTERCONNECTED ANY RESIDENT HAVING A FOSSIL-BURNING HEATER OR APPLIANCE, A FIREPLACE, OR AN ATTACHED GARAGE SHALL HAVE AN OPERATIONAL CARBON MONOXIDE ALARM INSTALLED WITHIN 10 FEET OF EACH ROOM USED FOR SLEEPING PERPOSES, PER RULE 9B-3.04.72


SD (SMOKE DETECTOR)


SCD (CARBON MONOXIDE/ SMOKE DETECTOR)


TELEPHONE OUTLET


TELEVISION RECEPTION OUTLET


SURFACE MOUNTED CEILING LIGHT


FLUSH MOUNTED LIGHT


WALL MTD. BRACKET LIGHT


DUPLEX FLOOD LIGHT


EXHAUST FAN


TRACK MTD. LIGHTS


A/C DISCONNECT

PUSH BUTTON (PB) / DOOR BELL (DB)

INTERCOM

KEYPAD

4' FLUORESCENT LIGHT

2' UNDER COUNTER LIGHT

NOTE: NOT ALL SYMBOLS ARE USED FOR THIS PROJECT.

ELECTRICAL NOTES:
ARC-FAULT CIRCUIT-INTERRUPTERS AND TAMPER RESISTANT RECEPTACLES SHALL BE INSTALLED IN DWELLING UNITS PER N.E.C 210.12 AND 400.11
ALL ELECTRIC, ELECTRICAL EQUIPMENT AND APPLIANCES TO BE SET AT OR ABOVE BASE FLOOD ELEVATION PLUS 1'-0" FREEBOARD.
ALL OUTLETS IN WET AREAS AND ALL EXTERIOR OUTLETS TO BE GFI'S.
INSTALL PHONE AND T.V PER CONTRACT.
INSTALL ALL ELECTRICAL PER NEC 2014


200 AMP ELECTRICAL RISER DIAGRAM

ELECTRICAL PLAN 1989		
200 AMP SERVICE		
TAG	QUANTITY	PRODUCT
A	(14)	(FLUSH MOUNTED LT)
B	(2)	(VAPORS)
C	(3)	(PENDANT LIGHT
D	(11)	(10" MUSHROOMS)
E	(3)	(24" 3 LT)
F	(X)	(36" 4 LT)
G	(X)	(NOT USED)
H	(2)	(COACH LIGHTS)
I	(X)	(COACH LIGHTS)
J	(X)	(J BOX)
K	(X)	(4' FLUORESCENT)
L	(X)	(2' FLUORESCENT)
M	(X)	(SLT CHANDELIER)
N	(X)	(3 LT)
O	(X)	(PENDANT/ NOOK)
P	(X)	(X)
Q	(X)	(X)


ELECTRICAL PLAN "BR"

ELECTRICAL PLAN "BR"
1/4" = 1'-0"

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION



D.R.HORTON
America's Builder



Gulf Coast
Drafting & Design, Inc.

EMAIL: PLANS@GULFCOASTDRAFTING.COM
PHONE: 239-540-1822
1515 SE 47th ST. CAPE CORAL, FL 33904

LOT: 18
SUBDIVISION: SOUTH GULF COVE
ADDRESS: 15707 APPLEWHITE CIRCLE

BLOCK: 4422

D.R.H. #: 579660066

MODEL
1989

GCD JOB # 12522

DATE:
04/13/21

DRAWN BY:
CWL

CHECKED BY:
JWC


REVISED:

PLAN:
ELECTRICAL

SCALE:
As indicated


A-5 BR

Y:\O-New Data\1 -MASTER 2019\2019-BUILDERS\DR HORTON 2019\SUBDIVISIONS\GULF COVE SPOT LOTS\12522 LOT 1\8 BLK 4422 1989 BR\REVIT\2522 1989 BR.rvt




R703.7 EXTERIOR PLASTER

ASTM C926 AND ASTM C1063



MID WALL WEEP SCREED DETAIL



WEEP SCREED DETAIL

INSTALL AT ALL EXTERIOR WALL LOCATIONS WHERE WOOD STUD FRAMING IS ABOVE MASONRY WALLS.

RESIDENTIAL SPECIFICATIONS

GENERAL NOTES

- THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS AT THE JOB SITE PRIOR TO COMMENCING WORK. THE CONTRACTOR SHALL REPORT ALL DISCREPANCIES BETWEEN THE DRAWINGS AND EXISTING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- THE CONTRACTOR SHALL SUPPLY, LOCATE AND BUILD INTO THE WORK ALL INSERTS, ANCHORS, ANGLES, PLATES, OPENINGS, SLEEVES, HANGERS, SLAB DEPRESSIONS AND PITCHES AS MAY BE REQUIRED TO ATTACH AND ACCOMMODATE OTHER WORK.
- ALL DETAILS AND SECTIONS SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL BE CONSTRUCTED TO APPLY TO ANY SIMILAR SITUATION ELSEWHERE IN THE WORK EXCEPT WHERE A DIFFERENT DETAIL IS SHOWN.
- FOR REQUIRED SOIL BEARING, SEE STRUCTURAL. THE CONTRACTOR SHALL REPORT ANY DIFFERING CONDITIONS TO THE DESIGNER PRIOR TO COMMENCING WORK.
- STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH JOB SPECIFICATION AND HOUSE PLANS, MECHANICAL, ELECTRICAL, PLUMBING, AND SITE DRAWINGS. CONSULT THESE DRAWINGS FOR SLEEVES, DEPRESSIONS AND OTHER DETAILS NOT SHOWN ON STRUCTURAL DRAWINGS.
- ALL SPECIFIED FASTENERS MAY ONLY BE SUBSTITUTED IF APPROVED BY THE ENGINEER IN WRITING. THE INSTALLATION OF THE FASTENERS SHALL BE IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATIONS. SIMPSON FASTENERS SPECIFIED MAY BE SUBSTITUTED WITH THE SAME QUANTITY AND EQUIVALENT STRENGTH PRODUCT. ALL BOLTS, NUTS, WASHERS, STRAPS AND FASTENERS INCLUDING NAILS, SHALL BE HOT MOPED DIPPED GALVANIZED OR STAINLESS STEEL. CONTINUOUS ANCHORAGE SHALL BE PROVIDED BETWEEN ALL TRUSSES, WALL SECTIONS, BEAMS, POSTS AND FOOTINGS WITH USE OF STRAPS AND CONNECTORS AS SPECIFIED HEREIN.
- TREATED WOOD REQUIREMENTS:- ALL TREATED WOOD EXPOSED TO WEATHER SHALL BE PROTECTED, PRESSURE TREATED, OR NATURALLY RESISTANT TO DECAY. ALL WOOD TOUCHING MASONRY OR CONCRETE SHALL BE ISOLATED, OR PRESSURE TREATED.
- THE STRUCTURE IS DESIGNED TO BE SELF SUPPORTING AND STABLE AFTER THE BUILDING IS COMPLETE. IT IS THE CONTRACTOR'S SOLE RESPONSIBILITY TO DETERMINE ERECTION PROCEDURES AND SEQUENCES TO ENSURE SAFETY OF THE BUILDING AND ITS COMPONENTS DURING ERECTION. THIS INCLUDES THE NECESSARY SHORING, SHEETING, TEMPORARY BRACING, GUYS, OR TIE DOWNS.
- CEILING DRYWALL INSTALLED WITHIN THE HOUSE TO TRUSSES SPACED 24" O.C. SHALL BE 5/8" DRYWALL OR 1/2" SAG RESISTANT PER SEC. 702.3.5
- LANAI CEILINGS & COVERED ENTRY CEILINGS 1X4 STRIPPING @ 16" O.C. FASTENED WITH 2-8d NAILS TO EACH TRUSS. 5/8" EXTERIOR GYP. BOARD CEILING FASTENED WITH 8d NAILS OR 1-5/8" DRYWALL SCREWS @ 6" O.C. EDGE AND FIELD.

2

GENERAL ROOF ASSEMBLY


ROOF SHEATHING FBOR TABLE R903.2.2 SHALL BE 1/2" APA RATED SHEATHING, EXPOSURE 1, SPAN RATING 40/20 OR BETTER. INSTALL PANELS WITH LONG DIMENSION PLACED PERPENDICULAR TO TRUSSES. A 1/8" SPACE BETWEEN ADJACENT SHEETS SHALL BE MAINTAINED. INSTALL "T" CLIPS AT UNSUPPORTED PANEL EDGES. FOR FASTENING, SEE STRUCTURAL.

FLASHING

FLASHING SHALL BE ALUMINUM, ALUMINUM ZINC COATED STEEL 0.0179" THICK, 26 GAUGE AZ50 ALUM ZINC, OR GALVANIZED STEEL 0.0179" THICK, 26 GAUGE ZINC COATED G90. FLASHING SHALL BE INSTALLED IN ACCORDANCE WITH THE ZIP SYSTEM ROOF SHEATHING MANUFACTURERS PUBLISHED REQUIREMENTS. ALL FLASHING AND INSTALLATION SHALL CONFORM TO SECTION R905.2.8 (1 TO 5).

DRIP EDGE

DRIP EDGE SHALL BE PROVIDED AT ALL EAVES AND GABLES OF SHINGLES ROOFS, LAPPED A MINIMUM OF 3" @ JOINTS. THE OUTSIDE EDGE SHALL EXTEND A MINIMUM OF 1/2" BELOW SHEATHING AND THE INSIDE EDGE SHALL EXTEND BACK A MINIMUM OF 2". DRIP EDGE SHALL BE FASTENED AT NO MORE THAN 4" CENTERS. THERE SHALL BE A MINIMUM OF 4" WIDTH OF ROOF CEMENT INSTALLED OVER THE DRIP EDGE FLANGE.



PAN FLASHING PER R703.4

SCALE: N.T.S.

3

ASPHALT SHINGLE ROOF SPECS



SHINGLES

30# FELT SHALL BE INSTALLED UNDER ASPHALT SHINGLES. ALL ASPHALT SHINGLES SHALL HAVE SELF-SEALING STRIPS OR BE INTERLOCKING AND COMPLY WITH ASTM D 225 OR D 3452. FOR FASTENING, SEE STRUCTURAL. INSTALLATION SHALL COMPLY WITH MANUFACTURER'S REQUIREMENTS FOR INSTALLATION IN THE GIVEN FLORIDA WIND ZONE, AS DETERMINED BY ASTM D 3161.

4


CLAY AND CONCRETE ROOF TILE SPECS

INSTALL PEEL AND STICK UNDERLAYMENT APPROVED FOR SINGLE LAYER APPLICATION UNDER TILE ROOF. THE INSTALLATION OF CLAY AND CONCRETE TILE SHALL COMPLY WITH THE PROVISIONS OF R905.3 F.B.C. MARKING: EACH ROOF TILE SHALL HAVE A PERMANENT MANUFACTURER'S IDENTIFICATION MARK. APPLICATION SPECIFICATIONS: THE TILE MANUFACTURER'S WRITTEN APPLICATION SPECIFICATIONS SHALL BE AVAILABLE AND SHALL INCLUDED BUT NOT BE LIMITED TO THE FOLLOWING:
1. TILE PLACEMENT AND SPACING
2. ATTACHMENT SYSTEM NECESSARY TO COMPLY WITH CURRENT WIND CODE.
A. AMOUNT AND PLACEMENT OF MORTAR
B. AMOUNT AND PLACEMENT OF ADHESIVE
C. TYPE, NUMBER, SIZE AND LENGTH OF FASTENERS AND CLIPS.
3. UNDERLAYMENT
4. SLOPE REQUIREMENT.











MINIMUM EGRESS WINDOW DETAIL

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL FLORIDA BUILDING CODE 2020 - 7TH EDITION




LOT: 1/8	BLOCK: 4422
SUBDIVISION: SOUTH GULF COVE	
ADDRES: 15707 APPLEWHITE CIRCLE	
D.R.H. #: 579660066	

MODEL 1989	GCD JOB # 12522
DATE: 04/13/21	
DRAWN BY: CWL	
CHECKED BY: JWC	
REVISED:	
PLAN: SECTIONS	
SCALE: As indicated	
A-6	

TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REINFORCING	SHAPE
F1	CONT.	1'-4"	0'-8"	2-#5	
F2	CONT.	1'-8"	0'-10"	2-#5	
F3	CONT.	1'-0"	1'-8"	2-#5	
F4	CONT.	1'-4"	1'-8"	2-#5	
F5	CONT.	1'-4"	1'-0"	2-#5	
F6	CONT.	1'-4"	1'-0"	2-#5	
F6A	CONT.	0'-8"	0'-8"	1-#5	
TE	CONT.	0'-8"	0'-8"	1-#5	

USED	TYPE	LENGTH	WIDTH	DEPTH	BOTTOM REINF.		REMARKS
					LONG WAY	SHORT WAY	
<input checked="" type="checkbox"/>	(A)	2'-6"	2'-6"	1'-0"	3-#5	3-#5	-
<input checked="" type="checkbox"/>	(B)	3'-0"	3'-0"	1'-0"	4-#5	4-#5	-
<input checked="" type="checkbox"/>	(C)	3'-6"	3'-6"	1'-0"	4-#5	4-#5	-
<input checked="" type="checkbox"/>	(D)	4'-0"	4'-0"	1'-2"	5-#5	5-#5	-
<input checked="" type="checkbox"/>	(E)	5'-0"	5'-0"	1'-2"	6-#5	6-#5	-



SCALE: 1/4" = 1'-0"

SCALE: 1/4" = 1'-0"

PLAN NOTES:

1. TOP OF GROUND FLOOR SLAB DATUM ELEVATION 0'-0"
2. "F#" DENOTES CONTINUOUS WALL FOOTING TYPE PER SCHEDULE THIS SHEET.

3. PROVIDE #5 VERTICAL REINFORCING AT DOT LOCATIONS SHOWN ON PLAN FROM FOOTING TO BOND BEAM.
4. ALL DIMENSIONS ARE TO OUTSIDE FACE OF MASONRY WALLS. SOME SLAB EDGES MAY EXTEND BEYOND FACE OF WALL.
5. FOR DIMENSIONS OF ROUGH OPENINGS IN MASONRY WALLS, COORDINATE WITH WINDOW/DOOR SUPPLIER.
6. PROVIDE PRESSURE TREATED BUCKS AT WINDOWS/ DOORS PER DETAIL 7/S-3.

$$\overline{1/4'' = 1'-0''}$$

This item has been digitally signed by Raul Reyes on the date adjacent to the seal. Printed copies of this document are not considered signed and sealed and the signature must be validated on any electronic copies.

INSTALL -
METAIG AL
ALL
TRUSSES
TO 1450 I
UPLIFT. FO
HIGHER
UPLIFTS,
SEE NOTES
ON PLAN.

1. PROVIDE A STRAP FROM THE ABOVE LIFT AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE AND SUITABLE FOR THE GEOMETRY. EMBED STRAP ON CENTERLINE OF WALL.
2. CONNECTORS ARE SIMPSON STRUCTURAL CONNECTORS. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS. SUBSTITUTIONS MUST BE APPROVED IN WRITING BY THE ENGINEER OF RECORD.
3. WHERE EMBEDDED STRAPS ARE MISSING, OR MIS-LOCATED, INSTALL RETROFIT STRAP PER 105-3.

INSTALL AT ALL TRUSSES TO 840 lb UPLIFT. FOR HIGHER UPLIFTS, SEE NOTES ON PLAN.	TRUSS STRAPPING TO STUD/WALL/ WOOD BEAM		
	MAX TRUSS UPLIFT @ 24" OC (LBS)	CONNECTOR	FASTENER
➔ 850	(1) JMTS16 G TO 20	(14) 1 Oak L - 1/2"	
1550	(2) HTS16 G TO 20	(14) 1 Oak L - 1/2"	
2550	(3) HTS16 G TO 20	(24) 1 Oak L - 1/2"	
1125	(1) HTS20 TO 30	(24) 1 Oak L - 1/2"	
2250	(2) HTS20 TO 30	(24) 1 Oak L - 1/2"	
3375	(3) HTS20 TO 30	(24) 1 Oak L - 1/2"	
4500	(4) HTS20 TO 30	(24) 1 Oak L - 1/2"	

SIMPSON CATALOG C-C- 2019



AT SWING DOORS, USE 2" RECESS STYLE
LINTEL IF NEEDED FOR ROUGH OPENING.

LINTELS BEAR 4" MIN. EACH END


1. ROOF TRUSSES BEARING ELEVATION VARIES, SEE LEGEND.
2. ROOF FRAMING SHALL BE WOOD TRUSSES DESIGNED BY A DELEGATED TRUSS ENGINEER PER DESIGN CRITERIA ON SHEET S-3.
3. PROVIDE STRAPPING AT TRUSSES PER NOTES ON THIS SHEET.
4. FOR NAILING OF ROOF, SEE 1 AND 2 ON S-3.
5. 8x8-1B etc., DENOTES PRECAST LINTEL ABOVE DOOR/WINDOW OPENING PER SCHEDULE THIS SHEET.

AT TRUSS BEARING, PROVIDE 8x8 MASONRY BOND BEAM W/ # 5 CONTINUOUS, SEE DETAIL 11/5-3.

EMBED METAL AT -
ALL TRUSSES, EXCEPT
AS NOTED AT
GIRDERS

8X8 CONTINUOUS MASONRY
BOND BEAM AT TOP OF WALL
WITH (1) #5 BAR, PROVIDED
CORNER BARS PER 8/5-3

WHERE DRYWALL CEILING
APPLIED TO TRUSSES AT
24" O.C. USE 5/8" DRYWALL
OR 1/2" SAG RESISTANT
PER FBCR 702.3.5



— (+33.5, -36.3) WIND
PRESSURES PER ASCE7-16, 160
MPH EXPOSURE C, AND
CONVERTED TO ALLOWABLE
STRESS DESIGN PRESSURES
USING 0.6W LOAD FACTOR.
(Vasd 124 MPH, RISK CAT II,
ENCLOSED, $k_d=0.85$, $H=15'$)

GARAGE SHALL BE SEPARATED FROM THE
 RESIDENCE & ATTIC BY NOT LESS THAN 1/2"
 GYP/SUM BOARD APPLIED TO THE GARAGE SIDE,
 GARAGES BENEATH HABITABLE ROOMS SHALL BE
 SEPARATED WITH NOT LESS THAN 5/8" TYPE "X"
 GYP/SUM BOARD OR EQUIVALENT. WHERE THE
 SEPARATION IS A FLOOR-CEILING ASSEMBLY THE
 STRUCTURE SUPPORTING THE SEPARATION SHALL
 ALSO BE PROTECTED BY NOT LESS THAN 1/2"
 GYP/SUM BOARD OR EQUIVALENT.

1-HTT4 THIS SIDE OF
B2 W/ 5/8" Ø
ALLTHREAD, DRILL AND
EPOXY. 12" MIN. EMBED

1-METAL6
@BI

— #5 VERTICAL @ DOT
LOCATION (48" O.C. MAX)
IN GROUTED CELL W/ 7"
HOOK INTO BOND BEAM

SET BOTTOM OF 8F8-B1 LINTEL AT GARAGE
DOOR HEAD HEIGHT, ADD COURSING AS
NEEDED, TO TOP OF WALL @ 9'-4" W/ 8X8
BOND BEAM W/ (1) #5 GROUT SOLID.


$$1/4'' = 1'-0''$$

DESIGN IN ACCORDANCE WITH THE RESIDENTIAL
FLORIDA BUILDING CODE 2020 - 7TH EDITION


NAIL TYPE (SECTION R803.2.3.1) — FACIA BOARD
19/32 SHEATHING

2 1/2" x 0.131" RING SHANK OR 3" x 0.120" RING SHANK (PER ASTM F1667 RSR-03 & 04)

1 NAILING OF ROOF SHEATHING




4 STEMWALL DETAILS



BUCK FASTENING GARAGE DOOR


NOTE: THIS BUCK FASTENING DETAIL IS INTENDED FOR FLANGED WINDOW/DOOR PRODUCTS THAT FASTEN THRU THE FLANGE WITH WOOD SCREWS TO THE BUCK. FOR WINDOW/DOOR PRODUCTS THAT DO NOT HAVE A FLANGE AND FASTEN INSTEAD OUTWARD THRU THE FRAME, USE MASONRY SCREWS PER MFR. THAT ARE LONG ENOUGH TO PENETRATE 2-1/4" INTO THE MASONRY. IN THIS CASE, THE BUCK MATERIAL IS SIMPLY A SPACER AND MAY BE 1x4 OR 1x6 OR OMITTED ENTIRELY AND THE SPACER MAY BE TACKED IN PLACE WITH MASONRY NAILS OR PINS.



9 STEPPED BOND BEAM & REINFORCING

SHEATHING SCHEDULE	
EXTERIOR STUD WALL	FLOOR
7/16" ZIP SYSTEM WALL SHEATHING BY HUBER ENGINEERED WOODS LLC, NAILED W/ 8d COMMON WIRE @ 6" O.C. EDGE AND 6" O.C. FIELD. PROVIDE 2x4 BLOCKING AT ALL JOINTS. INSTALL SHEATHING AND SEAM TAPE IN STRICT ACCORDANCE WITH MFR. WRITTEN INSTRUCTIONS.	N/A
	EXTERIOR CEILING
ROOF – PER FBCR TABLE 803.2.2 19/32 CLASS A.P.A. RATED SHEATHING, EXPOSURE 1, SPAN RATING 40/20, FASTEN WITH RING SHANK NAILS PER DETAIL 1/S-3 (WHEN ZIP BRAND ROOF SHEATHING IS USED, H-CLIPS ARE <u>NOT</u> REQUIRED)	1) 1x4 STRIPPING @ 16"OC w/ 2-8d NAILS TO EACH TRUSS, 5/8" EXTERIOR GYPBOARD CEILING, FASTEN w/8d NAILS OR 1 5/8" DRYWALL SCREWS @ 6"OC EDGE & FIELD. 2) 3/8" BC PLYWOOD NAILED w/ 6d COMMON @ 6" OC EDGE & FIELD.
	SOFFIT
	ALUMINUM PERFORATED SOFFIT INSTALLED PER MANUFACTURER INSTRUCTIONS TO MEET WIND PRESSURES PER R704.


NOTE: EXTERIOR CEILINGS SPECIFIED ABOVE MEET THE DESIGN WIND PRESSURES PER R703.1.2



NOTES:

- 1) PROVIDE SAWCUTS TO CREATE APPROXIMATE 20' X 20' MAXIMUM SQUARES.
- 2) SAWCUT CONCRETE SLAB WITHIN 4 TO 12 HOURS OF CONCRETE PLACEMENT.

5 SLAB SAWCUT DETAIL



8 CORNER BAR DETAIL IN BOND BEAMS

RETROFIT STRAPS TO CONCRETE/MASONRY			
TRUSS UPLIFT (LBS) @ 24" OC		CONNECTOR	
TO 840	1-MTSM16 or 20	7-10dx1 1/2"	4-1/4"x2 1/4" TITEN
TO 1045	1-HTSM16 or 20	8-10dx1 1/2"	4-1/4"x2 1/4" TITEN
TO 2090	2-HTSM16 or 20	8-10dx1 1/2"	4-1/4"x2 1/4" TITEN
TO 4300	2-LGT2	16-16d,	7-1/4"x2 1/4" TITEN
TO 3480	HTT16	18-16d,	5/8" x ALLTHREAD, DRILL & EPOXY 10" EMBED w/ SIMPSON SET.
TO 10530	HGT-2/3	TWO 3/4" x ALLTHREAD, DRILL & EPOXY 12" EMBED WITH SIMPSON SET.	


NOTES:

- 1) WHERE EMBEDDED STRAP IS MISSING OR MIS-LOCATED, PROVIDE A STRAP FROM THE ABOVE LIST AT EACH ROOF TRUSS BEARING POINT, BASED ON THE TRUSS UPLIFT VALUES IN THE SIGNED AND SEALED TRUSS DESIGN PACKAGE.
- 2) CONNECTORS ARE SIMPSON STRONG TIE. ALL CONNECTORS SHALL BE INSTALLED IN STRICT ACCORDANCE WITH SIMPSON PRINTED INSTRUCTIONS.


10 RETROFIT UPLIFT CONNECTOR SCHEDULE

WINDOW/DOOR/SOFFIT DESIGN WIND PRESSURES			
WIND PRESSURES PER ASCE7-16, 160 MPH, EXPOSURE C, AND CONVERTED TO ALLOWABLE STRESS DESIGN PRESSURES USING 0.6W LOAD FACTOR. (V _{std} =124 MPH, RISK CAT II, ENCLOSED, k _d =0.85, γ =15', λ =1.21)			
TYPE	INTERIOR ZONE 4		END ZONE 5
SOFFIT	+33.5	-36.3	+33.5 -44.8
TYPICAL WINDOWS & DOORS	+33.5	-36.3	+33.5 -44.8
8' OR 9' GARAGE DOORS		+29.4	-33.3
16' OR 18' GARAGE DOORS		+28.2	-31.5

- 1) TABLE MAY BE USED FOR ANY SIZE WINDOW OR DOOR IN EACH TYPE.
2) USE "INTERIOR ZONE 4" PRESSURES UNLESS WINDOW OR DOOR IS LOCATED WITHIN THE "END ZONE 5" (SEE DIAGRAM BELOW), THEN USE THE HIGHER PRESSURES UNDER THE "END ZONE 5" COLUMN.
3) ALL GLASS / GLAZING SHALL BE IMPACT RATED OR USE IMPACT RATED SHUTTERS.
4) SUBMIT PRODUCT APPROVALS TO THE BUILDING DEPARTMENT AS REQUIRED BY THE LOCAL JURISDICTION.
5) MANUFACTURED SOFFIT PRODUCTS SHALL BE INSTALLED PER MFR ENGINEERING SPEC SHEETS.
- * ON IRREGULAR SHAPED BUILDINGS, THERE IS NO GUIDANCE IN THE CODE FOR HOW FAR A CORNER MUST PROTRUDE FROM THE MAIN BUILDING TO BE CONSIDERED "ZONE 5". WE HAVE CHOSEN >15'. THIS IS SUBJECT TO JUDGEMENT CALL BY THE AUTHORITY HAVING JURISDICTION.
-
- END ZONE 5 PRESSURES OCCUR AT "PRIMARY" OUTSIDE CORNERS OF BUILDING (BOLD LINES)
- INTERIOR ZONE 4 PRESSURES
- END ZONE WIDTH = 4'-0" MEASURED FROM FACE OF WALL (FIG R301.2(7))
- * >15'
- TYPICAL HOUSE PLAN
- IN ZONE 5, MANUFACTURED SOFFIT PRODUCTS MAY REQUIRE ADDITIONAL BATTENS OR FASTENING PER MFR ENGINEERING SPEC SHEETS TO MEET THE PRESSURE REQUIREMENTS.



3



6


STEP FOOTING

SCALE: NTS

FOOTING

CORNER BARS


SCALE: NTS



11 FULL HEIGHT WALL SECTION
SCALE: $\frac{3}{4}" = 1'-0"$

[illegible]

STRUCTURAL ENGINEERING:
STRUCTURAL
SYSTEMS
OF NORTH FLORIDA
1634 S.E. 47th STREET, SUITE #3
CAPE CORAL, FL 33904
(239) 549-4554
CA# 8829



BUILDER:

D·R·HORTON • RHI
NYSE


America's Builder

STRUCTURAL DETAILS
MODEL 1989 B
2 CAR
15707 APPLEWHITE CIRCLE
PORT CHARLOTTE, FLORIDA
LOT: 18 BLOCK: 4422 SUBDIVISION: SOUTH GULF C


DESIGN/DRAWN
DWB/GH
CHECKED
DWB
DATE
04/14/21
SCALE
VARIES
JOB NO.
DR12522
SHEET

S-3

SHEET 3 OF 4



1 OUTLOOKER DETAIL AT RAISED GABLE
SCALE: N.T.S.



2 FALSE KNEEWALL AT ENTRY
SCALE: 3/4" = 1'-0"

FOR SCOSTA TRUSSES, ELEVATION B, JOB # DR1989B, DATED: 02/10/21, REVISED: NONE

DESIGNED IN ACCORDANCE WITH FLORIDA BUILDING CODE 7th EDITION (2020) RESIDENTIAL

BUILDER:

A circular professional engineer license seal for the State of Florida. The outer ring contains the text "RAUL REYES" on the left and "PROFESSIONAL ENGINEER" on the right, separated by three stars. The inner circle contains the word "LICENSE" on the left and "STATE OF FLORIDA" on the right, also separated by three stars. In the center of the seal is the license number "No. 88925".

STRUCTURAL ENGINEERING:

**STRUCTURAL
SYSTEMS
OF NORTH FLORIDA**

1634 S.E. 47th STREET, SUITE #3
CAPE CORAL, FL 33904
(239) 549-4554
CA# 8829

STRUCTURAL DETAILS
MODEL 1989 B
2 CAR

15707 APPLEWHITE CIRCLE
PORT CHARLOTTE, FLORIDA
LOT: 18 BLOCK: 4422 SUBDIVISION: SOUTH GULF COVE

DESIGN/DRAWN
DWB/GH
CHECKED
DWB
DATE
04/14/21
SCALE
VARIES
JOB NO.
DR12522
SHEET

S-4

SHEET 4 OF 4

[illegible]