PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON PORTLAND CEMENT			
REPORT REFERENCE	DPL CPC 64		
CLIENT REFERENCE	DP01 CPC 05-26 52.5N		
SAMPLE	CEM I 52.5N		
SEAL NUMBER	B446019		
SAMPLE DATE	07-Oct-26		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	08-Oct-26		
DATE OF TESTS	08-Oct-26	to	05-Nov-26
DATE OF REPORT	05-Nov-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME			
INITIAL SETTING TIME	218	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	33.6	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	62.8	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	2.81	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	0.51	%	(BSEN 196-2:2013)
SULPHATE	3.17	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21