PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON PORTLAND CEMENT			
REPORT REFERENCE	DPL 42 3		
CLIENT REFERENCE	DP19 CPC 05-26 CEM111 A 40%GGBS 42.5N		
SAMPLE	CEM III/A 42.5N		
SEAL NUMBER	B446022		
SAMPLE DATE	07-Oct-26		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	08-Oct-26		
DATE OF TESTS	08-Oct-26	to	05-Nov-26
DATE OF REPORT	05-Nov-26		

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	217	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	20.0	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	58.3	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI (CORRECTED)	4.39	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	1.13	%	(BSEN 196-2:2013)
SULPHATE	2.61	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21