PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT			
REPORT REFERENCE	PC 22		
CLIENT REFERENCE	CPC/DPL/42/25-26 11/9/26		
SAMPLE	CEM111/A 42.5N		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	14-Sep-26		
DATE OF TESTS	15-Sep-26	to	13-Oct-26
DATE OF REPORT	22-Oct-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME		
INITIAL SETTING TIME	203 mins	> Or = 60 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).		
AT 2 DAYS	19.5 MPa	>Or = 10 Mpa
AT 28 DAYS	61.6 MPa	> Or = 42.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received		
INSOLUBLE RESIDUE	1.05 %	< Or = 5.0%
SULPHATE	2.61 %	< Or = 3.5%
LOI (CORRECTED)	3.30 %	< Or = 5.0%
END OF REPORT		

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21