PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT			
REPORT REFERENCE	PC 23		
CLIENT REFERENCE	CPC/DPL/42/26-26 16/9/26		
SAMPLE	CEM111/A 42.5N		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	17-Sep-26		
DATE OF TESTS	17-Sep-26	to	15-Oct-26
DATE OF REPORT	22-Oct-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME		
INITIAL SETTING TIME	196 mins	> Or = 60 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).		
AT 2 DAYS	20.9 MPa	>Or = 10 Mpa
AT 28 DAYS	60.2 MPa	> Or = 42.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received		
INSOLUBLE RESIDUE	1.06 %	< Or = 5.0%
SULPHATE	2.62 %	< Or = 3.5%
LOI (CORRECTED)	3.41 %	< Or = 5.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21