PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT		
REPORT REFERENCE	PC 25	
CLIENT REFERENCE	CPC/DPL/42/28-26 30/9/26	
SAMPLE	CEM111/A 42.5N	
SAND	GERMAN	
DATE OF RECEIPT OF SAMPLE	02-Oct-26	
DATE OF TESTS	05-Oct-26 to 02-Nov-26	
DATE OF REPORT	02-Nov-26	
ALL RESULTS RELATE ONLY TO SAMPLE TESTED		

INITIAL SETTING TIME		
INITIAL SETTING TIME	219 mins	> Or = 60 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).		
AT 2 DAYS	19.8 MPa	>Or = 10 Mpa
AT 28 DAYS	60.2 MPa	> Or = 42.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received		
INSOLUBLE RESIDUE	1.08 %	< Or = 5.0%
SULPHATE	2.69 %	< Or = 3.5%
LOI (CORRECTED)	3.25 %	< Or = 5.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21