PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT			
REPORT REFERENCE	PC 26		
CLIENT REFERENCE	CPC/DPL/42/30-26 16/10/26		
SAMPLE	CEM111/A 42.5N		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	19-Oct-26		
DATE OF TESTS	20-Oct-26	to	17-Nov-26
DATE OF REPORT	18-Nov-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME		
INITIAL SETTING TIME	196 mins	> Or = 60 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).		
AT 2 DAYS	20.0 MPa	>Or = 10 Mpa
AT 28 DAYS	56.5 MPa	> Or = 42.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received		
INSOLUBLE RESIDUE	0.84 %	< Or = 5.0%
SULPHATE	2.83 %	< Or = 3.5%
LOI (CORRECTED)	3.19 %	< Or = 5.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21