PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT			
REPORT REFERENCE	DPL 52 473		
CLIENT REFERENCE	CPC/DPL/52/37-26 16/9/26		
SAMPLE	CEM I 52.5N		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	17-Sep-26		
DATE OF TESTS	17-Sep-26	to	15-Oct-26
DATE OF REPORT	22-Oct-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME			
INITIAL SETTING TIME	201	mins	> Or = 45 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	37.6	MPa	>Or = 30 Mpa Mpa
AT 28 DAYS	65.0	MPa	> Or = 52.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received			
LOI	2.95	%	< Or = 5.0%
INSOLUBLE RESIDUE	0.66	%	< Or = 5.0%
SULPHATE	3.08	%	< Or = 4.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21