PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT	
REPORT REFERENCE	DPL 52 475
CLIENT REFERENCE	CPC/DPL/52/39-26 30/9/26
SAMPLE	CEM I 52.5N
SAND	GERMAN
DATE OF RECEIPT OF SAMPLE	02-Oct-26
DATE OF TESTS	05-Oct-26 to 02-Nov-26
DATE OF REPORT	02-Nov-26

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	220	mins	> Or = 45 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	35.0	MPa	>Or = 30 Mpa Mpa
AT 28 DAYS	63.8	MPa	> Or = 52.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received			
LOI	2.88	%	< Or = 5.0%
INSOLUBLE RESIDUE	0.67	%	< Or = 5.0%
SULPHATE	3.15	%	< Or = 4.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21