PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR PORTLAND CEMENT	
REPORT REFERENCE	DPL 52 476
CLIENT REFERENCE	CPC/DPL/52/41-26 16/10/26
SAMPLE	CEM I 52.5N
SAND	GERMAN
DATE OF RECEIPT OF SAMPLE	19-Oct-26
DATE OF TESTS	20-Oct-26 to 17-Nov-26
DATE OF REPORT	18-Nov-26

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	219	mins	> Or = 45 mins

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	34.9	MPa	>Or = 30 Mpa Mpa
AT 28 DAYS	60.1	MPa	> Or = 52.5

CHEMICAL COMPOSITION EN196-2013 :- by mass, as received			
LOI	3.18	%	< Or = 5.0%
INSOLUBLE RESIDUE	0.45	%	< Or = 5.0%
SULPHATE	3.11	%	< Or = 4.0%

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21