



ESTIMATE

A.D. Master Construction LLC. License #: ADMASMC771RR. Bond Account #: 466CF819962

A.D. Master Construction
United States

BILL TO
Moses Ike
Ike Moses

206-368-5440

Estimate Number: EST127
Estimate Date: September 19, 2025
Valid Until: October 19, 2025
Grand Total (USD): \$1,245.26

Items	Amount
-------	--------

Door Preparation and Installation	\$1,130.00
Removing the old door, remove old trim, molding, and door jambs. Install the Sill Pan. Place the Door Unit and Secure. Secure the Lockset Jamb. Install Hardware. Trim and Insulate: install the exterior trim, frame. Apply caulk around the entire outside of the door where the exterior trim meets the jamb and the wall. Caulk where the sill meets the jamb and slab and install wedge pads at the bottom of both sides of the frame. Ensure proper weatherproofing. Trim Inside and update adjusted baseboards. Adjusted Area: Prepare area adjusted to door, left, up, right. Update finishing. Paint adjusted area and stairs. Entry door delivery and rough materials are included.	

Subtotal:	\$1,130.00
NT 10.2%:	\$115.26
Grand Total (USD):	\$1,245.26