PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON PORTLAND CEMENT			
REPORT REFERENCE	DG 77		
CLIENT REFERENCE	DAC/01/ 05-06 CEM1 52.5N		
SAMPLE	CEM I 52.5R		
SEAL NUMBER	B445163		
SAMPLE DATE	11-Sep-26		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	11-Sep-26		
DATE OF TESTS	11-Sep-26	to	09-Oct-26
DATE OF REPORT	22-Oct-26		

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	227	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	32.9	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	64.3	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	2.85	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	0.48	%	(BSEN 196-2:2013)
SULPHATE	3.07	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes — Senior Technician **Date** 29.09.21