PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON CEMENT			
REPORT REFERENCE	DG 42 550		
CLIENT REFERENCE	CPC/DAC/269 30/9/26		
SAMPLE	CEM II A-L 42.5R		
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	05-Oct-26		
DATE OF TESTS	05-Oct-26	to	02-Nov-26
DATE OF REPORT	02-Nov-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME			
INITIAL SETTING TIME	194	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	30.9	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	57.2	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	n/a	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	n/a	%	(BSEN 196-2:2013)
SULPHATE	3.08	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes
Senior Technician