PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON CEMENT			
REPORT REFERENCE	DG 52 550		
CLIENT REFERENCE	CPC/DAC/256 NO DATE ON SAMPLE CERT		
SAMPLE	52.5N	MATAPORQUERA	
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	14-Aug-26		
DATE OF TESTS	17-Aug-26 to 14-Sep-26		
DATE OF REPORT	15-Sep-26		
ALL RESULTS RELATE ONLY TO SAMPLE TESTED			

INITIAL SETTING TIME			
INITIAL SETTING TIME	219	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	36.5	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	62.7	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	3.11	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	0.51	%	(BSEN 196-2:2013)
SULPHATE	3.17	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes
Senior Technician