PARKHOUSE ENTERPRISE LTD
Independent consultants & specialist materials suppliers

3 Dunstan Hill
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4FG

T: 01652 656931
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON CEMENT			
REPORT REFERENCE	DG 52 553		
CLIENT REFERENCE	CPC/DAC/262 4/9/26		
SAMPLE	52.5N	MATAPORQUERA	
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	08-Sep-26		
DATE OF TESTS	08-Sep-26	to	06-Oct-26
DATE OF REPORT	07-Oct-26		

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	207	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	33.3	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	65.4	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	2.46	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	0.58	%	(BSEN 196-2:2013)
SULPHATE	3.01	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes
Senior Technician