PARKHOUSE ENTERPRISES
Independent consultants & specialist materials suppliers

7 East Cross Street
Kirton in Lindsey
Gainsborough
Lincolnshire
DN21 4DT

T: 01652 640756
E: office@parkhouseent.co.uk

TEST REPORT PREPARED FOR DRAGON CEMENT			
REPORT REFERENCE	DG 52 557		
CLIENT REFERENCE	CPC/DAC/272 8/10/26		
SAMPLE	52.5N	MATAPORQUERA	
SAND	GERMAN		
DATE OF RECEIPT OF SAMPLE	14-Oct-26		
DATE OF TESTS	15-Oct-26	to	12-Nov-26
DATE OF REPORT	17-Nov-26		

ALL RESULTS RELATE ONLY TO SAMPLE TESTED

INITIAL SETTING TIME			
INITIAL SETTING TIME	206	mins	(BSEN 196-3:2016)

COMPRESSIVE STRENGTH: MORTAR PRISMS (BSEN 196-1:2016).			
AT 2 DAYS	33.6	MPa	(Mean of 6 results,none discarded)
AT 28 DAYS	60.6	MPa	(Mean of 6 results,none discarded)

CHEMICAL COMPOSITION :- by mass, as received			
LOI	2.89	%	(BSEN 196-2:2013)
INSOLUBLE RESIDUE	0.54	%	(BSEN 196-2:2013)
SULPHATE	3.00	%	(BSEN 196-2:2013)

END OF REPORT

SIGNED:.....

Certificate signed by: S.Sykes
Senior Technician