



# Metro Tunnel Cross Yarra Project



Cross Yarra Project contracted Aqua Prep to remove 120 cubic meters of concrete from a tunnel section. The CYP team chose this method to minimise severe vibrations that could impact nearby structures and workers.

Using an Aquajet Systems Aqua Cutter 710V robot, the team achieved a daily removal rate exceeding two cubic meters. The affected area measured 60 meters in length, 2 meters in height, and 1 meter in depth.



## Contact



Peter Bradford - 0468 388 751



[sales@aquaprep.com.au](mailto:sales@aquaprep.com.au)



[www.aquaprep.com.au](http://www.aquaprep.com.au)

22 Graham Daff Boulevard Braeside Victoria 3195  
ABN 21 155 116 037

