INSPIRED PEOPLE ▸ CREATIVE DESIGN ▸ TRANSFORMING COMMUNITIES

PROJECT DATA

PARCELS = 24-C.2-02-6, 24-C.2-02-5, 24-C.2-02-4
MAXIMUM LOT WIDTH = 335.05'
MINIMUM LOT WIDTH = 224.25'

TOTAL SITE AREA = 1.29 ACRES (56,236 S.F.)
DISTURBED AREA = 1.20 ACRES +/- (52,272 S.F.)
EXISTING ZONING = C-3
ZONING OF ALL ADJACENT PROPERTIES = C-3, RESIDENTIAL
EXISTING USE = COMMERCIAL, RESIDENTIAL
PROPOSED USE = FINANCIAL INSTITUTION
PROPOSED BUILDING FLOOR AREA = 4,083 +/- S.F. (7% OF SITE)
PROPOSED BUILDING HEIGHT = ONE STORY (45' MAXIMUM ALLOWED)
TOTAL EXISTING BUILDING FLOOR AREA = 6,650 S.F. (TO BE REMOVED)

PARKING REQUIRED
MINIMUM PARKING REQUIRED = 14 (1 PER 300 S.F. OF GROSS FLOOR AREA)
MAXIMUM PARKING ALLOWED = 20 (1 PER 200 S.F. OF GROSS FLOOR AREA)
ADA PARKING REQUIRED = 1 SPACE (1 VAN ACCESSIBLE)

PARKING PROVIDED
EXISTING PARKING = 0 SPACES
EXISTING ADA PARKING = 0 SPACES
PROPOSED ADA PARKING = 1 SPACES (1 VAN ACCESSIBLE)
PROPOSED STANDARD PARKING = 19 SPACES
TOTAL PROPOSED PARKING = 20 SPACES
QUEUE SPACES PROVIDED = 4 SPACES

EXISTING IMPERVIOUS = 20,638 S.F. (0.47 ACRES) (36% OF SITE)
PROPOSED IMPERVIOUS = 27,566 S.F. (0.63 ACRES) (49% OF SITE)
TOTAL INCREASE IN IMPERVIOUS = 6,928 S.F. (33%)

LANDSCAPE
PROPOSED VUA AREA = 22,508 S.F. (0.52 ACRES)
INTERIOR LANDSCAPE AREA REQUIRED = 1,125 S.F. (5 S.F. PER 100 S.F. OF VUA)
INTERIOR LANDSCAPE AREA PROVIDED = 1,135 S.F.

FREESTANDING SIGN
MAXIMUM AREA = 40 S.F.
MAXIMUM HEIGHT = 20 FT
PROPOSED AREA = 40 S.F.
PROPOSED HEIGHT = 6 FT

BUILDING SETBACKS
FRONT = 30'
SIDE = NONE
REAR = NONE

LANDSCAPE BUFFER
FRONT = 10'
SIDE = NONE
REAR = NONE

NOTES

1. ALL EXISTING STRUCTURES TO BE REMOVED.
2. EXISTING TREES AND VEGETATION TO BE REMOVED.

EROSION PREVENTION AND SEDIMENT CONTROL NOTES

1. THE APPROVED EROSION PREVENTION AND SEDIMENT CONTROL (EPSC) PLAN SHALL BE IMPLEMENTED PRIOR TO ANY LAND-DISTURBING ACTIVITY ON THE CONSTRUCTION SITE. ANY MODIFICATIONS TO THE APPROVED EPSC PLAN MUST BE REVIEWED AND APPROVED BY MSD'S PRIVATE DEVELOPMENT REVIEW OFFICE. EPSC BMP'S (BEST MANAGEMENT PRACTICES) SHALL BE INSTALLED PER THE PLAN AND MSD STANDARDS.
2. ACTIONS MUST BE TAKEN TO MINIMIZE THE TRACKING OF MUD AND SOIL FROM CONSTRUCTION AREAS ONTO PUBLIC ROADWAYS. SOIL TRACKED ONTO THE ROADWAY SHALL BE REMOVED DAILY.
3. SOIL STOCKPILES SHALL BE LOCATED AWAY FROM THE STREAMS, PONDS, SWALES, AND CATCH BASINS. STOCKPILES SHALL BE SEEDED, MULCHED, AND ADEQUATELY CONTAINED THROUGH THE USE OF SILT FENCE.
4. ALL STREAM CROSSINGS MUST UTILIZE LOW-WATER CROSSING STRUCTURES PER MSD STANDARD DRAWING ER-02-02.
5. SEDIMENT-LADEN GROUNDWATER ENCOUNTERED DURING TRENCHING, BORING OR OTHER ACTIVITIES SHALL BE PUMPED TO A SEDIMENT TRAPPING DEVICE PRIOR TO BEING DISCHARGED INTO A STREAM, POND, SWALE, OR CATCH BASIN.
6. WHERE CONSTRUCTION OR LAND DISTURBING ACTIVITY WILL OR HAS TEMPORARILY CEASED ON ANY PORTION OF A SITE, TEMPORARY SITE STABILIZATION MEASURES SHALL BE REQUIRED AS SOON AS PRACTICAL, BUT NO LATER THAN 14 DAYS AFTER THE ACTIVITY HAS CEASED.
7. MITIGATION MEASURES FOR DUST CONTROL SHALL BE IN PLACE DURING CONSTRUCTION TO PREVENT FUGITIVE EMISSIONS REACHING EXISTING ROADS AND NEIGHBORHOODS.

KYTC NOTES

1. THERE SHOULD BE NO COMMERCIAL SIGNS IN THE RIGHT OF WAY.
2. THERE SHOULD BE NO LANDSCAPING IN THE RIGHT OF WAY WITHOUT AN ENCROACHMENT PERMIT. TREE SPECIES PLANTED IN THE RIGHT OF WAY MUST CONFORM WITH DISTRICT 5 LIST OF APPROVED TREES.
3. SITE LIGHTING SHOULD NOT SHINE IN THE EYES OF DRIVERS. IF IT DOES, IT SHOULD BE RE-AIMED, SHIELDED OR TURNED OFF.
4. ALL DRAINAGE STRUCTURES WITHIN STATE RIGHT OF WAY SHALL BE STATE DESIGN. IF VERTICAL HEADWALLS ARE PRESENT, THEY SHALL BE REPLACED WITH SLOPED HEADWALLS PER CURRENT STANDARDS.
5. THERE SHALL BE NO PARKING NOR AND PORTION OF ANY PARKING LOT ON STATE RIGHT OF WAY.
6. ALL NEW AND EXISTING SIDEWALKS SHALL BE EITHER BROUGHT UP TO OR BUILT TO ADA CURRENT STANDARDS.

FLOODPLAIN NOTE

AS INDICATED ON FEMA MAP NUMBER 21185C0205E, THIS SITE IS LOCATED WITHIN ZONE X WHICH HAS BEEN DETERMINED TO BE OUTSIDE BOTH THE 100-YEAR AND 500-YEAR FLOODPLAINS. MAP DATED 9/22/2026.

MPW NOTE:

ALL ENTRANCES WILL BE MADE WITH A HARD AND DURABLE SURFACE.



VICINITY MAP
N.T.S

LEGEND:

- ⊕ BENCHMARK
- ○ 1/2" IRON PIN FOUND (UNLESS NOTED OTHERWISE)
- ● 1/2" IRON PIN SET (KOHLBRAND 3524)
- × CROSS NOTCH FOUND (UNLESS NOTED OTHERWISE)
- ◎ IRON PIPE FOUND (SIZE AS NOTED)
- Ⓢ SANITARY MANHOLE
- CO CLEANOUT
- □ CATCH BASIN
- DOWNSPOUT
- E ELECTRIC METER
- AC A/C UNIT
- LIGHT POLE
- UTILITY POLE
- GUY WIRE
- G GAS METER
- G GAS VALVE
- W WATER METER
- MB MAILBOX
- SB SOIL BORING
- SINGLE POST SIGN
- X FENCE LINE
- TREE LINE
- o HANDRAIL
- W WATER LINE
- G GAS LINE
- UE UNDERGROUND ELECTRIC
- OH OVERHEAD UTILITIES
- STORM SEWER
- SANITARY SEWER
- RAILROAD
- DECIDUOUS TREE
- BUSH
- ASPHALT
- CONCRETE
- GRAVEL
- LANDSCAPE
- RIP RAP



KY-146
CONTROL POINT IRON PIN N:303407.899 E:1291123.913
CONTROL POINT IRON PIN N:303135.330 E:1291224.879
BENCHMARK CROSS NOTCH N:303301.217 E:1291353.388 ELE:786.26'
24-C.2-02-7&8 AGREE STORES LLC D.B. 1236, PG. 229
ITEM #10 EX ENCROACHMENT AGREEMENT D.B. 1192, PG. 339
ITEM #9 15' SANITARY SEWER EASEMENT D.B. 550, PG. 482
VINSAND 3279
A.G. 0.04' NO CAP
A.G. 0.10' NO CAP
B.G. 0.75' NO CAP
S62°20'22"E 335.05'
N62°20'42"W 309.23'
N62°20'29"W 267.61'
N62°20'42"W 224.25'
N27°11'59"E 200.01'
0.370 ACRES
24-C.2-02-6 PARCEL 1 WOODFIELD HOLDINGS LLC D.B. 898, PG. 310 16,318.09 SQ. FT.
0.497 ACRES
24-C.2-02-5 PARCEL 2 COMBS KAREN S D.B. 1208, PG. 080 21,662.20 SQ. FT.
0.424 ACRES
24-C.2-02-4 PARCEL 3 COMBS KAREN S D.B. 1208, PG. 080 18,452.02 SQ. FT.
24-C.2-02-3 MINK TURF FARMS LLC D.B. 1321, PG. 374
EX. 1-STORY GARAGE 569± SQ.FT. HEIGHT = 11.1±
EX. 1-STORY GARAGE 1314± SQ.FT. HEIGHT = 17.2±
#6452 EX. 2-STORY STONE BUILDING
#6454 EX. 2-STORY VINYL BUILDING
EX. 1-STORY DILAPIDATED SHED 245± SQ.FT.
PROPOSED ONE-STORY FINANCIAL INSTITUTION BUILDING 4,083 +/- SF
10' VEHICULAR USE LANDSCAPE BUFFER AREA
30' FRONT YARD SETBACK
LOUISVILLE AND NASHVILLE RAILWAY R.R. CO. (C.S.X.)
15' SANITARY SEWER EASEMENT D.B. 535, PG. 369
REAL ESTATE SIGN
POSSIBLE DESTROYED STORM STRUCTURE
C1
C2
C3
R25'
R15'
R5'
62.3'
75.61'
12'
11'
13'
13'
10'
16'
15'
24'
18'
VAN
1
2
3
D.F.G 1985

CURVE TABLE					
CURVE	RADIUS	LENGTH	DELTA	DIRECTION	CHORD
C1	2540.82	56.06	1°15'51"	S54°37'02"W	56.06
C2	2540.82	85.41	1°55'34"	S56°12'45"W	85.41
C3	2540.82	13.96	0°18'53"	S57°19'58"W	13.96

KEY NOTES

- ⟨1⟩ SCREENED DUMPSTER PAD
- ⟨2⟩ ADA RAMP
- ⟨3⟩ MONUMENT SIGN

PROPOSED LEGEND:

- PARKING BLOCK
- ASPHALT PAVEMENT
- CONCRETE PAVEMENT
- CONCRETE WALK
- INTERIOR LANDSCAPE AREA
- DETECTABLE WARNING

Kentucky811

Know what's below. 811 before you dig.

NOTE:
UNDERGROUND UTILITIES ARE PLOTTED FROM A COMPILATION OF AVAILABLE RECORD INFORMATION AND SURFACE INDICATIONS OF UNDERGROUND STRUCTURES AND MAY NOT BE INCLUSIVE. PRECISE LOCATIONS AND THE EXISTENCE OR NON EXISTENCE OF UNDERGROUND UTILITIES CANNOT BE VERIFIED. PLEASE NOTIFY THE KENTUCKY UTILITY PROTECTION SERVICE AT 811 OR 1-800-382-5544 BEFORE ANY PERIOD OF EXCAVATION OR CONSTRUCTION ACTIVITY.



TYPICAL PARKING SPACE LAYOUT
NO SCALE



TYPICAL HANDICAP PARKING SPACE LAYOUT
NO SCALE

NOTE: CONCRETE WHEEL STOPS OR CURBING AT LEAST SIX (6) INCHES HIGH AND SIX (6) INCHES WIDE SHALL BE PROVIDED TO PREVENT VEHICLES FORM OVERHANGING ABUTTING SIDEWALKS, PROPERTIES OR PUBLIC RIGHTS-OF-WAY, TO PROTECT LANDSCAPED AREAS AND TO PROTECT ADJACENT PROPERTIES.

NOTE:
1. ONE ACCESSIBLE PARKING SPACE FOR EVERY SIX OR FRACTION THERE OF SHALL BE DESIGNATED AS "VAN ACCESSIBLE". LOCATION AS NOTED ON THE DRAWINGS.
2. ONE SIGN TO BE INSTALLED AT EACH ACCESSIBLE PARKING SPACE

THE KLEINGERS GROUP

CIVIL ENGINEERING
SURVEYING
LANDSCAPE ARCHITECTURE

www.kleingers.com

2211 River Road
Louisville, KY 40206
502.365.9950

H:\LOUISVILLE\2026\260327\000_DWG_Sheets\260327DEV000.dwg, 9/23/2026 3:00 PM, Mimi Honaker

CLIENT:

K4 ARCHITECTURE
555 GEST STREET
CINCINNATI, OH 45203

OWNER:

L&N FEDERAL CREDIT UNION
9115 SMYRNA PARKWAY
LOUISVILLE, KY 40229

SEAL:

NO.	DATE	DESCRIPTION
NO	DATE	DESCRIPTION

L&N FEDERAL CREDIT UNION - CRESTWOOD
6454 KY-146
CRESTWOOD, KY 40014

PROJECT NO: 260327.000
DATE: 2026-09-23
SCALE: 1"=20'
0 10 20 40

SHEET NAME:
SITE PLAN

SHEET NO.
DEV-01

INSPIRED PEOPLE ▸ CREATIVE DESIGN ▸ TRANSFORMING COMMUNITIES

PROJECT DATA

PARCELS = 24-C.2-02-6, 24-C.2-02-5, 24-C.2-02-4
MAXIMUM LOT WIDTH = 335.05'
MINIMUM LOT WIDTH = 224.25'

TOTAL SITE AREA = 1.29 ACRES (56,236 S.F.)
DISTURBED AREA = 1.20 ACRES +/- (52,272 S.F.)
EXISTING ZONING = C-3
ZONING OF ALL ADJACENT PROPERTIES = C-3, RESIDENTIAL
EXISTING USE = COMMERCIAL, RESIDENTIAL
PROPOSED USE = FINANCIAL INSTITUTION
PROPOSED BUILDING FLOOR AREA = 4,083 +/- S.F. (7% OF SITE)
PROPOSED BUILDING HEIGHT = ONE STORY (45' MAXIMUM ALLOWED)
TOTAL EXISTING BUILDING FLOOR AREA = 6,650 S.F. (TO BE REMOVED)

PARKING REQUIRED
MINIMUM PARKING REQUIRED = 14 (1 PER 300 S.F. OF GROSS FLOOR AREA)
MAXIMUM PARKING ALLOWED = 20 (1 PER 200 S.F. OF GROSS FLOOR AREA)
ADA PARKING REQUIRED = 1 SPACE (1 VAN ACCESSIBLE)

PARKING PROVIDED
EXISTING PARKING = 0 SPACES
EXISTING ADA PARKING = 0 SPACES
PROPOSED ADA PARKING = 1 SPACES (1 VAN ACCESSIBLE)
PROPOSED STANDARD PARKING = 19 SPACES
TOTAL PROPOSED PARKING = 20 SPACES
QUEUE SPACES PROVIDED = 4 SPACES

EXISTING IMPERVIOUS = 20,638 S.F. (0.47 ACRES) (36% OF SITE)
PROPOSED IMPERVIOUS = 27,566 S.F. (0.63 ACRES) (49% OF SITE)
TOTAL INCREASE IN IMPERVIOUS = 6,928 S.F. (33%)

LANDSCAPE
PROPOSED VUA AREA = 22,508 S.F. (0.52 ACRES)
INTERIOR LANDSCAPE AREA REQUIRED = 1,125 S.F. (5 S.F. PER 100 S.F. OF VUA)
INTERIOR LANDSCAPE AREA PROVIDED = 1,135 S.F.

FREESTANDING SIGN
MAXIMUM AREA = 40 S.F.
MAXIMUM HEIGHT = 20 FT
PROPOSED AREA = 40 S.F.
PROPOSED HEIGHT = 6 FT

BUILDING SETBACKS
FRONT = 30'
SIDE = NONE
REAR = NONE

LANDSCAPE BUFFER
FRONT = 10'
SIDE = NONE
REAR = NONE

UTILITY NOTES

1. ALL EXISTING UTILITY STRUCTURES TO BE REMOVED. UTILITY LINES TO BE REMOVED UP TO THEIR METER LOCATIONS.
2. EXISTING STORM CULVERTS TO BE REMOVED.

FIRE DEPARTMENT NOTES

1. THE SUBJECT PROPERTY IS COVERED BY THE SOUTH OLDHAM FIRE DEPARTMENT, STATION 1.
2. LOCAL FIRE AUTHORITY HAVING JURISDICTION (AHJ) CONTACT INFORMATION: CHIEF EDDIE TURNER, (502) 241-8992.
3. HYDRANTS: PRIOR TO THE COMBUSTIBLE PHASE OF CONSTRUCTION AN ADEQUATE WATER SUPPLY INCLUDING ACCESSIBLE HYDRANTS FOR FIREFIGHTING PURPOSES MUST BE MADE AVAILABLE, AND NO UTILITIES SHALL BE CONNECTED TO THE STRUCTURE UNTIL ADEQUATE SUPPLY IS PROVIDED (OLDHAM COUNTY CODE OF ORDINANCES 152.18).
4. GATES: NO GATES SHALL BE INSTALLED WHICH LIMIT OR RESTRICT ACCESS TO A RESIDENTIAL AREA, EXCEPT AS APPROVED BY THE AHJ OF THE REFERENCED FIRE DISTRICT.
5. EMERGENCY RESPONDER RADIO COVERAGE: EMERGENCY RADIO SYSTEMS ARE REQUIRED TO MEET MINIMUM SIGNAL STRENGTH CRITERIA, TO BE CONFIRMED VIA THIRD PARTY TESTING, PRIOR TO ISSUANCE OF THE CERTIFICATE OF OCCUPANCY IN SOME BUILDINGS.
6. REQUIREMENTS FOR SPECIFICATIONS OF FIRE DEPARTMENT CONNECTIONS (FDC), THREADS, SIZE, LOCATION, PLACEMENT OF THE KNOX BOX, OR FIRE SAFETY BUILDING MARKING SIGNAGE MUST BE OBTAINED FROM THE AHJ OF THE REFERENCED FIRE DISTRICT.
7. PERMITTED PROJECTS SHALL COMPLY WITH NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) 241, STANDARD FOR SAFEGUARDING CONSTRUCTION, ALTERATION, AND DEMOLITION OPERATIONS.

MSD NOTES

1. CONSTRUCTION PLANS AND DOCUMENTS SHALL COMPLY WITH LOUISVILLE AND JEFFERSON COUNTY METROPOLITAN SEWER DISTRICT DESIGN MANUAL AND STANDARD SPECIFICATIONS AND OTHER LOCAL, STATE, AND FEDERAL ORDINANCES.
2. SANITARY SEWER SERVICE SHALL BE PROVIDED BY EXISTING CONNECTION AND SUBJECT TO APPLICABLE FEES.
3. ALL DRAINAGE, EPSC, AND WATER QUALITY PRACTICES SHOWN ON THIS PLAN ARE FOR CONCEPTUAL PURPOSES ONLY. FINAL DESIGN OF THESE ELEMENTS WILL BE DETERMINED PRIOR TO CONSTRUCTION PLAN APPROVAL AND SHALL COMPLY WITH ALL MS4 AND MSD DESIGN MANUAL REQUIREMENTS.
4. SITE SERVICED BY MORRIS FORMAN WATER TREATMENT FACILITY.
5. NO INCREASE OF DRAINAGE ON TO THE ADJACENT PROPERTY OWNERS. POST DEVELOPED DRAINAGE PATTERNS SHALL REMAIN AS THEY ARE TODAY.
6. AN EPSC PLAN SHALL BE DEVELOPED AND APPROVED IN ACCORDANCE WITH MSD DESIGN MANUAL AND STANDARD SPECIFICATIONS PRIOR TO CONSTRUCTION PLAN APPROVAL.
7. THIS PROJECT IS SUBJECT TO MS4 WATER QUALITY REGULATIONS ONCE THE INCREMENTAL AREA OF DISTURBANCE SUMS EQUAL TO OR GREATER THAN 1 ACRE OF DISTURBANCE. PER THIS PRELIMINARY DEVELOPMENT PLAN, THE AREA OF DISTURBANCE IS 23,434.4 SF



PROPOSED ONE-STORY FINANCIAL INSTITUTION BUILDING 4,083 +/- SF
KY-146
CONTROL POINT IRON PIN N:303407.899 E:1291123.913
CONTROL POINT IRON PIN N:303135.330 E:1291224.879
BENCHMARK CROSS NOTCH N:303301.217 E:1291353.388 EL:786.26'
S62°20'22"E 335.05'
N62°20'42"W 309.23'
N62°20'29"W 267.81'
N62°20'42"W 224.25'
N27°11'59"E 200.01'
S57°29'29"W 72.46'
10' VEHICULAR USE LANDSCAPE BUFFER AREA
30' FRONT YARD SETBACK
0.370 ACRES
0.497 ACRES
0.424 ACRES
24-C.2-02-7&8 AGREE STORES LLC D.B. 1236, PG. 229
24-C.2-02-6 PARCEL 1 WOODFIELD HOLDINGS LLC D.B. 858, PG. 310
24-C.2-02-5 PARCEL 2 COMBS KAREN S D.B. 1206, PG. 080
24-C.2-02-4 PARCEL 3 COMBS KAREN S D.B. 1206, PG. 07
24-C.2-02-3 MINK TURF FARMS LLC D.B. 1321, PG. 374
LOUISVILLE AND NASHVILLE RAILWAY R.R. CO. (C.S.X.)
TRACT 1
TRACT 2

CURVE TABLE					
CURVE	RADIUS	LENGTH	DELTA	DIRECTION	CHORD
C1	2540.82	56.06	1°15'51"	S54°37'02"W	56.06
C2	2540.82	85.41	1°55'34"	S56°12'45"W	85.41
C3	2540.82	13.96	0°18'53"	S57°19'58"W	13.96

KEY NOTES

1. MSD DOUBLE CURB INLET
2. SLOPED AND FLARED HEADWALL
3. 48" DIA. PRECAST CONCRETE MANHOLE WITH HS-20 LOADED RADIAL FRAME AND GRATE
4. TRANSFORMER AND 8'X8' CONCRETE PAD
5. 6" SCH40 PVC SANITARY SEWER PIPE
6. FIRE HYDRANT

Kentucky 811

Know what's below. 811 before you dig.

NOTE :
UNDERGROUND UTILITIES ARE PLOTTED FROM A COMPILATION OF AVAILABLE RECORD INFORMATION AND SURFACE INDICATIONS OF UNDERGROUND STRUCTURES AND MAY NOT BE INCLUSIVE. PRECISE LOCATIONS AND THE EXISTENCE OR NON EXISTENCE OF UNDERGROUND UTILITIES CANNOT BE VERIFIED. PLEASE NOTIFY THE KENTUCKY UTILITY PROTECTION SERVICE AT 811 OR 1-800-382-5544 BEFORE ANY PERIOD OF EXCAVATION OR CONSTRUCTION ACTIVITY.



VICINITY MAP
N.T.S

LEGEND:

- ⌖ BENCHMARK
- ○ 1/2" IRON PIN FOUND (UNLESS NOTED OTHERWISE)
- ● 1/2" IRON PIN SET (KOHLBRAND 3524)
- × CROSS NOTCH FOUND (UNLESS NOTED OTHERWISE)
- ◎ IRON PIPE FOUND (SIZE AS NOTED)
- Ⓢ SANITARY MANHOLE
- CLEANOUT
- ☐ CATCH BASIN
- DOWNSPOUT
- ELECTRIC METER
- A/C UNIT
- LIGHT POLE
- UTILITY POLE
- GUY WIRE
- GAS METER
- GAS VALVE
- WATER METER
- MAILBOX
- SOIL BORING
- SINGLE POST SIGN
- —X— FENCE LINE
- TREE LINE
- —o— HANDRAIL
- —W— WATER LINE
- —G— GAS LINE
- —UE— UNDERGROUND ELECTRIC
- —OH— OVERHEAD UTILITIES
- STORM SEWER
- SANITARY SEWER
- RAILROAD
- DECIDUOUS TREE
- BUSH
- ▭ ASPHALT
- CONCRETE
- GRAVEL
- LANDSCAPE
- RIP RAP

PROPOSED LEGEND:

- PARKING BLOCK
- ▨ ASPHALT PAVEMENT
- ▨ CONCRETE PAVEMENT
- ▭ CONCRETE WALK
- ▨ INTERIOR LANDSCAPE AREA
- ▨ DETECTABLE WARNING

THE KLEINGERS GROUP
CIVIL ENGINEERING
SURVEYING
LANDSCAPE ARCHITECTURE
www.kleingers.com
2211 River Road
Louisville, KY 40206
502.365.9950

CLIENT:

K4 ARCHITECTURE
555 GEST STREET
CINCINNATI, OH 45203

OWNER:

L&N FEDERAL CREDIT UNION
9115 SMYRNA PARKWAY
LOUISVILLE, KY 40229

SEAL:

NO.	DATE	DESCRIPTION
NO	DATE	DESCRIPTION

L&N FEDERAL CREDIT UNION - CRESTWOOD
6454 KY-146
CRESTWOOD, KY 40014

PROJECT NO: **260327.000**
DATE: **2026-09-23**
SCALE: **1"=20'**
0 10 20 40

SHEET NAME:
UTILITY PLAN

SHEET NO.
DEV-02

H:\LOUISVILLE\2026\260327\000_DWG_Sheets\260327DEV000.dwg, 9/23/2026 3:00 PM, Mimi Honaker